

Estimate Abstract

OD/346/3301/116134/392157/00075349 : Const of CC road from Gilajodi Haripada Sahu house to Laxmidhar Sahu house
Block : Basta, Gram Panchayat : Raghunathpur
Created By:PRAKASH CHANDRA NAIK

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0101a (Earthwork in ordinary soil within 50m, initial lead and 1.5m, initial lift) : Earth work in ordinary soil within 50m, initial lead and 1.5m, initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per direction of the Engineer-in-charge.			
	7.645536	Cubic Meter	149.3184	1141.6192026624
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	19.7817200448	Cubic Meter	1367.139232	27044.365549687
3	Concrete : AR0303a (Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	29.0583037248	Cubic Meter	6758.34745726	196386.11309079
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.			
	18.1006082624	Cubic Meter	8351.85337962	151173.6262895
5	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	57.0796032	Square Meter	216.23489289764	12342.601884592
Total Amount (A) : 388088.32601724				

Additional Components			
#	Item Name	Remark	Amount (in Rs.)

1	Provision for Contingency @ Rs.4000	-	4000
2	Display Citizen Board @ Rs.5000	-	5000
3	Any Other Lumpsum @ Rs.2911.67	Vibrator	2911.67
Additional Components Amount (F) : 11911.67			

Grand Total Amount (A + F) : 399999.99601724			
---	--	--	--

PRAKASH CHANDRA NAIK
JE
Basta Block

BIKRAM KUMAR JENA
AEE
Basta Block

Mihir Ranjan Behera
BDO
Basta Block