

Estimate Abstract

**OD/365/3489/120081/389634/00102185 : Const of CC Drain from Debendra Sethi house to Khaskala Naik house
at Majhigaon village under Bangriposi GP
Block : Bangriposi, Gram Panchayat : Bangriposi
Created By:Srihari Santra**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	52.65	Cubic Meter	240.77592	12676.852188
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	8.1	Cubic Meter	1038.192332	8409.3578892
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	29.97	Cubic Meter	6057.4845243	181542.81119327
4	Plastering : AR1027 (6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside)) : 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.			
	145.8	Square Meter	194.081670094	28297.107499705
5	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	145.8	Square Meter	216.23489289764	31527.047384476
6	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	4.05	Cubic Meter	7467.9174871	30245.065822755

Total Amount (A) : 292698.24197741

Additional Components

#	Item Name	Remark	Amount (in Rs.)
1	Display Citizen Board @ Rs.4301	-	4301
2	Provision for Contingency @ Rs.3000	-	3000

Additional Components Amount (F) : 7301

Grand Total Amount (A + F) : 299999.24197741

Srihari Santra
JE
Bangriposi Block

Suvendu Kumar Naik
AEE
Bangriposi Block

Paramananda Khandei
BDO
Bangriposi Block