

Estimate Abstract

**OD/350/3342/117076/399783/00108797 : Improvement of CC road at kulagaonisalo village ward no1 2 3
Block : Nischinta Koili, Gram Panchayat : Asueresswar
Created By:Pradeep Kumar Senapati**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	4.185	Cubic Meter	240.77592	1007.6472252
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	13.02	Cubic Meter	1086.157232	14141.76716064
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	20.6925	Cubic Meter	6090.15944436	126020.62430242
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaicaion and direction of Engineer-in charge.			
	18.6	Cubic Meter	7559.06192932	140598.55188535
5	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	43.4	Square Meter	216.39264180804	9391.4406544689
Total Amount (A) : 291160.03122808				

Additional Components			
#	Item Name	Remark	Amount (in Rs.)

1	Provision for Contingency @ Rs.3000	-	3000
2	Display Citizen Board @ Rs.5000	-	5000
3	Any Other Lumpsum @ Rs.839.85	EXPANTION BOARD	839.85
Additional Components Amount (F) : 8839.85			

Grand Total Amount (A + F) : 299999.88122808		
---	--	--

Pradeep Kumar Senapati
JE
Nischinta Koili Block

Nalinikanta Mohapatra
AEE
Nischinta Koili Block

Dibyendu Kumar Das
BDO
Nischinta Koili Block