

**Estimate Abstract**

**OD/369/3541/120980/409605/00075811 : CONST. OF KOTAKANA COMMUNITY CENTER**  
**Block : Kanas, Gram Panchayat : Gadasahi**  
**Created By:UDAYABHANU MOHANTY**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Plastering : AR1004 (12mm thick cement plaster (1:6) over Brick work in inside) :</b> 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.			
	137.6725	Square Meter	174.9921807692	24091.611006948
2	<b>Plastering : AR1014 (16mm thick cement Plaster in CM (1:6) over brick work in inside.) :</b> 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.			
	183.77	Square Meter	250.272544182	45992.585444326
3	<b>Other Building Items. : AR1901B (Vitrified Tile 600mmx600mm Plain Ivory) :</b> Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)			
	71.15	Square Meter	1013.4975755206	72110.352498291
4	<b>Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) :</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	19.422	Cubic Meter	5879.98299946	114201.02981551
5	<b>Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) :</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	6.786	Cubic Meter	7358.26905102	49933.213780222
6	<b>Flooring : AR0817aa (Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3)) :</b> Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.			

13.4	Square Meter	1532.189611776	20531.340797798
7	<b>Painting : AR0901d (Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface)) :</b> Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.		
	321.44	Square Meter	71.83753306751
8	<b>Painting : AR0918ca (Finishing wall two coats with weather coat with one coat oilbound Primer) :</b> Finishing wall surface two coats with weather coat with one coat oilbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)		
	137.67	Square Meter	156.86604451751
9	<b>Painting : AR0922 (Finishing wall two coats with distemper of approved shades on new work (Inside)) :</b> Finishing wall two coats with distemper of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)		
	183.77	Square Meter	78.8505283
10	<b>Painting : AR0903b (Painting two coats of enamel paint with a coat of red oxide primer over iron surface) :</b> Painting two coats of enamel paint with a coat of red oxide primer over iron surface including all costs of labour, Paint, Primer, brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.		
	17	Square Meter	230.35420628603
<b>Total Amount (A) : 389953.7214136</b>			

Additional Components			
#	Item Name	Remark	Amount (in Rs.)
1	Provision for EI Work @ Rs.26896	-	26896
2	Provision for Contingency @ Rs.4500	-	4500
3	Display Citizen Board @ Rs.5000	-	5000
4	Any Other Lumpsum @ Rs.23650	Supplying, fitting & fixing of M.S Door & Window	23650
<b>Additional Components Amount (F) : 60046</b>			

**Grand Total Amount (A + F) : 449999.7214136**

**UDAYABHANU MOHANTY**  
**JE**  
**Kanas Block**

**SASWAT KUMAR SENAPATI**  
**AEE**  
**Kanas Block**

**SOUMYA RANJAN SWAIN**  
**BDO**  
**Kanas Block**