

Estimate Abstract

**OD/350/3342/117095/399740/00111932 : Improvement of CC road from Krushna Sahu House to Ratan Das
Block : Nischinta Koili, Gram Panchayat : Kenduapatna
Created By:Mama Behera**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	4.88	Cubic Meter	240.77592	1174.9864896
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	18.3	Cubic Meter	1086.157232	19876.6773456
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	20.74	Cubic Meter	6090.15944436	126309.90687603
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaicaion and direction of Engineer-in charge.			
	18.3	Cubic Meter	7559.06192932	138330.83330656
5	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	24.4	Square Meter	216.23489289764	5276.1313867024
				Total Amount (A) : 290968.53540448

Additional Components			
#	Item Name	Remark	Amount (in Rs.)

1	Provision for Contingency @ Rs.3000	-	3000
2	Display Citizen Board @ Rs.5000	-	5000
3	Any Other Lumpsum @ Rs.1031	Vibrator	1031
4	Provision for survey investigation and quality control @ Rs.0.45	-	0.45
Additional Components Amount (F) :			9031.45
Grand Total Amount (A + F) :			299999.98540448

Mama Behera
JE
Nischinta Koili Block

Nalinikanta Mohapatra
AEE
Nischinta Koili Block

Dibyendu Kumar Das
BDO
Nischinta Koili Block