

Estimate Abstract

**OD/368/3535/120856/422190/00107211 : Construction of Multipurpose cultural shed at Belarani Play ground
near Panchayat Office Chatiaguda
Block : Sinapali, Gram Panchayat : Chatiaguda
Created By:AKSHYA KUMAR MOHAPATRA**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	28.1952	Cubic Meter	240.77592	6788.725219584
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	56.1408	Cubic Meter	459.856232	25816.696749466
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	11.5218	Cubic Meter	5097.82244354	58736.090629979
4	Masonry Brick Work : AR0603c (Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth) : Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.			
	13.1922	Cubic Meter	4912.220958272	64803.001325716
5	R.C.C. Work : AR0404Aa (Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)			
	4.7925	Cubic Meter	5614.6266979723	26908.098450032
6	R.C.C. Work : AR0404Ab (Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Plinth band)			

2.244325	Cubic Meter	6371.448823114	14299.920452376
7	R.C.C. Work : AR0409 (Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.		
	7.1	Quintal	8024.542617
8	Plastering : AR1004 (12mm thick cement plaster (1:6) over Brick work in inside) : 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.		
	37.26	Square Meter	164.8828202508
9	Flooring : AR0802i (2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG crusher broken chips) : 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG crusher broken chips including punning incl. cost, conveyance & royalty of materials as per direction of Engineer-in-charge.		
	93.375	Square Meter	354.0999572508
10	Painting : AR0917 (Finishing wall with one coat water proofing cement paint of approved shade in the inner surface of old work to give an even shade (Inside).) : Finishing wall with one coat water proofing cement paint of approved shade in the inner surface of old work to give an even shade including all costs of labour, Paint and Brushes required for the work, etc. complete and as per direction of Engineer-in-charge. (Inside)		
	18.18	Square Meter	27.5981756842
Total Amount (A) : 294036.13763263			

Additional Components			
#	Item Name	Remark	Amount (in Rs.)
1	Provision for Contingency @ 1%	-	2940.3613763263
2	Display Citizen Board @ Rs.3000	-	3000
Additional Components Amount (F) : 5940.3613763263			

Grand Total Amount (A + F) : 299976.49900896			
---	--	--	--

AKSHYA KUMAR MOHAPATRA
JE
Sinapali Block

Pradosh Kumar Behera
AEE
Sinapali Block

KARMI ORAM
BDO
Sinapali Block