

Estimate Abstract

**OD/350/3339/117006/399474/00112621 : Construction OF CC ROAD FROM RAMESH DAS HOUSE TO ASHOK
SETHI HOOUSE WARD NO13
Block : Mahanga, Gram Panchayat : Madhupur
Created By:JAGANNATH PRASADA BARIK**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	5.4675	Cubic Meter	240.77592	1316.4423426
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	17.31375	Cubic Meter	793.620832	13740.55268004
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	23.085	Cubic Meter	5954.66880286	137463.52931402
4	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaicaion and direction of Engineer-in charge.			
	18.225	Cubic Meter	7438.54302282	135567.44659089
5	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	24.3	Square Meter	216.23489289764	5254.5078974127
Total Amount (A) : 293342.47882497				

Additional Components			
#	Item Name	Remark	Amount (in Rs.)

1	Provision for Contingency @ 1%	-	2933.4247882497
2	Display Citizen Board @ Rs.3424	-	3424
3	Any Other Lumpsum @ Rs.300	-	300
Additional Components Amount (F) : 6657.4247882497			

Grand Total Amount (A + F) : 299999.90361322			
---	--	--	--

JAGANNATH PRASADA BARIK
JE
Mahanga Block

SANDIP KUMAR DAS
AEE
Mahanga Block

SUBHASIS PALATA
BDO
Mahanga Block