

Estimate Abstract

**OD/359/3424/118909/417370/00108419 : CONST OF APPROACH ROAD FROM LARIBADI TO KUDIGUNJA
Block : Daringibadi, Gram Panchayat : Simanbadi
Created By:TUSHAR RANJAN SETHI**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	11.358	Cubic Meter	240.77592	2734.73289936
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	4.63455	Cubic Meter	645.049832	2989.5156988956
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	11.3733	Cubic Meter	5782.38283924	65764.774745528
4	R.C.C. Work : AR0404Ag (Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Roof slab, landing, balcony, sun shade)			
	9.276575	Cubic Meter	13277.36759413	123168.49628952
5	R.C.C. Work : AR0409 (Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.			
	9.6985	Quintal	9566.7779235	92783.395691065
6	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	38.724	Square Meter	216.70813962884	8391.8059989872

Total Amount (A) : 295832.72132335

Additional Components

#	Item Name	Remark	Amount (in Rs.)
1	Provision for Contingency @ Rs.3000	-	3000
2	Display Citizen Board @ Rs.1167	-	1167

Additional Components Amount (F) : 4167

Grand Total Amount (A + F) : 299999.72132335

TUSHAR RANJAN SETHI
JE
Daringibadi Block

SANJAYA KUMAR RATH
AEE
Daringibadi Block

PRITI RANJAN RATH
BDO
Daringibadi Block