

**Estimate Abstract**

**OD/350/3339/116989/399426/00106425 : Construction of CC road from RD road to Harijan Sahi  
Block : Mahanga, Gram Panchayat : Basudevpur  
Created By:JAGANNATH PRASADA BARIK**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift) :</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	5.4675	Cubic Meter	240.77592	1316.4423426
2	<b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	17.31375	Cubic Meter	793.620832	13740.55268004
3	<b>Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) :</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	21.87	Cubic Meter	5940.91861236	129927.89005231
4	<b>R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) :</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	24.3	Square Meter	216.23489289764	5254.5078974127
5	<b>Concrete : AR0307 (First floor) :</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	18.225	Cubic Meter	7799.01368932	142137.02448786
				<b>Total Amount (A) : 292376.41746022</b>

<b>Additional Components</b>			
#	Item Name	Remark	Amount (in Rs.)
1	Provision for Contingency @ 1%	-	2923.7641746022

2	Display Citizen Board @ Rs.4499	-	4499
3	Any Other Lumpsum @ Rs.200	-	200
<b>Additional Components Amount (F) : 7622.7641746022</b>			

<b>Grand Total Amount (A + F) : 299999.18163483</b>			
---	--	--	--

**JAGANNATH PRASADA BARIK**  
**JE**  
Mahanga Block

**SANDIP KUMAR DAS**  
**AEE**  
Mahanga Block

**Tilottama Prusty**  
**BDO**  
Mahanga Block