

Estimate Abstract

**OD/359/3424/118903/417366/00065744 : Const. of Culvert at Tala Adivasi, sahi at Kirikuti
Block : Daringibadi, Gram Panchayat : Kirikuti
Created By:TUSHAR RANJAN SETHI**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	19.76177	Cubic Meter	240.77592	4758.1583525784
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	2.46659	Cubic Meter	579.298832	1428.8927060229
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	18.98766	Cubic Meter	5711.32077444	108444.617016
4	R.C.C. Work : AR0404Ag (Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips) : Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Roof slab, landing, balcony, sun shade)			
	3.2424	Cubic Meter	13099.918409841	42475.175452068
5	R.C.C. Work : AR0409 (Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position) : Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.			
	3.24	Quintal	9552.907644	30951.42076656
6	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	48.045	Square Meter	216.55039071844	10404.163522067

Total Amount (A) : 198462.4278153

Additional Components

#	Item Name	Remark	Amount (in Rs.)
1	Provision for Contingency @ Rs.2020	-	2020
2	Display Citizen Board @ Rs.1555	-	1555

Additional Components Amount (F) : 3575

Grand Total Amount (A + F) : 202037.4278153

TUSHAR RANJAN SETHI
JE
Daringibadi Block

SANJAYA KUMAR RATH
AEE
Daringibadi Block

PRITI RANJAN RATH
BDO
Daringibadi Block