

Estimate Abstract

**OD/346/3298/116056/394021/00063609 : Impvt. & Const. of cc road from Laxmidhar mangal house to Baishnda mangal house at barhampur
Block : Bahanaga, Gram Panchayat : Kharasahapur
Created By:PRASANTA GHADAI**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift) : Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	10.204242048	Cubic Meter	240.77592	2456.9357670099
2	Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) : Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	7.10943101568	Cubic Meter	1540.455232	10951.760204647
3	Concrete : AR0303 (Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal) : Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	9.49993527168	Cubic Meter	6367.64713726	60492.235636868
4	R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) : Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	25.7527116	Square Meter	216.23489289764	5568.6348346498
5	Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) : Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaicaion and direction of Engineer-in charge.			
	7.84941696	Cubic Meter	7796.59981962	61198.762854458
Total Amount (A) : 140668.32929763				

Additional Components			
#	Item Name	Remark	Amount (in Rs.)

1	Provision for Contingency @ Rs.1437	-	1437
2	Display Citizen Board @ Rs.1000	-	1000
Additional Components Amount (F) : 2437			

Grand Total Amount (A + F) : 143105.32929763			
---	--	--	--

PRASANTA GHADAI
JE
Bahanaga Block

Bibhuti Bhusan Nayak
AEE
Bahanaga Block

Subhashree Tudu
BDO
Bahanaga Block