

**Estimate Abstract**

**OD/364/3481/119954/430543/00126256 : CONST OF CC DRAIN AT KANDHAATALGUDA  
Block : Khairaput, Gram Panchayat : Khairaput  
Created By:SAMIR DAS**

Sl No	Quantity	Unit	Rate in (Rs.)	Amount (Rs.)
1	<b>Earth Work : AR0102aa (Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift) :</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge			
	119.61	Cubic Meter	245.98752	29422.5672672
2	<b>Earth Work : AR0115 (Filling foundation and plinth with sand well watered and rammed) :</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.			
	13.29	Cubic Meter	651.792592	8662.32354768
3	<b>R.C.C. Work : AR0410c (R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc) :</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc			
	398.7	Square Meter	217.24489289764	86615.538798289
4	<b>Concrete : AR0303a (Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal) :</b> Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.			
	86.385	Cubic Meter	5293.6147674	457288.91168185
5	<b>Concrete : AR0307 (Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum) :</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.			
	3.3225	Cubic Meter	7385.9174758	24539.710813345
6	<b>Plastering : AR1026 (6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces (inside)) :</b> 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.			
	199.35	Square Meter	160.765908266	32048.683812827
<b>Total Amount (A) :</b>				<b>638577.73592119</b>

**Additional Components**

#	Item Name	Remark	Amount (in Rs.)
1	Provision for Contingency @ 1%	-	6385.7773592119
2	Display Citizen Board @ Rs.5036	-	5036
<b>Additional Components Amount (F) : 11421.777359212</b>			

**Grand Total Amount (A + F) : 649999.5132804**

**SAMIR DAS**  
JE  
Khairaput Block

**DUSHMANT KUMAR BEHERA**  
AEE  
Khairaput Block

**ARPITA MOHANTY**  
BDO  
Khairaput Block