

Analysis

OD/366/3517/120490/427816/00013548 : Const.of CC Road at Dumarmunda Dharani sahi
Block : Nabarangpur, Panchayat : Basini
Created By:Sunil Khora

Item 1
Earth Work (AR0102aa): Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge
Sub-Item of Work Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	25.8	Per day	452	11661.6	0
LR001 : Male mulia	25.8	Per day	452	11661.6	0
Total Amount (a+b+c)				23323.2	
Total GST (a)					0
LABOUR CESS @ 1% (+)					233.232
Grand Total					23556.432
Say For Unit 1 (Grand Total/100)					235.56432

Item 2
Earth Work (AR0115): Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work Filling foundation and plinth with sand well watered and rammed

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	71.94	7194	0
LR002 : Female mulia	12.36	Per day	452	5586.72	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	341.11	34111	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	40.25	4025	0

Total Amount (a+b+c)	50916.72				
Total GST (a)	0				
LABOUR CESS @ 1% (+)	509.1672				
Grand Total	51425.8872				
Say For Unit 1 (Grand Total/100)	514.258872				

Item 3

Concrete (AR0303): Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR025 : Mason	0.18	Per day	552	99.36	0
LR002 : Female mulia	1.4	Per day	452	632.8	0
LR001 : Male mulia	2.5	Per day	452	1130	0
BRM340 : Cement	2.29	1 Qntl.	521.88	1195.1052	334.629456
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	76.13	36.5424	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	995.25	955.44	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	30.732	70.37628	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	341.11	163.7328	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	341.11	327.4656	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
-------------------	-----------------	-------------	-------------	---------------	------------

BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	40.25	19.32	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	149.5	143.52	0

Total Amount (a+b+c)	4773.66228
Total GST (a)	334.629456
LABOUR CESS @ 1% (+)	51.08291736
Grand Total	5159.37465336
Say For Unit 1 (Grand Total/1)	5159.37465336

Item 4

R.C.C. Work (AR0410c): Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc

Sub-Item of Work

R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	58374.79	1558.606893	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	1.26	1Mtr.	30.81	38.8206	0
LR008 : Sangi mulia	0.5	Per day	502	251	0
LR027 : Carpenter	0.5	Per day	552	276	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	245.856	6.5643552	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	245.856	1.50955584	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	0	0	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	0	0	0

Total Amount (a+b+c)	2132.50140404
-----------------------------	---------------

Total GST (a)	0
LABOUR CESS @ 1% (+)	21.3250140404
Grand Total	2153.8264180804
Say For Unit 1 (Grand Total/10)	215.38264180804

Item 5

Concrete (AR0307): Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.4	Per day	452	632.8	0
LR001 : Male mulia	3.2	Per day	452	1446.4	0
LR025 : Mason	0.68	Per day	552	375.36	0
BRM340 : Cement	3.23	1 Qntl.	521.88	1685.6724	471.988272
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	76.13	34.2585	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	1396.62	1256.958	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	30.732	99.26436	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	341.11	153.4995	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	341.11	306.999	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
------------	----------	------	------	--------	-----

BRM340 : Cement	3.23	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	40.25	18.1125	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	149.5	134.55	0

Total Amount (a+b+c)	6143.87426
Total GST (a)	471.988272
LABOUR CESS @ 1% (+)	66.15862532
Grand Total	6682.02115732
Say For Unit 1 (Grand Total/1)	6682.02115732

ARABINDA BEHERA
JE
Nabarangpur Block

SURYA NARAYAN BEHERA
AEE
Nabarangpur Block

Sunil Khora
BDO
Nabarangpur Block