

Analysis

**OD/365/3490/120098/389168/00014276 : CONSTRUCTION OF BOUNDARY WALL AT
BANKISOLE UP SCHOOL UNDER BANKISOLE G.P
Block : Baripada, Panchayat : Bankisole
Created By:AISHWARYA BHUYAN**

Item 1

Earth Work (AR0102a): Earth work in hard soil or gravelly soil within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge

Sub-Item of Work

Earth work in hard soil or gravelly soil within 50m. Initial lead and 1.5m initial lift

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	21.5	Per day	452	9718	0
LR001 : Male mulia	21.5	Per day	452	9718	0

Total Amount (a+b+c)

19436

Total GST (a)

0

LABOUR CESS @ 1% (+)

194.36

Grand Total

19630.36

Say For Unit 1 (Grand Total/100)

196.3036

Item 2

Earth Work (AR0115): Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work

Filling foundation and plinth with sand well watered and rammed

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	60.43	6043	0
LR002 : Female mulia	12.36	Per day	452	5586.72	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	497.35	49735	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	602.25	60225	0

Total Amount (a+b+c)	121589.72				
Total GST (a)	0				
LABOUR CESS @ 1% (+)	1215.8972				
Grand Total	122805.6172				
Say For Unit 1 (Grand Total/100)	1228.056172				

Item 3

Concrete (AR0303): Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR025 : Mason	0.18	Per day	552	99.36	0
LR002 : Female mulia	1.4	Per day	452	632.8	0
LR001 : Male mulia	2.5	Per day	452	1130	0
BRM340 : Cement	2.29	1 Qntl.	428.91	982.2039	275.017092
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	66.85	32.088	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	995.25	955.44	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	30.732	70.37628	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	497.35	238.728	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	653.59	627.4464	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
-------------------	-----------------	-------------	-------------	---------------	------------

BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	602.25	289.08	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	551.5	529.44	0

Total Amount (a+b+c)	5586.96258
Total GST (a)	275.017092
LABOUR CESS @ 1% (+)	58.61979672
Grand Total	5920.59946872
Say For Unit 1 (Grand Total/1)	5920.59946872

Item 4

R.C.C. Work (AR0409): Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.

Sub-Item of Work

Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR001 : Male mulia	8	Per day	452	3616	0
LR046 : Blacksmith	3	Per day	602	1806	0
LR010 : Mate	0.44	Per day	502	220.88	0
BRM162 : Binding Wire.	8	1 Kg.	90	720	0
BRM341 : Steel	10.5	1 Qntl.	5775.86	60646.53	10916.3754

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	10.5	1 Qntl.	30.732	322.686	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	10.5	1 Qntl.	0	0	0

Total Amount (a+b+c)	67332.096
Total GST (a)	10916.3754
LABOUR CESS @ 1% (+)	782.484714
Grand Total	79030.956114

Item 5

R.C.C. Work (AR0404Aa): Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centering and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)

Sub-Item of Work

Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
Combine :: R.C.C. Work (AR0404A)					
PM096 : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0
PM083 : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0
LR001 : Male mulia	1.3333	Per day	452	602.6516	0
LR025 : Mason	0.1	Per day	552	55.2	0
LR010 : Mate	0.0573	Per day	502	28.7646	0
BRM340 : Cement	3.4733	1 Qntl.	428.91	1489.733103	417.12526884
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	66.85	30.0825	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1380	496.8	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1382.29	746.4366	0
Combine :: R.C.C. Work (AR0410c)					
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	1Cum.	58374.79	233.79103395	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.189	1Mtr.	30.81	5.82309	0
LR008 : Sangi mulia	0.075	Per day	502	37.65	0

LR027 : Carpenter	0.075	Per day	552	41.4	0
-------------------	-------	---------	-----	------	---

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	30.732	106.7414556	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	497.35	223.8075	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	653.59	235.2924	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	653.59	352.9386	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	1Cum.	245.856	0.98465328	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.000921	1Mtr.	245.856	0.226433376	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	602.25	271.0125	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	551.5	198.54	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	551.5	297.81	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	1Cum.	0	0	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.000921	1Mtr.	0	0	0

Total Amount (a+b+c)	5827.506069206
Total GST (a)	417.12526884
LABOUR CESS @ 1% (+)	62.44631338046
Grand Total	6307.0776514265
Say For Unit 1 (Grand Total/1)	6307.0776514265

Item 6

Masonry Brick Work (AR0603bi): Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm² immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work

Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRMMR0025 : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK	1	1 Cum	33	33	0
LR001 : Male mulia	2.82	Per day	452	1274.64	0
LR025 : Mason	1.05	Per day	552	579.6	0
LR044 : Mason	0.35	Per day	602	210.7	0
BRM340 : Cement	0.672	1 Qntl.	428.91	288.22752	80.7037056
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	66.85	18.718	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm² with dimensional tolerance ± 2 %	350	1000 Nos	5	1750	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.672	1 Qntl.	30.732	20.651904	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	497.35	139.258	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm² with dimensional tolerance ± 2 %	350	1000 Nos	1.36475	477.6625	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.672	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	602.25	168.63	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm² with dimensional tolerance ± 2 %	350	1000 Nos	0.04025	14.0875	0

Total Amount (a+b+c)	4975.175424
Total GST (a)	80.7037056
LABOUR CESS @ 1% (+)	50.558791296

Grand Total	5106.437920896
Say For Unit 1 (Grand Total/1)	5106.437920896

Item 7

Plastering (AR1004i): 12mm thick cement plaster (1:6) over Brick work in outside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.

Sub-Item of Work

12mm thick cement plaster (1:6) over Brick work in outside.

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.05	Per day	452	22.6	0
LR001 : Male mulia	0.07	Per day	452	31.64	0
LR025 : Mason	0.14	Per day	552	77.28	0
BRM340 : Cement	0.0358	1 Qntl.	428.91	15.354978	4.29939384
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	66.85	1.00275	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0358	1 Qntl.	30.732	1.1002056	0
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	497.35	7.46025	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0358	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	602.25	9.03375	0

Total Amount (a+b+c)	165.4719336
Total GST (a)	4.29939384
LABOUR CESS @ 1% (+)	1.6977132744
Grand Total	171.4690407144
Say For Unit 1 (Grand Total/1)	171.4690407144

Item 8

Plastering (AR1014i): 16mm thick cement Plaster in CM (1:6) over brick work in outside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.

Sub-Item of Work
16mm thick cement Plaster in CM (1:6) over brick work in outside (outside)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.11	Per day	452	49.72	0
LR001 : Male mulia	0.13	Per day	452	58.76	0
LR025 : Mason	0.16	Per day	552	88.32	0
BRM340 : Cement	0.043	1 Qntl.	428.91	18.44313	5.1640764
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	66.85	1.2033	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.043	1 Qntl.	30.732	1.321476	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	497.35	8.9523	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.043	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	602.25	10.8405	0

Total Amount (a+b+c)	237.560706
Total GST (a)	5.1640764
LABOUR CESS @ 1% (+)	2.427247824
Grand Total	245.152030224
Say For Unit 1 (Grand Total/1)	245.152030224

Item 9

Painting (AR0918cb): Finishing wall two coats with weather coat with one coat waterbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)

Sub-Item of Work
Finishing wall two coats with weather coat with one coat waterbound Primer

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
Combine :: Painting (AR0918f)					
BRM255 : Weather Coat (I.S.I.)	0.125	1 Ltr	194.79	24.34875	0

LR001 : Male mulia	0.064	Per day	452	28.928	0
LR048 : Painter/ Polisher	0.054	Per day	602	32.508	0
Combine :: Painting (AR0901di)					
BRM253 : Wall cement primer (I.S.I.) Water bound	0.090322580645161	1 Ltr	159.03	14.364	0
LR048 : Painter/ Polisher	0.053763440860215	Per day	602	32.365591397849	0
LR001 : Male mulia	0.053763440860215	Per day	452	24.301075268817	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	0.125	1 Ltr	0.30732	0.038415	0
BRM253 : Wall cement primer (I.S.I.) Water bound	0.090322580645161	1 Ltr	0.30732	0.027757935483871	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	0.125	1 Ltr	0	0	0
BRM253 : Wall cement primer (I.S.I.) Water bound	0.090322580645161	1 Ltr	0	0	0

Total Amount (a+b+c)	156.88158960215
Total GST (a)	0
LABOUR CESS @ 1% (+)	1.5688158960215
Grand Total	158.45040549817
Say For Unit 1 (Grand Total/1)	158.45040549817

BHIM CHARAN TUDU
JE
Baripada Block

SUSMITA BEHERA
AEE
Baripada Block

AISHWARYA BHUYAN
BDO
Baripada Block