

Analysis

**OD/364/3484/119960/430234/00015497 : Construction of VSS building at Sukraguda
Block : Malkangiri, Panchayat : Challanguda
Created By:Tapan kumar senapati**

Item 1

Earth Work (AR0122Ai1): Earthwork in all kinds of soil within 50m to 75m lead and 1.5m, initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per direction of the Engineer-in-charge.

Sub-Item of Work

Earthwork in all kinds of soil within 50m to 75m lead and 1.5m, initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
Combine :: Earth Work (AR0122Ai)					
LR002 : Female mulia	23.6767	Per day	452	10701.8684	0
LR001 : Male mulia	23.6767	Per day	452	10701.8684	0
Combine :: Earth Work (AR0107)					
LR001 : Male mulia	3	Per day	452	1356	0

Total Amount (a+b+c)	22759.7368
Total GST (a)	0
LABOUR CESS @ 1% (+)	227.597368
Grand Total	22987.334168
Say For Unit 1 (Grand Total/100)	229.87334168

Item 2

Earth Work (AR0115): Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

Filling foundation and plinth with sand well watered and rammed

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	71.94	7194	0
LR002 : Female mulia	12.36	Per day	452	5586.72	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	406.21	40621	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	40.25	4025	0

Total Amount (a+b+c)	57426.72				
Total GST (a)	0				
LABOUR CESS @ 1% (+)	574.2672				
Grand Total	58000.9872				
Say For Unit 1 (Grand Total/100)	580.009872				

Item 3

Concrete (AR0304a): Cement concrete (1:4:8) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

Cement concrete (1:4:8) with 4 cm. hard granite(Hand Broken) metal

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.4	Per day	452	632.8	0
LR001 : Male mulia	2.5	Per day	452	1130	0
LR025 : Mason	0.18	Per day	552	99.36	0
BRM340 : Cement	1.72	1 Qntl.	633.36	1089.3792	305.026176
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	76.88	36.9024	0
BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	1 Cum.	787.36	755.8656	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	1.72	1 Qntl.	36.677	63.08444	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	601.51	288.7248	0

BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	1 Cum.	601.51	577.4496	0
---	------	--------	--------	----------	---

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	1.72	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	40.25	19.32	0
BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	1 Cum.	149.5	143.52	0

Total Amount (a+b+c)	4836.40604
Total GST (a)	305.026176
LABOUR CESS @ 1% (+)	51.41432216
Grand Total	5192.84653816
Say For Unit 1 (Grand Total/1)	5192.84653816

Item 4

R.C.C. Work (AR0404A): Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. (excluding centering and shuttering)

Sub-Item of Work

Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
PM096 : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0
PM083 : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0
LR001 : Male mulia	1.3333	Per day	452	602.6516	0
LR025 : Mason	0.1	Per day	552	55.2	0
LR010 : Mate	0.0573	Per day	502	28.7646	0
BRM340 : Cement	3.4733	1 Qntl.	633.36	2199.849288	615.95780064
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0

BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1418.67	510.7212	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1382.29	746.4366	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	36.677	127.3902241	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	601.51	270.6795	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	601.51	216.5436	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	601.51	324.8154	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	40.25	18.1125	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	149.5	53.82	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	149.5	80.73	0

Total Amount (a+b+c)	5642.1305121
Total GST (a)	615.95780064
LABOUR CESS @ 1% (+)	62.5808831274
Grand Total	6320.6691958674
Say For Unit 1 (Grand Total/1)	6320.6691958674

Item 5

R.C.C. Work (AR0409): Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.

Sub-Item of Work

Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR001 : Male mulia	8	Per day	452	3616	0
LR046 : Blacksmith	3	Per day	602	1806	0
LR010 : Mate	0.44	Per day	502	220.88	0
BRM162 : Binding Wire.	8	1 Kg.	90.1	720.8	0
BRM341 : Steel	10.5	1 Qntl.	6415.68	67364.64	12125.6352

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	10.5	1 Qntl.	36.677	385.1085	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	10.5	1 Qntl.	0	0	0

Total Amount (a+b+c)					74113.4285
Total GST (a)					12125.6352
LABOUR CESS @ 1% (+)					862.390637
Grand Total					87101.454337
Say For Unit 1 (Grand Total/10)					8710.1454337

Item 6

Masonry Brick Work (AR0602di): Brickwork with C.B. Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:4) in superstructure having crushing strength not less than 75.00 Kg/cm² immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work

C.B. Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:4) in superstructure

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
------------	----------	------	------	--------	-----

BRMMR0025 : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK	1	1 Cum	33	33	0
BRM001 : Well burnt clamp burnt bricks (25 Cm. x 12Cm. x 8Cm.) having crushing strength not less than 35 Kg./Cm2 with dimensional tolerance ± 8 percent.	350	1000 Nos	4.23196	1481.186	0
BRM340 : Cement	1	1 Qntl.	633.36	633.36	177.3408
LR001 : Male mulia	2.82	Per day	452	1274.64	0
LR025 : Mason	1.05	Per day	552	579.6	0
LR044 : Mason	0.35	Per day	602	210.7	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	76.88	21.5264	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM001 : Well burnt clamp burnt bricks (25 Cm. x 12Cm. x 8Cm.) having crushing strength not less than 35 Kg./Cm2 with dimensional tolerance ± 8 percent.	350	1000 Nos	1.15865	405.5275	0
BRM340 : Cement	1	1 Qntl.	36.677	36.677	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	601.51	168.4228	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM001 : Well burnt clamp burnt bricks (25 Cm. x 12Cm. x 8Cm.) having crushing strength not less than 35 Kg./Cm2 with dimensional tolerance ± 8 percent.	350	1000 Nos	0.04025	14.0875	0
BRM340 : Cement	1	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	40.25	11.27	0

Total Amount (a+b+c)	4869.9972
Total GST (a)	177.3408
LABOUR CESS @ 1% (+)	50.47338
Grand Total	5097.81138
Say For Unit 1 (Grand Total/1)	5097.81138

Item 7

Other Building Items. (AR1901B): Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)

Sub-Item of Work

Vitrified Tile 600mmx600mm Plain Ivory

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM174 : White Cement.	0.076	1Qntl	2017.18	153.30568	42.9255904
BRM340 : Cement	1.074	1 Qntl.	633.36	680.22864	190.4640192
BRM028 : Screened and washed sharp sand for mortar	0.21	1 Cum	76.88	16.1448	0
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	651.08	6510.8	1171.944
LR001 : Male mulia	2.16	Per day	452	976.32	0
LR044 : Mason	2.16	Per day	602	1300.32	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM174 : White Cement.	0.076	1Qntl	36.677	2.787452	0
BRM340 : Cement	1.074	1 Qntl.	36.677	39.391098	0
BRM028 : Screened and washed sharp sand for mortar	0.21	1 Cum	601.51	126.3171	0
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	12.8738891	128.738891	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM174 : White Cement.	0.076	1Qntl	0	0	0
BRM340 : Cement	1.074	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.21	1 Cum	40.25	8.4525	0
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	0	0	0

Total Amount (a+b+c)	9942.806161
Total GST (a)	1405.3336096
LABOUR CESS @ 1% (+)	113.481397706
Grand Total	11461.621168306
Say For Unit 1 (Grand Total/10)	1146.1621168306

Item 8

Plastering (AR1014): 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.

Sub-Item of Work

16mm thick cement Plaster in CM (1:6) over brick work in inside.

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.11	Per day	452	49.72	0
LR001 : Male mulia	0.13	Per day	452	58.76	0
LR025 : Mason	0.16	Per day	552	88.32	0
BRM340 : Cement	0.043	1 Qntl.	633.36	27.23448	7.6256544
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	76.88	1.38384	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.043	1 Qntl.	36.677	1.577111	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	601.51	10.82718	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.043	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	40.25	0.7245	0

Total Amount (a+b+c)	238.547111
Total GST (a)	7.6256544
LABOUR CESS @ 1% (+)	2.461727654
Grand Total	248.634493054
Say For Unit 1 (Grand Total/1)	248.634493054

Item 9

Plastering (AR1004): 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.

Sub-Item of Work

12mm thick cement plaster (1:6) over Brick work in inside

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.05	Per day	452	22.6	0
LR001 : Male mulia	0.07	Per day	452	31.64	0
LR025 : Mason	0.14	Per day	552	77.28	0
BRM340 : Cement	0.0358	1 Qntl.	633.36	22.674288	6.34880064
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	76.88	1.1532	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0358	1 Qntl.	36.677	1.3130366	0
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	601.51	9.02265	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0358	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	40.25	0.60375	0

Total Amount (a+b+c)

166.2869246

Total GST (a)

6.34880064

LABOUR CESS @ 1% (+)

1.7263572524

Grand Total

174.3620824924

Say For Unit 1 (Grand Total/1)

174.3620824924

Item 10

Iron Work (AR1704): Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in-charge.

Sub-Item of Work

Iron Doors and windows fixing

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	0.508	1 Qntl.	6415.68	3259.16544	586.6497792
LR001 : Male mulia	3.25	Per day	452	1469	0
LR011 : Helper to carpenter or Blacksmith/ Painter/ Blaster/Plumber/ Electrician/ Fitter/Welder	1	Per day	502	502	0
LR028 : Fitter	1	Per day	552	552	0
LR047 : Fitter	1	Per day	602	602	0
LR026 : Black smith	1	Per day	552	552	0
LR046 : Blacksmith	0.75	Per day	602	451.5	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	0.508	1 Qntl.	36.677	18.631916	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	0.508	1 Qntl.	0	0	0

Total Amount (a+b+c)					7406.297356
Total GST (a)					586.6497792
LABOUR CESS @ 1% (+)					79.929471352
Grand Total					8072.876606552
Say For Unit 1 (Grand Total/0.508)					15891.489382976

Item 11
Painting (AR0922): Finishing wall two coats with distemper of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)
Sub-Item of Work Finishing wall two coats with distemper of approved shades on new work (Inside)

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST

LR048 : Painter/ Polisher	0.52	Per day	602	313.04	0
BRM142 : Distemper	2.5	1 Kg.	70.1	175.25	31.545
LR001 : Male mulia	0.62	Per day	452	280.24	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM142 : Distemper	2.5	1 Kg.	0.36677	0.916925	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM142 : Distemper	2.5	1 Kg.	0	0	0

Total Amount (a+b+c)	769.446925				
Total GST (a)	31.545				
LABOUR CESS @ 1% (+)	8.00991925				
Grand Total	809.00184425				
Say For Unit 1 (Grand Total/10)	80.900184425				

Item 12

Other Building Items. (AR1902): Finishing surface of walls with cement based wall putty (water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes,labour,T&P,etc.complete. and as per the direction of Engineer in Charge.

Sub-Item of Work
cement based wall putty (water based)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRMMR0038 : Cement based putty	8	kg	30	240	0
LR001 : Male mulia	0.57	Per day	452	257.64	0
LR025 : Mason	0.5	Per day	552	276	0

Total Amount (a+b+c)	773.64				
Total GST (a)	0				
LABOUR CESS @ 1% (+)	7.7364				
Grand Total	781.3764				
Say For Unit 1 (Grand Total/10)	78.13764				

Item 13

Painting (AR0901d): Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.

Sub-Item of Work

Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM253 : Wall cement primer (I.S.I.) Water bound	0.7812	1 Ltr	159.03	124.234236	0
LR048 : Painter/ Polisher	0.5	Per day	602	301	0
LR001 : Male mulia	0.5	Per day	452	226	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM253 : Wall cement primer (I.S.I.) Water bound	0.7812	1 Ltr	0.36677	0.286520724	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM253 : Wall cement primer (I.S.I.) Water bound	0.7812	1 Ltr	0	0	0

Total Amount (a+b+c)

651.520756724

Total GST (a)

0

LABOUR CESS @ 1% (+)

6.51520756724

Grand Total

658.03596429124

Say For Unit 1 (Grand Total/9.3)

70.756555300133

Item 14

Flooring (AR0816): Fixing tiles in floors(30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755), treads, or steps and landing on a 25mm thick bed of cement mortar 1:1 (1cement: 1sand) jointed with neat cement slurry mixed with pigment to match the shades of the tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.

Sub-Item of Work

30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
------------	----------	------	------	--------	-----

MR0381 : Wax Polish	10	1 Sqm	8.5	85	0
BRM130 : Tiles up to 30cm x 30cm / 40cm x 40cm special plain / printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755	10	1 Sqm.	450.08	4500.8	810.144
LR001 : Male mulia	2.16	Per day	452	976.32	0
LR044 : Mason	2.16	Per day	602	1300.32	0
LR008 : Sangi mulia	5.5	Per day	502	2761	0
BRM340 : Cement	2.737	1 Qntl.	633.36	1733.50632	485.3817696
BRM028 : Screened and washed sharp sand for mortar	0.13	1 Cum	76.88	9.9944	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM130 : Tiles up to 30cm x 30cm / 40cm x 40cm special plain / printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755	10	1 Sqm.	12.8738891	128.738891	0
BRM340 : Cement	2.737	1 Qntl.	36.677	100.384949	0
BRM028 : Screened and washed sharp sand for mortar	0.13	1 Cum	601.51	78.1963	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM130 : Tiles up to 30cm x 30cm / 40cm x 40cm special plain / printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755	10	1 Sqm.	0	0	0
BRM340 : Cement	2.737	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.13	1 Cum	40.25	5.2325	0

Total Amount (a+b+c)	11679.49336
Total GST (a)	1295.5257696
LABOUR CESS @ 1% (+)	129.750191296
Grand Total	13104.769320896
Say For Unit 1 (Grand Total/10)	1310.4769320896

Item 15

Painting (AR0901b): Priming one coat in inner surface with primer of approved quality over iron work including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.

Sub-Item of Work
Fourth Floor

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR048 : Painter/ Polisher	0.562754405	Per day	602	338.77815181	0
BRM137 : Red oxide Primer	0.5022	1 Litre	142.7	71.66394	12.8995092
LR001 : Male mulia	0.562754405	Per day	452	254.36499106	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM137 : Red oxide Primer	0.5022	1 Litre	0.36677	0.184191894	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM137 : Red oxide Primer	0.5022	1 Litre	0	0	0

Total Amount (a+b+c)	664.991274764
Total GST (a)	12.8995092
LABOUR CESS @ 1% (+)	6.77890783964
Grand Total	684.66969180364
Say For Unit 1 (Grand Total/9.3)	73.620396968133

Er.BUDHIRAM TIYU
JE
Malkangiri Block

Er. ABHIJIT SETHI
AEE
Malkangiri Block

Tapan kumar senapati
BDO
Malkangiri Block