

Analysis

OD/367/3527/120671/406307/00017162 : Maintenance of Krushnaprasad Mundia Tala Road
Block : Nayagarh, Gram Panchayat : Lathipada
Created By:Aishwarya Bhuyan

Item 1

Earth Work (AR0102aa): Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge

Sub-Item of Work

Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	25.8	Per day	462	11919.6	0
LR001 : Male mulia	25.8	Per day	462	11919.6	0

Total Amount (a+b+c)

23839.2

Total GST (a)

0

LABOUR CESS @ 1% (+)

238.392

Grand Total

24077.592

Say For Unit 1 (Grand Total/100)

240.77592

Item 2

Earth Work (AR0115): Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work

Filling foundation and plinth with sand well watered and rammed

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	56.57	5657	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	354.13	35413	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	305.25	30525	0

Total Amount (a+b+c)	77305.32				
Total GST (a)	0				
LABOUR CESS @ 1% (+)	773.0532				
Grand Total	78078.3732				
Say For Unit 1 (Grand Total/100)	780.783732				

Item 3

Concrete (AR0303a): Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	2.5	Per day	462	1155	0
LR025 : Mason	0.18	Per day	562	101.16	0
BRM340 : Cement	2.29	1 Qntl.	554.5	1269.805	355.5454
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	63	30.24	0
BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	1 Cum.	762.43	731.9328	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	24.787	56.76223	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	354.13	169.9824	0
BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	1 Cum.	276.01	264.9696	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	305.25	146.52	0
BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	1 Cum.	199.5	191.52	0

Total Amount (a+b+c)	4764.69203
Total GST (a)	355.5454
LABOUR CESS @ 1% (+)	51.2023743
Grand Total	5171.4398043
Say For Unit 1 (Grand Total/1)	5171.4398043

Item 4

Concrete (AR0307): Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.

Sub-Item of Work

Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	3.2	Per day	462	1478.4	0
LR025 : Mason	0.68	Per day	562	382.16	0
BRM340 : Cement	3.23	1 Qntl.	554.5	1791.035	501.4898
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	63	28.35	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	1396.62	1256.958	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	24.787	80.06201	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	354.13	159.3585	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	276.01	248.409	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
------------	----------	------	------	--------	-----

BRM340 : Cement	3.23	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	305.25	137.3625	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	199.5	179.55	0

Total Amount (a+b+c)	6388.44501
Total GST (a)	501.4898
LABOUR CESS @ 1% (+)	68.8993481
Grand Total	6958.8341581
Say For Unit 1 (Grand Total/1)	6958.8341581

Item 5

R.C.C. Work (AR0410c): Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc

Sub-Item of Work

R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	58374.79	1558.606893	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	1.26	1Mtr.	30.81	38.8206	0
LR008 : Sangi mulia	0.5	Per day	512	256	0
LR027 : Carpenter	0.5	Per day	562	281	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	198.296	5.2945032	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	198.296	1.21753744	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	0	0	0

BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	0	0	0
---	---------	-------	---	---	---

Total Amount (a+b+c)	2140.93953364
Total GST (a)	0
LABOUR CESS @ 1% (+)	21.4093953364
Grand Total	2162.3489289764
Say For Unit 1 (Grand Total/10)	216.23489289764

Manoja Kumar Sethi
JE
Nayagarh Block

Chandra Sekhar Samantaray
AEE
Nayagarh Block

Aishwarya Bhuyan
BDO
Nayagarh Block