

Analysis

OD/367/3527/120676/406658/00013798 : DEV OF CREMATORIUM NOTAR

Block : Nayagarh, Gram Panchayat : Notar

Created By:Aishwarya Bhuyan

Item 1

Earth Work (AR0102aa): Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge

Sub-Item of Work

Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	25.8	Per day	462	11919.6	0
LR001 : Male mulia	25.8	Per day	462	11919.6	0

Total Amount (a+b+c)

23839.2

Total GST (a)

0

LABOUR CESS @ 1% (+)

238.392

Grand Total

24077.592

Say For Unit 1 (Grand Total/100)

240.77592

Item 2

Earth Work (AR0115): Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work

Filling foundation and plinth with sand well watered and rammed

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	56.57	5657	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	354.13	35413	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	305.25	30525	0

Total Amount (a+b+c)	77305.32				
Total GST (a)	0				
LABOUR CESS @ 1% (+)	773.0532				
Grand Total	78078.3732				
Say For Unit 1 (Grand Total/100)	780.783732				

Item 3

Concrete (AR0303a): Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	2.5	Per day	462	1155	0
LR025 : Mason	0.18	Per day	562	101.16	0
BRM340 : Cement	2.29	1 Qntl.	554.5	1269.805	355.5454
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	63	30.24	0
BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	1 Cum.	762.43	731.9328	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	24.787	56.76223	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	354.13	169.9824	0
BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	1 Cum.	276.01	264.9696	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	305.25	146.52	0
BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	1 Cum.	199.5	191.52	0

Total Amount (a+b+c)	4764.69203
Total GST (a)	355.5454
LABOUR CESS @ 1% (+)	51.2023743
Grand Total	5171.4398043
Say For Unit 1 (Grand Total/1)	5171.4398043

Item 4

Masonry Brick Work (AR0603b): Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work

Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.14	Per day	462	64.68	0
LR001 : Male mulia	2.82	Per day	462	1302.84	0
LR025 : Mason	1.05	Per day	562	590.1	0
LR044 : Mason	0.35	Per day	612	214.2	0
BRM340 : Cement	0.672	1 Qntl.	554.5	372.624	104.33472
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	63	17.64	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm² with dimensional tolerance ± 2 %	350	1000 Nos	5.14255	1799.8925	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.672	1 Qntl.	24.787	16.656864	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	354.13	99.1564	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm² with dimensional tolerance ± 2 %	350	1000 Nos	0.8641	302.435	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
------------	----------	------	------	--------	-----

BRM340 : Cement	0.672	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	305.25	85.47	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance ± 2 %	350	1000 Nos	0.04025	14.0875	0

Total Amount (a+b+c)	4879.782264				
Total GST (a)	104.33472				
LABOUR CESS @ 1% (+)	49.84116984				
Grand Total	5033.95815384				
Say For Unit 1 (Grand Total/1)	5033.95815384				

Item 5

R.C.C. Work (AR0404Aa): Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)

Sub-Item of Work

Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
Combine :: R.C.C. Work (AR0404A)					
PM096 : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0
PM083 : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0
LR001 : Male mulia	1.3333	Per day	462	615.9846	0
LR025 : Mason	0.1	Per day	562	56.2	0
LR010 : Mate	0.0573	Per day	512	29.3376	0
BRM340 : Cement	3.4733	1 Qntl.	554.5	1925.94485	539.264558
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	63	28.35	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1418.67	510.7212	0

BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1360.29	734.5566	0
Combine :: R.C.C. Work (AR0410c)					
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	1Cum.	58374.79	233.79103395	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.189	1Mtr.	30.81	5.82309	0
LR008 : Sangi mulia	0.075	Per day	512	38.4	0
LR027 : Carpenter	0.075	Per day	562	42.15	0

b) Carriage Rate Details						
Particular	Quantity	Unit	Rate	Amount	GST	
BRM340 : Cement	3.4733	1 Qntl.	24.787	86.0926871	0	
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	354.13	159.3585	0	
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	276.01	99.3636	0	
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	276.01	149.0454	0	
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	1Cum.	198.296	0.79417548	0	
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.000921	1Mtr.	198.296	0.182630616	0	

c) Royalty Rate Details						
Particular	Quantity	Unit	Rate	Amount	GST	
BRM340 : Cement	3.4733	1 Qntl.	0	0	0	
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	305.25	137.3625	0	
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	199.5	71.82	0	
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	199.5	107.73	0	
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	1Cum.	0	0	0	
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.000921	1Mtr.	0	0	0	

Total Amount (a+b+c)	5404.828467146
Total GST (a)	539.264558
LABOUR CESS @ 1% (+)	59.44093025146
Grand Total	6003.5339553975
Say For Unit 1 (Grand Total/1)	6003.5339553975

Item 6

R.C.C. Work (AR0404Ab): Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Plinth band)

Sub-Item of Work

Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
Combine :: R.C.C. Work (AR0404A)					
PM096 : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0
PM083 : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0
LR001 : Male mulia	1.3333	Per day	462	615.9846	0
LR025 : Mason	0.1	Per day	562	56.2	0
LR010 : Mate	0.0573	Per day	512	29.3376	0
BRM340 : Cement	3.4733	1 Qntl.	554.5	1925.94485	539.264558
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	63	28.35	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1418.67	510.7212	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1360.29	734.5566	0
Combine :: R.C.C. Work (AR0410c)					
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.01335	1Cum.	58374.79	779.3034465	0

BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.63	1Mtr.	30.81	19.4103	0
LR008 : Sangi mulia	0.25	Per day	512	128	0
LR027 : Carpenter	0.25	Per day	562	140.5	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	24.787	86.0926871	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	354.13	159.3585	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	276.01	99.3636	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	276.01	149.0454	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.01335	1Cum.	198.296	2.6472516	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00307	1Mtr.	198.296	0.60876872	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	305.25	137.3625	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	199.5	71.82	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	199.5	107.73	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.01335	1Cum.	0	0	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00307	1Mtr.	0	0	0

Total Amount (a+b+c)	6154.15730392
Total GST (a)	539.264558
LABOUR CESS @ 1% (+)	66.9342186192
Grand Total	6760.3560805392
Say For Unit 1 (Grand Total/1)	6760.3560805392

Item 7

R.C.C. Work (AR0404Ac): Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge. (RCC Beams, Column, Girder & Bressmer etc)

Sub-Item of Work

Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
Combine :: R.C.C. Work (AR0404A)					
PM096 : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0
PM083 : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0
LR001 : Male mulia	1.3333	Per day	462	615.9846	0
LR025 : Mason	0.1	Per day	562	56.2	0
LR010 : Mate	0.0573	Per day	512	29.3376	0
BRM340 : Cement	3.4733	1 Qntl.	554.5	1925.94485	539.264558
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	63	28.35	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1418.67	510.7212	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1360.29	734.5566	0
Combine :: R.C.C. Work (AR0410d)					
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	4.4196	1Mtr	51.87	229.244652	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.041529	1Cum.	58374.79	2424.24665391	0
LR008 : Sangi mulia	5.23875	Per day	512	2682.24	0
LR027 : Carpenter	5.23875	Per day	562	2944.1775	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	24.787	86.0926871	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	354.13	159.3585	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	276.01	99.3636	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	276.01	149.0454	0
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.045339	1Mtr	198.296	8.990542344	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.041529	1Cum.	198.296	8.235034584	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	305.25	137.3625	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	199.5	71.82	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	199.5	107.73	0
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.045339	1Mtr	0	0	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.041529	1Cum.	0	0	0

Total Amount (a+b+c)	13380.821919938
Total GST (a)	539.264558
LABOUR CESS @ 1% (+)	139.20086477938
Grand Total	14059.287342717
Say For Unit 1 (Grand Total/1)	14059.287342717

Item 8

R.C.C. Work (AR0404Bg): Reinforced cement concrete work of M-20 grade with 20mm & downgrade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Roof slab, lending, balcony, sun shed)(Nominal mix as per IS-456, Table-9).

Sub-Item of Work

Reinforced cement concrete work of M-20 grade with 20mm & downgrade size black hard crusher broken granite chips(RCC Roof slab, lending, balcony, sun shed)(Nominal mix as per IS-456, Table-9).

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
Combine :: R.C.C. Work (AR0404B)					
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1418.67	510.7212	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1360.29	734.5566	0
PM096 : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0
PM083 : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0
LR001 : Male mulia	1.3333	Per day	462	615.9846	0
LR025 : Mason	0.1	Per day	562	56.2	0
LR010 : Mate	0.0573	Per day	512	29.3376	0
BRM340 : Cement	3.4733	1 Qntl.	554.5	1925.94485	539.264558
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	63	28.35	0
Combine :: R.C.C. Work (AR0410a)					
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	6.2216	1Mtr	51.87	322.714392	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0502172	1Cum.	58374.79	2931.418504388	0
LR008 : Sangi mulia	3.05525	Per day	512	1564.288	0
LR027 : Carpenter	3.05525	Per day	562	1717.0505	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
------------	----------	------	------	--------	-----

BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	276.01	99.3636	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	276.01	149.0454	0
BRM340 : Cement	3.4733	1 Qntl.	24.787	86.0926871	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	354.13	159.3585	0
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.076659	1Mtr	198.296	15.201173064	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0502172	1Cum.	198.296	9.9578698912	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	199.5	71.82	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	199.5	107.73	0
BRM340 : Cement	3.4733	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	305.25	137.3625	0
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.076659	1Mtr	0	0	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0502172	1Cum.	0	0	0

Total Amount (a+b+c)	11644.317976443
Total GST (a)	539.264558
LABOUR CESS @ 1% (+)	121.83582534443
Grand Total	12305.418359788
Say For Unit 1 (Grand Total/1)	12305.418359788

Item 9
R.C.C. Work (AR0409): Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.

Sub-Item of Work
Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR001 : Male mulia	8	Per day	462	3696	0
LR046 : Blacksmith	3	Per day	612	1836	0
LR010 : Mate	0.44	Per day	512	225.28	0
BRM162 : Binding Wire.	8	1 Kg.	90.1	720.8	0
BRM341 : Steel	10.5	1 Qntl.	6591.7	69212.85	12458.313

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	10.5	1 Qntl.	24.787	260.2635	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	10.5	1 Qntl.	0	0	0

Total Amount (a+b+c)					75951.1935
Total GST (a)					12458.313
LABOUR CESS @ 1% (+)					884.095065
Grand Total					89293.601565
Say For Unit 1 (Grand Total/10)					8929.3601565

Item 10

Masonry Brick Work (AR0603bi): Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work
Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.14	Per day	462	64.68	0
BRMMR0025 : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK	1	1 Cum	33	33	0

LR001 : Male mulia	2.82	Per day	462	1302.84	0
LR025 : Mason	1.05	Per day	562	590.1	0
LR044 : Mason	0.35	Per day	612	214.2	0
BRM340 : Cement	0.672	1 Qntl.	554.5	372.624	104.33472
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	63	17.64	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	350	1000 Nos	5.14255	1799.8925	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.672	1 Qntl.	24.787	16.656864	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	354.13	99.1564	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	350	1000 Nos	0.8641	302.435	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.672	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	305.25	85.47	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	350	1000 Nos	0.04025	14.0875	0

Total Amount (a+b+c)	4912.782264
Total GST (a)	104.33472
LABOUR CESS @ 1% (+)	50.17116984
Grand Total	5067.28815384
Say For Unit 1 (Grand Total/1)	5067.28815384

Item 11

Plastering (AR1027): 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.

Sub-Item of Work

6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside)

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR001 : Male mulia	0.12	Per day	462	55.44	0
LR002 : Female mulia	0.05	Per day	462	23.1	0
LR025 : Mason	0.14	Per day	562	78.68	0
BRM340 : Cement	0.0372	1 Qntl.	554.5	20.6274	5.775672
BRM028 : Screened and washed sharp sand for mortar	0.0075	1 Cum	63	0.4725	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0372	1 Qntl.	24.787	0.9220764	0
BRM028 : Screened and washed sharp sand for mortar	0.0075	1 Cum	354.13	2.655975	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0372	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.0075	1 Cum	305.25	2.289375	0

Total Amount (a+b+c)	184.1873264				
Total GST (a)	5.775672				
LABOUR CESS @ 1% (+)	1.899629984				
Grand Total	191.862628384				
Say For Unit 1 (Grand Total/1)	191.862628384				

Item 12

Plastering (AR1004): 12mm thick cement plster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.

Sub-Item of Work

12mm thick cement plster (1:6) over Brick work in inside

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.05	Per day	462	23.1	0
LR001 : Male mulia	0.07	Per day	462	32.34	0
LR025 : Mason	0.14	Per day	562	78.68	0
BRM340 : Cement	0.0358	1 Qntl.	554.5	19.8511	5.558308

BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	63	0.945	0
---	-------	-------	----	-------	---

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0358	1 Qntl.	24.787	0.8873746	0
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	354.13	5.31195	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0358	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	305.25	4.57875	0

Total Amount (a+b+c)	165.6941746				
Total GST (a)	5.558308				
LABOUR CESS @ 1% (+)	1.712524826				
Grand Total	172.965007426				
Say For Unit 1 (Grand Total/1)	172.965007426				

Item 13

Plastering (AR1014): 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.

Sub-Item of Work

16mm thick cement Plaster in CM (1:6) over brick work in inside.

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.11	Per day	462	50.82	0
LR001 : Male mulia	0.13	Per day	462	60.06	0
LR025 : Mason	0.16	Per day	562	89.92	0
BRM340 : Cement	0.043	1 Qntl.	554.5	23.8435	6.67618
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	63	1.134	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.043	1 Qntl.	24.787	1.065841	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	354.13	6.37434	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.043	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	305.25	5.4945	0

Total Amount (a+b+c)	238.712181
Total GST (a)	6.67618
LABOUR CESS @ 1% (+)	2.45388361
Grand Total	247.84224461
Say For Unit 1 (Grand Total/1)	247.84224461

Item 14
Painting (AR0901d): Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.
Sub-Item of Work Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface)

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM253 : Wall cement primer (I.S.I.) Water bound	0.7812	1 Ltr	159.03	124.234236	0
LR048 : Painter/ Polisher	0.5	Per day	612	306	0
LR001 : Male mulia	0.5	Per day	462	231	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM253 : Wall cement primer (I.S.I.) Water bound	0.7812	1 Ltr	0.24787	0.193636044	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM253 : Wall cement primer (I.S.I.) Water bound	0.7812	1 Ltr	0	0	0

Total Amount (a+b+c)	661.427872044
Total GST (a)	0
LABOUR CESS @ 1% (+)	6.61427872044
Grand Total	668.04215076444
Say For Unit 1 (Grand Total/9.3)	71.83248932951

Item 15

Painting (AR0918ca): Finishing wall surface two coats with weather coat with one coat oilbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)

Sub-Item of Work

Finishing wall two coats with weather coat with one coat oilbound Primer

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
Combine :: Painting (AR0918f)					
BRM255 : Weather Coat (I.S.I.)	0.125	1 Ltr	194.79	24.34875	0
LR001 : Male mulia	0.064	Per day	462	29.568	0
LR048 : Painter/ Polisher	0.054	Per day	612	33.048	0
Combine :: Painting (AR0901ci)					
BRM252 : Wall cement primer (I.S.I.) Oil bound	0.084	1 Ltr	125.5	10.542	0
LR048 : Painter/ Polisher	0.053763440860215	Per day	612	32.903225806452	0
LR001 : Male mulia	0.053763440860215	Per day	462	24.838709677419	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	0.125	1 Ltr	0.24787	0.03098375	0
BRM252 : Wall cement primer (I.S.I.) Oil bound	0.084	1 Ltr	0.24787	0.02082108	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	0.125	1 Ltr	0	0	0
BRM252 : Wall cement primer (I.S.I.) Oil bound	0.084	1 Ltr	0	0	0

Total Amount (a+b+c)	155.30049031387
Total GST (a)	0
LABOUR CESS @ 1% (+)	1.5530049031387
Grand Total	156.85349521701
Say For Unit 1 (Grand Total/1)	156.85349521701

Item 16

Painting (AR0920): Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)

Sub-Item of Work

Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM140 : Plastic Emulsion paint	1.25	1 Litre	249.24	311.55	0
LR048 : Painter/ Polisher	0.54	Per day	612	330.48	0
LR001 : Male mulia	0.64	Per day	462	295.68	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM140 : Plastic Emulsion paint	1.25	1 Litre	0.24787	0.3098375	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM140 : Plastic Emulsion paint	1.25	1 Litre	0	0	0

Total Amount (a+b+c)

938.0198375

Total GST (a)

0

LABOUR CESS @ 1% (+)

9.380198375

Grand Total

947.400035875

Say For Unit 1 (Grand Total/10)

94.7400035875

Item 17

Flooring (AR0817aa): Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.

Sub-Item of Work

Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B Ia) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	643.11	6431.1	0

BRMMR0027 : Wax Polish	10	1 Sqm	8.5	85	0
LR044 : Mason	3.25	Per day	612	1989	0
LR001 : Male mulia	3.25	Per day	462	1501.5	0
LR008 : Sangi mulia	7.6	Per day	512	3891.2	0
BRM340 : Cement	1.375	1 Qntl.	554.5	762.4375	213.4825
BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	63	9.45	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	9.6011111	96.011111	0
BRM340 : Cement	1.375	1 Qntl.	24.787	34.082125	0
BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	354.13	53.1195	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	0	0	0
BRM340 : Cement	1.375	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	305.25	45.7875	0

Total Amount (a+b+c)	14898.687736
Total GST (a)	213.4825
LABOUR CESS @ 1% (+)	151.12170236
Grand Total	15263.29193836
Say For Unit 1 (Grand Total/10)	1526.329193836

Item 18

Flooring (AR0817b): Fixing ceramic tiles (20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) in wall cladding on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.

Sub-Item of Work

Fixing ceramic tiles (20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM129 : Tiles up to 20cmx30cm / 20cm x 20cm special plain /printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753	10	1 Sqm.	405	4050	0
LR001 : Male mulia	3.25	Per day	462	1501.5	0
LR044 : Mason	3.25	Per day	612	1989	0
BRM340 : Cement	1.375	1 Qntl.	554.5	762.4375	213.4825
BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	63	9.45	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM129 : Tiles up to 20cmx30cm / 20cm x 20cm special plain /printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753	10	1 Sqm.	9.6011111	96.011111	0
BRM340 : Cement	1.375	1 Qntl.	24.787	34.082125	0
BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	354.13	53.1195	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM129 : Tiles up to 20cmx30cm / 20cm x 20cm special plain /printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753	10	1 Sqm.	0	0	0
BRM340 : Cement	1.375	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	305.25	45.7875	0

Total Amount (a+b+c)

8541.387736

Total GST (a)

213.4825

LABOUR CESS @ 1% (+)

87.54870236

Grand Total	8842.41893836
Say For Unit 1 (Grand Total/10)	884.241893836

Item 19

Plastering (AR1017): 20mm thick cement Plaster in CM (1:4) over stone work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.

Sub-Item of Work

20mm thick cement Plaster in CM (1:4) over brick work in inside.

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.11	Per day	462	50.82	0
LR001 : Male mulia	0.13	Per day	462	60.06	0
LR025 : Mason	0.16	Per day	562	89.92	0
BRM340 : Cement	0.0744	1 Qntl.	554.5	41.2548	11.551344
BRM028 : Screened and washed sharp sand for mortar	0.021	1 Cum	63	1.323	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0744	1 Qntl.	24.787	1.8441528	0
BRM028 : Screened and washed sharp sand for mortar	0.021	1 Cum	354.13	7.43673	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0744	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.021	1 Cum	305.25	6.41025	0

Total Amount (a+b+c)	259.0689328
Total GST (a)	11.551344
LABOUR CESS @ 1% (+)	2.706202768
Grand Total	273.326479568
Say For Unit 1 (Grand Total/1)	273.326479568

Item 20

Iron Work (AR1704): Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in-charge.

Sub-Item of Work
Iron Doors and windows fixing

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	0.508	1 Qntl.	6591.7	3348.5836	602.745048
LR001 : Male mulia	3.25	Per day	462	1501.5	0
LR011 : Helper to carpenter or Blacksmith/ Painter/ Blaster/Plumber/ Electrician/ Fitter/Welder	1	Per day	512	512	0
LR028 : Fitter	1	Per day	562	562	0
LR047 : Fitter	1	Per day	612	612	0
LR026 : Black smith	1	Per day	562	562	0
LR046 : Blacksmith	0.75	Per day	612	459	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	0.508	1 Qntl.	24.787	12.591796	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	0.508	1 Qntl.	0	0	0

Total Amount (a+b+c)				7569.675396	
Total GST (a)				602.745048	
LABOUR CESS @ 1% (+)				81.72420444	
Grand Total				8254.14464844	
Say For Unit 1 (Grand Total/0.508)				16248.316237087	

Item 21

Concrete (AR0307): Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.

Sub-Item of Work
Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	3.2	Per day	462	1478.4	0
LR025 : Mason	0.68	Per day	562	382.16	0
BRM340 : Cement	3.23	1 Qntl.	554.5	1791.035	501.4898
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	63	28.35	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	1396.62	1256.958	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	24.787	80.06201	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	354.13	159.3585	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	276.01	248.409	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	305.25	137.3625	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	199.5	179.55	0

Total Amount (a+b+c)	6388.44501				
Total GST (a)	501.4898				
LABOUR CESS @ 1% (+)	68.8993481				
Grand Total	6958.8341581				
Say For Unit 1 (Grand Total/1)	6958.8341581				

Item 22

R.C.C. Work (AR0410c): Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc

Sub-Item of Work

R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	58374.79	1558.606893	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	1.26	1Mtr.	30.81	38.8206	0
LR008 : Sangi mulia	0.5	Per day	512	256	0
LR027 : Carpenter	0.5	Per day	562	281	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	198.296	5.2945032	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	198.296	1.21753744	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	0	0	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	0	0	0

Total Amount (a+b+c)	2140.93953364
Total GST (a)	0
LABOUR CESS @ 1% (+)	21.4093953364
Grand Total	2162.3489289764
Say For Unit 1 (Grand Total/10)	216.23489289764

Item 23

Concrete (AR0318): 4cm thick grading concrete (1:2:4) on roof slab with 12mm size hard granite chips (Crusher Broken) including hoisting and laying in position compacting and curing for the proper period with cost conveyance, royalty, taxes of all materials, labor and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge. (Old Work)

Sub-Item of Work

4cm thick grading concrete (1:2:4) on roof slab with 12mm size hard granite chips (Crusher Broken)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR001 : Male mulia	1.008	Per day	462	465.696	0
LR044 : Mason	0.165	Per day	612	100.98	0
BRM340 : Cement	0.1287	1 Qntl.	554.5	71.36415	19.981962
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	63	1.134	0
BRM064 : Granite stone broken chips of 4.7 mm size passing through 6.7 mm sieve (crusher broken.) and retained on 2.36 mm sieve.	0.018	1 Cum.	850.2	15.3036	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.018	1 Cum.	1396.62	25.13916	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.1287	1 Qntl.	24.787	3.1900869	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	354.13	6.37434	0
BRM064 : Granite stone broken chips of 4.7 mm size passing through 6.7 mm sieve (crusher broken.) and retained on 2.36 mm sieve.	0.018	1 Cum.	276.01	4.96818	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.018	1 Cum.	276.01	4.96818	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.1287	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	305.25	5.4945	0
BRM064 : Granite stone broken chips of 4.7 mm size passing through 6.7 mm sieve (crusher broken.) and retained on 2.36 mm sieve.	0.018	1 Cum.	199.5	3.591	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.018	1 Cum.	199.5	3.591	0

Total Amount (a+b+c)	711.7941969
Total GST (a)	19.981962
LABOUR CESS @ 1% (+)	7.317761589
Grand Total	739.093920489
Say For Unit 1 (Grand Total/1)	739.093920489

Manoja Kumar Sethi
JE
Nayagarh Block

Chandra Sekhar Samantaray
AEE
Nayagarh Block

Aishwarya Bhuyan
BDO
Nayagarh Block