

Analysis

**OD/345/3297/116037/420890/00063773 : CONSTRUCTION OF COMMUNITY CENTRE FOR
MALISAMAJ AT TIKRAPADA
Block : Turekela, Gram Panchayat : Kandeil
Created By:Purnananda Patel**

Item 1
Earth Work (AR0102aa): Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge
Sub-Item of Work Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	25.8	Per day	462	11919.6	0
LR001 : Male mulia	25.8	Per day	462	11919.6	0
Total Amount (a+b+c)				23839.2	
Total GST (a)					0
LABOUR CESS @ 1% (+)					238.392
Grand Total					24077.592
Say For Unit 1 (Grand Total/100)					240.77592

Item 2
Earth Work (AR0115): Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work Filling foundation and plinth with sand well watered and rammed

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	71.94	7194	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	341.11	34111	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST

BRM029 : Sand for filling and road blinding	100	1 Cum	62.75	6275	0
---	-----	-------	-------	------	---

Total Amount (a+b+c)	53290.32
Total GST (a)	0
LABOUR CESS @ 1% (+)	532.9032
Grand Total	53823.2232
Say For Unit 1 (Grand Total/100)	538.232232

Item 3

Concrete (AR0303a): Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	2.5	Per day	462	1155	0
LR025 : Mason	0.18	Per day	562	101.16	0
BRM340 : Cement	2.29	1 Qntl.	541.48	1239.9892	223.198056
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	76.88	36.9024	0
BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	1 Cum.	787.36	755.8656	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	54.512	124.83248	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	341.11	163.7328	0
BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	1 Cum.	341.11	327.4656	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	62.75	30.12	0
BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	1 Cum.	157.5	151.2	0

Total Amount (a+b+c)	4733.06808
Total GST (a)	223.198056
LABOUR CESS @ 1% (+)	49.56266136
Grand Total	5005.82879736

Say For Unit 1 (Grand Total/1)	5005.82879736
--------------------------------	---------------

Item 4

Masonry Brick Work (AR0603ei): Brickwork with C.B. Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work
C.B. Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in superstructure

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.14	Per day	462	64.68	0
BRMMR0025 : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK	1	1 Cum	33	33	0
BRM002 : Well burnt clamp burnt bricks (23 Cm. x 11Cm. x 8Cm.) having crushing strength not less than 35 Kg./Cm ² with dimensional tolerance ± 8 percent.	400	1000 Nos	4.11387	1645.548	0
LR001 : Male mulia	2.96	Per day	462	1367.52	0
LR025 : Mason	1.05	Per day	562	590.1	0
LR044 : Mason	0.35	Per day	612	214.2	0
BRM340 : Cement	0.672	1 Qntl.	541.48	363.87456	65.4974208
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	76.88	21.5264	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM002 : Well burnt clamp burnt bricks (23 Cm. x 11Cm. x 8Cm.) having crushing strength not less than 35 Kg./Cm ² with dimensional tolerance ± 8 percent.	400	1000 Nos	0.8091	323.64	0
BRM340 : Cement	0.672	1 Qntl.	54.512	36.632064	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	341.11	95.5108	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM002 : Well burnt clamp burnt bricks (23 Cm. x 11Cm. x 8Cm.) having crushing strength not less than 35 Kg./Cm ² with dimensional tolerance ± 8 percent.	400	1000 Nos	0.04025	16.1	0
BRM340 : Cement	0.672	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	62.75	17.57	0

Total Amount (a+b+c)	4789.901824
-----------------------------	-------------

Total GST (a)	65.4974208
LABOUR CESS @ 1% (+)	48.553992448
Grand Total	4903.953237248
Say For Unit 1 (Grand Total/1)	4903.953237248

Item 5

R.C.C. Work (AR0404Aa): Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)

Sub-Item of Work

Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
Combine :: R.C.C. Work (AR0404A)					
PM096 : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0
PM083 : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0
LR001 : Male mulia	1.3333	Per day	462	615.9846	0
LR025 : Mason	0.1	Per day	562	56.2	0
LR010 : Mate	0.0573	Per day	512	29.3376	0
BRM340 : Cement	3.4733	1 Qntl.	541.48	1880.722484	338.53004712
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1400	504	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1382.29	746.4366	0
Combine :: R.C.C. Work (AR0410c)					
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	1Cum.	58374.79	233.79103395	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.189	1Mtr.	30.81	5.82309	0
LR008 : Sangi mulia	0.075	Per day	512	38.4	0
LR027 : Carpenter	0.075	Per day	562	42.15	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	54.512	189.3365296	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	341.11	153.4995	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	341.11	122.7996	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	341.11	184.1994	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	1Cum.	198.296	0.79417548	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.000921	1Mtr.	198.296	0.182630616	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	62.75	28.2375	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	157.5	56.7	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	157.5	85.05	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	1Cum.	0	0	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.000921	1Mtr.	0	0	0

Total Amount (a+b+c)	5380.060743646
Total GST (a)	338.53004712
LABOUR CESS @ 1% (+)	57.18590790766
Grand Total	5775.7766986737
Say For Unit 1 (Grand Total/1)	5775.7766986737

Item 6
R.C.C. Work (AR0404Ab): Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Plinth band)
Sub-Item of Work Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
Combine :: R.C.C. Work (AR0404A)					

PM096 : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0
PM083 : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0
LR001 : Male mulia	1.3333	Per day	462	615.9846	0
LR025 : Mason	0.1	Per day	562	56.2	0
LR010 : Mate	0.0573	Per day	512	29.3376	0
BRM340 : Cement	3.4733	1 Qntl.	541.48	1880.722484	338.53004712
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1400	504	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1382.29	746.4366	0
Combine :: R.C.C. Work (AR0410c)					
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.01335	1Cum.	58374.79	779.3034465	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.63	1Mtr.	30.81	19.4103	0
LR008 : Sangi mulia	0.25	Per day	512	128	0
LR027 : Carpenter	0.25	Per day	562	140.5	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	54.512	189.3365296	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	341.11	153.4995	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	341.11	122.7996	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	341.11	184.1994	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.01335	1Cum.	198.296	2.6472516	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00307	1Mtr.	198.296	0.60876872	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	62.75	28.2375	0

BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	157.5	56.7	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	157.5	85.05	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.01335	1Cum.	0	0	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00307	1Mtr.	0	0	0

Total Amount (a+b+c)	6129.38958042
Total GST (a)	338.53004712
LABOUR CESS @ 1% (+)	64.6791962754
Grand Total	6532.5988238154
Say For Unit 1 (Grand Total/1)	6532.5988238154

Item 7

R.C.C. Work (AR0404Ad): Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Lintels)

Sub-Item of Work

Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
Combine :: R.C.C. Work (AR0404A)					
PM096 : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0
PM083 : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0
LR001 : Male mulia	1.3333	Per day	462	615.9846	0
LR025 : Mason	0.1	Per day	562	56.2	0
LR010 : Mate	0.0573	Per day	512	29.3376	0
BRM340 : Cement	3.4733	1 Qntl.	541.48	1880.722484	338.53004712
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1400	504	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1382.29	746.4366	0

Combine :: R.C.C. Work (AR0410e)					
BRM094 : Non-sal bullahs 125mm. mean dia of any length.	3.7695	1Mtr.	41.81	157.602795	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0741335	1Cum.	58374.79	4327.527494465	0
LR008 : Sangi mulia	2.24375	Per day	512	1148.8	0
LR027 : Carpenter	2.24375	Per day	562	1260.9875	0

b) Carriage Rate Details						
Particular	Quantity	Unit	Rate	Amount	GST	
BRM340 : Cement	3.4733	1 Qntl.	54.512	189.3365296	0	
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	341.11	153.4995	0	
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	341.11	122.7996	0	
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	341.11	184.1994	0	
BRM094 : Non-sal bullahs 125mm. mean dia of any length.	0.049542	1Mtr.	198.296	9.823980432	0	
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0741335	1Cum.	198.296	14.700376516	0	

c) Royalty Rate Details						
Particular	Quantity	Unit	Rate	Amount	GST	
BRM340 : Cement	3.4733	1 Qntl.	0	0	0	
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	62.75	28.2375	0	
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	157.5	56.7	0	
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	157.5	85.05	0	
BRM094 : Non-sal bullahs 125mm. mean dia of any length.	0.049542	1Mtr.	0	0	0	
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0741335	1Cum.	0	0	0	

Total Amount (a+b+c)	11978.361960013
Total GST (a)	338.53004712
LABOUR CESS @ 1% (+)	123.16892007133
Grand Total	12440.060927204
Say For Unit 1 (Grand Total/1)	12440.060927204

Item 8

R.C.C. Work (AR0404Ac): Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge. (RCC Beams, Column, Girder & Bressmer etc)

Sub-Item of Work

Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
Combine :: R.C.C. Work (AR0404A)					
PM096 : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0
PM083 : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0
LR001 : Male mulia	1.3333	Per day	462	615.9846	0
LR025 : Mason	0.1	Per day	562	56.2	0
LR010 : Mate	0.0573	Per day	512	29.3376	0
BRM340 : Cement	3.4733	1 Qntl.	541.48	1880.722484	338.53004712
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1400	504	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1382.29	746.4366	0
Combine :: R.C.C. Work (AR0410d)					
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	4.4196	1Mtr	51.87	229.244652	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.041529	1Cum.	58374.79	2424.24665391	0
LR008 : Sangi mulia	5.23875	Per day	512	2682.24	0
LR027 : Carpenter	5.23875	Per day	562	2944.1775	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	54.512	189.3365296	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	341.11	153.4995	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	341.11	122.7996	0

BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	341.11	184.1994	0
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.045339	1Mtr	198.296	8.990542344	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.041529	1Cum.	198.296	8.235034584	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	62.75	28.2375	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	157.5	56.7	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	157.5	85.05	0
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.045339	1Mtr	0	0	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.041529	1Cum.	0	0	0

Total Amount (a+b+c)	13356.054196438
Total GST (a)	338.53004712
LABOUR CESS @ 1% (+)	136.94584243558
Grand Total	13831.530085994
Say For Unit 1 (Grand Total/1)	13831.530085994

Item 9

R.C.C. Work (AR0404Ag): Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Roof slab, landing, balcony, sun shade)

Sub-Item of Work

Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
Combine :: R.C.C. Work (AR0404A)					
PM096 : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0
PM083 : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0
LR001 : Male mulia	1.3333	Per day	462	615.9846	0
LR025 : Mason	0.1	Per day	562	56.2	0

LR010 : Mate	0.0573	Per day	512	29.3376	0
BRM340 : Cement	3.4733	1 Qntl.	541.48	1880.722484	338.53004712
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1400	504	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1382.29	746.4366	0
Combine :: R.C.C. Work (AR0410a)					
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	6.2216	1Mtr	51.87	322.714392	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0502172	1Cum.	58374.79	2931.418504388	0
LR008 : Sangi mulia	3.05525	Per day	512	1564.288	0
LR027 : Carpenter	3.05525	Per day	562	1717.0505	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	54.512	189.3365296	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	341.11	153.4995	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	341.11	122.7996	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	341.11	184.1994	0
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.076659	1Mtr	198.296	15.201173064	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0502172	1Cum.	198.296	9.9578698912	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	62.75	28.2375	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	157.5	56.7	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	157.5	85.05	0
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.076659	1Mtr	0	0	0

BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0502172	1Cum.	0	0	0
--	-----------	-------	---	---	---

Total Amount (a+b+c)	11619.550252943
Total GST (a)	338.53004712
LABOUR CESS @ 1% (+)	119.58080300063
Grand Total	12077.661103064
Say For Unit 1 (Grand Total/1)	12077.661103064

Item 10

R.C.C. Work (AR0409): Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.

Sub-Item of Work

Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR001 : Male mulia	8	Per day	462	3696	0
LR046 : Blacksmith	3	Per day	612	1836	0
LR010 : Mate	0.44	Per day	512	225.28	0
BRM162 : Binding Wire.	8	1 Kg.	90	720	0
BRM341 : Steel	10.5	1 Qntl.	6567.46	68958.33	12412.4994

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	10.5	1 Qntl.	54.512	572.376	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	10.5	1 Qntl.	0	0	0

Total Amount (a+b+c)	76007.986
Total GST (a)	12412.4994
LABOUR CESS @ 1% (+)	884.204854
Grand Total	89304.690254
Say For Unit 1 (Grand Total/10)	8930.4690254

Item 11

Plastering (AR1014): 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.

Sub-Item of Work

16mm thick cement Plaster in CM (1:6) over brick work in inside.

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.11	Per day	462	50.82	0
LR001 : Male mulia	0.13	Per day	462	60.06	0
LR025 : Mason	0.16	Per day	562	89.92	0
BRM340 : Cement	0.043	1 Qntl.	541.48	23.28364	4.1910552
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	76.88	1.38384	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.043	1 Qntl.	54.512	2.344016	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	341.11	6.13998	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.043	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	62.75	1.1295	0

Total Amount (a+b+c)	235.080976
Total GST (a)	4.1910552
LABOUR CESS @ 1% (+)	2.392720312
Grand Total	241.664751512
Say For Unit 1 (Grand Total/1)	241.664751512

Item 12

Plastering (AR1014i): 16mm thick cement Plaster in CM (1:6) over brick work in outside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.

Sub-Item of Work

16mm thick cement Plaster in CM (1:6) over brick work in outside (outside)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.11	Per day	462	50.82	0
LR001 : Male mulia	0.13	Per day	462	60.06	0
LR025 : Mason	0.16	Per day	562	89.92	0

BRM340 : Cement	0.043	1 Qntl.	541.48	23.28364	4.1910552
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	76.88	1.38384	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.043	1 Qntl.	54.512	2.344016	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	341.11	6.13998	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.043	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	62.75	1.1295	0

Total Amount (a+b+c)	235.080976
Total GST (a)	4.1910552
LABOUR CESS @ 1% (+)	2.392720312
Grand Total	241.664751512
Say For Unit 1 (Grand Total/1)	241.664751512

Item 13

Other Building Items. (AR1902): Finishing surface of walls with cement based wall putty (water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes,labour,T&P,etc.complete. and as per the direction of Engineer in Charge.

Sub-Item of Work
cement based wall putty (water based)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRMMR0038 : Cement based putty	8	kg	30	240	0
LR001 : Male mulia	0.57	Per day	462	263.34	0
LR025 : Mason	0.5	Per day	562	281	0

Total Amount (a+b+c)	784.34
Total GST (a)	0
LABOUR CESS @ 1% (+)	7.8434
Grand Total	792.1834
Say For Unit 1 (Grand Total/10)	79.21834

Item 14

Painting (AR0920): Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)

Sub-Item of Work

Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM140 : Plastic Emulsion paint	1.25	1 Litre	249.34	311.675	0
LR048 : Painter/ Polisher	0.54	Per day	612	330.48	0
LR001 : Male mulia	0.64	Per day	462	295.68	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM140 : Plastic Emulsion paint	1.25	1 Litre	0.54512	0.6814	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM140 : Plastic Emulsion paint	1.25	1 Litre	0	0	0

Total Amount (a+b+c)

938.5164

Total GST (a)

0

LABOUR CESS @ 1% (+)

9.385164

Grand Total

947.901564

Say For Unit 1 (Grand Total/10)

94.7901564

Item 15

Painting (AR0901d): Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.

Sub-Item of Work

Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM253 : Wall cement primer (I.S.I.) Water bound	0.7812	1 Ltr	159.03	124.234236	0
LR048 : Painter/ Polisher	0.5	Per day	612	306	0
LR001 : Male mulia	0.5	Per day	462	231	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM253 : Wall cement primer (I.S.I.) Water bound	0.7812	1 Ltr	0.54512	0.425847744	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM253 : Wall cement primer (I.S.I.) Water bound	0.7812	1 Ltr	0	0	0

Total Amount (a+b+c)	661.660083744
Total GST (a)	0
LABOUR CESS @ 1% (+)	6.61660083744
Grand Total	668.27668458144
Say For Unit 1 (Grand Total/9.3)	71.85770801951

Item 16

Painting (AR0918Ai): Finishing wall one coat with weather coat including all costs of labour, Paint, Primer and Brushes required for the work etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work

Finishing wall one coat with weather coat

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	0.75	1 Ltr	194.79	146.0925	0
LR001 : Male mulia	0.43	Per day	462	198.66	0
LR048 : Painter/ Polisher	0.36	Per day	612	220.32	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	0.75	1 Ltr	0.54512	0.40884	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	0.75	1 Ltr	0	0	0

Total Amount (a+b+c)	565.48134
Total GST (a)	0
LABOUR CESS @ 1% (+)	5.6548134
Grand Total	571.1361534
Say For Unit 1 (Grand Total/10)	57.11361534

Item 17

Painting (AR0918g): Finishing wall with two coats weather coat paint of approved shade including one coat of oil bound primer in the outer surface of old work to give an even shade including all costs of labour, Paint, Brushes, and putty required for the work, etc. complete and as per direction of Engineer-in-charge. (Outside)

Sub-Item of Work
Finishing wall with two coats weather coat paint of approved shade including one coat of oil bound primer in the outer surface of old work .(Outside)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
Combine :: Painting (AR0918f)					
BRM255 : Weather Coat (I.S.I.)	0.125	1 Ltr	194.79	24.34875	0
LR001 : Male mulia	0.064	Per day	462	29.568	0
LR048 : Painter/ Polisher	0.054	Per day	612	33.048	0
Combine :: Painting (AR0901ci)					
BRM252 : Wall cement primer (I.S.I.) Oil bound	0.084	1 Ltr	125.5	10.542	0
LR048 : Painter/ Polisher	0.053763440860215	Per day	612	32.903225806452	0
LR001 : Male mulia	0.053763440860215	Per day	462	24.838709677419	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	0.125	1 Ltr	0.54512	0.06814	0
BRM252 : Wall cement primer (I.S.I.) Oil bound	0.084	1 Ltr	0.54512	0.04579008	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	0.125	1 Ltr	0	0	0
BRM252 : Wall cement primer (I.S.I.) Oil bound	0.084	1 Ltr	0	0	0

Total Amount (a+b+c)	155.36261556387
Total GST (a)	0
LABOUR CESS @ 1% (+)	1.5536261556387
Grand Total	156.91624171951
Say For Unit 1 (Grand Total/1)	156.91624171951

Item 18

Iron Work (AR1704): Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in-charge.

Sub-Item of Work
Iron Doors and windows fixing

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	0.508	1 Qntl.	6567.46	3336.26968	600.5285424

LR001 : Male mulia	3.25	Per day	462	1501.5	0
LR011 : Helper to carpenter or Blacksmith/ Painter/ Blaster/Plumber/ Electrician/ Fitter/Welder	1	Per day	512	512	0
LR028 : Fitter	1	Per day	562	562	0
LR047 : Fitter	1	Per day	612	612	0
LR026 : Black smith	1	Per day	562	562	0
LR046 : Blacksmith	0.75	Per day	612	459	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	0.508	1 Qntl.	54.512	27.692096	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	0.508	1 Qntl.	0	0	0

Total Amount (a+b+c)	7572.461776
Total GST (a)	600.5285424
LABOUR CESS @ 1% (+)	81.729903184
Grand Total	8254.720221584
Say For Unit 1 (Grand Total/0.508)	16249.449255087

Item 19

Flooring (AR0802ii): 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips including punning incl. cost, conveyance & royalty of materials as per direction of Engineer-in-charge.

Sub-Item of Work

2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR001 : Male mulia	0.14	Per day	462	64.68	0
LR002 : Female mulia	0.22	Per day	462	101.64	0
LR044 : Mason	0.13	Per day	612	79.56	0
BRM340 : Cement	0.0858	1 Qntl.	541.48	46.458984	8.36261712

BRM028 : Screened and washed sharp sand for mortar	0.012	1 Cum	76.88	0.92256	0
BRM057 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve)(Hand broken)	0.023	1 Cum.	1085.19	24.95937	0

b) Carriage Rate Details						
Particular	Quantity	Unit	Rate	Amount	GST	
BRM340 : Cement	0.0858	1 Qntl.	54.512	4.6771296	0	
BRM028 : Screened and washed sharp sand for mortar	0.012	1 Cum	341.11	4.09332	0	
BRM057 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve)(Hand broken)	0.023	1 Cum.	341.11	7.84553	0	

c) Royalty Rate Details						
Particular	Quantity	Unit	Rate	Amount	GST	
BRM340 : Cement	0.0858	1 Qntl.	0	0	0	
BRM028 : Screened and washed sharp sand for mortar	0.012	1 Cum	62.75	0.753	0	
BRM057 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve)(Hand broken)	0.023	1 Cum.	157.5	3.6225	0	

Total Amount (a+b+c)	339.2123936
Total GST (a)	8.36261712
LABOUR CESS @ 1% (+)	3.4757501072
Grand Total	351.0507608272
Say For Unit 1 (Grand Total/1)	351.0507608272

MANORANJAN SAHU
JE
Turekela Block

NABA MALLICK
AEE
Turekela Block

Purnananda Patel
BDO
Turekela Block