

Analysis

OD/366/3520/120549/427209/00064028 : Const. of CC road from PMGSY road to Hiralal House
Block : Raigarh, Gram Panchayat : Naktisimoda
Created By:RITU SINGH

Item 1

Earth Work (AR0102aa): Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge

Sub-Item of Work

Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	25.8	Per day	462	11919.6	0
LR001 : Male mulia	25.8	Per day	462	11919.6	0

Total Amount (a+b+c)

23839.2

Total GST (a)

0

LABOUR CESS @ 1% (+)

238.392

Grand Total

24077.592

Say For Unit 1 (Grand Total/100)

240.77592

Item 2

Earth Work (AR0115): Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

Filling foundation and plinth with sand well watered and rammed

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	71.94	7194	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	666.61	66661	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
------------	----------	------	------	--------	-----

BRM029 : Sand for filling and road blinding	100	1 Cum	50.25	5025	0
---	-----	-------	-------	------	---

Total Amount (a+b+c)	84590.32
Total GST (a)	0
LABOUR CESS @ 1% (+)	845.9032
Grand Total	85436.2232
Say For Unit 1 (Grand Total/100)	854.362232

Item 3
R.C.C. Work (AR0410c): Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc
Sub-Item of Work R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	58374.79	1558.606893	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	1.26	1Mtr.	30.81	38.8206	0
LR008 : Sangi mulia	0.5	Per day	512	256	0
LR027 : Carpenter	0.5	Per day	562	281	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	245.856	6.5643552	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	245.856	1.50955584	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	0	0	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	0	0	0

Total Amount (a+b+c)	2142.50140404
Total GST (a)	0
LABOUR CESS @ 1% (+)	21.4250140404
Grand Total	2163.9264180804
Say For Unit 1 (Grand Total/10)	216.39264180804

Item 4

Concrete (AR0303a): Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	2.5	Per day	462	1155	0
LR025 : Mason	0.18	Per day	562	101.16	0
BRM340 : Cement	2.29	1 Qntl.	548.44	1255.9276	226.066968
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	76.13	36.5424	0
BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	1 Cum.	787.36	755.8656	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	30.732	70.37628	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	666.61	319.9728	0
BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	1 Cum.	406.21	389.9616	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	50.25	24.12	0
BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	1 Cum.	172.5	165.6	0

Total Amount (a+b+c)

4921.32628

Total GST (a)

226.066968

LABOUR CESS @ 1% (+)

51.47393248

Grand Total

5198.86718048

Say For Unit 1 (Grand Total/1)

5198.86718048

Item 5

Concrete (AR0307): Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.

Sub-Item of Work

Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum

a) Specific Rate Details						
Particular	Quantity	Unit	Rate	Amount	GST	
LR002 : Female mulia	1.4	Per day	462	646.8	0	
LR001 : Male mulia	3.2	Per day	462	1478.4	0	
LR025 : Mason	0.68	Per day	562	382.16	0	
BRM340 : Cement	3.23	1 Qntl.	548.44	1771.4612	318.863016	
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	76.13	34.2585	0	
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	1396.62	1256.958	0	

b) Carriage Rate Details						
Particular	Quantity	Unit	Rate	Amount	GST	
BRM340 : Cement	3.23	1 Qntl.	30.732	99.26436	0	
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	666.61	299.9745	0	
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	999.91	899.919	0	

c) Royalty Rate Details						
Particular	Quantity	Unit	Rate	Amount	GST	
BRM340 : Cement	3.23	1 Qntl.	0	0	0	
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	50.25	22.6125	0	
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	172.5	155.25	0	

Total Amount (a+b+c)	7047.05806					
Total GST (a)	318.863016					
LABOUR CESS @ 1% (+)	73.65921076					
Grand Total	7439.58028676					
Say For Unit 1 (Grand Total/1)	7439.58028676					

TANMAY PATTNAIK
JE
Raighar Block

SIDDHARTH SHANKAR RANA
AEE
Raighar Block

RITU SINGH
BDO
Raighar Block