

Analysis

OD/354/3378/117862/412577/00064286 : REPAIR AND MAINTENANCE OF AWC-II BUILDING AT DAKHINAPUR

Block : Kukudakhandi, Gram Panchayat : Dakhinapur

Created By:PALLAVI SWAIN

Item 1

Dismantling (AR1603): Dismantling brick or stone masonry in lime or cement mortar under 3m. height including stacking the useful materials for reuse and removing the debris within 50m. Lead and as per direction of Engineer-in-Charge.

Sub-Item of Work

Dismantling brick or stone masonry under 3m.

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	4.5	Per day	462	2079	0
LR001 : Male mulia	4	Per day	462	1848	0

Total Amount (a+b+c)

3927

Total GST (a)

0

LABOUR CESS @ 1% (+)

39.27

Grand Total

3966.27

Say For Unit 1 (Grand Total/2.83)

1401.5088339223

Item 2

Earth Work (AR0102aa): Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge

Sub-Item of Work

Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	25.8	Per day	462	11919.6	0
LR001 : Male mulia	25.8	Per day	462	11919.6	0

Total Amount (a+b+c)

23839.2

Total GST (a)

0

LABOUR CESS @ 1% (+)

238.392

Grand Total

24077.592

Say For Unit 1 (Grand Total/100)

240.77592

Item 3

Earth Work (AR0115): Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

Filling foundation and plinth with sand well watered and rammed

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	62.86	6286	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	471.31	47131	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	205.25	20525	0

Total Amount (a+b+c)

79652.32

Total GST (a)

0

LABOUR CESS @ 1% (+)

796.5232

Grand Total

80448.8432

Say For Unit 1 (Grand Total/100)

804.488432

Item 4

Concrete (AR0303): Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR025 : Mason	0.18	Per day	562	101.16	0
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	2.5	Per day	462	1155	0
BRM340 : Cement	2.29	1 Qntl.	568.23	1301.2467	234.224406
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	66.23	31.7904	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	995.25	955.44	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	30.732	70.37628	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	341.11	163.7328	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	341.11	327.4656	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	205.25	98.52	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	269.5	258.72	0

Total Amount (a+b+c)	5110.25178				
Total GST (a)	234.224406				
LABOUR CESS @ 1% (+)	53.44476186				
Grand Total	5397.92094786				
Say For Unit 1 (Grand Total/1)	5397.92094786				

Item 5

Concrete (AR0307): Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.

Sub-Item of Work

Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	3.2	Per day	462	1478.4	0
LR025 : Mason	0.68	Per day	562	382.16	0
BRM340 : Cement	3.23	1 Qntl.	568.23	1835.3829	330.368922
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	66.23	29.8035	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	1396.62	1256.958	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST

BRM340 : Cement	3.23	1 Qntl.	30.732	99.26436	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	471.31	212.0895	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	341.11	306.999	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	205.25	92.3625	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	269.5	242.55	0

Total Amount (a+b+c)	6582.76976
Total GST (a)	330.368922
LABOUR CESS @ 1% (+)	69.13138682
Grand Total	6982.27006882
Say For Unit 1 (Grand Total/1)	6982.27006882

Item 6
Masonry Brick Work (AR0603ei): Brickwork with C.B. Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ±8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.
Sub-Item of Work C.B. Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in superstructure

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.14	Per day	462	64.68	0
BRMMR0025 : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK	1	1 Cum	33	33	0
BRM002 : Well burnt clamp burnt bricks (23 Cm. x 11Cm. x 8Cm.) having crushing strength not less than 35 Kg./Cm ² with dimensional tolerance ± 8 percent.	400	1000 Nos	4.11387	1645.548	0
LR001 : Male mulia	2.96	Per day	462	1367.52	0
LR025 : Mason	1.05	Per day	562	590.1	0
LR044 : Mason	0.35	Per day	612	214.2	0

BRM340 : Cement	0.672	1 Qntl.	568.23	381.85056	68.7331008
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	66.23	18.5444	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM002 : Well burnt clamp burnt bricks (23 Cm. x 11Cm. x 8Cm.) having crushing strength not less than 35 Kg./Cm2 with dimensional tolerance \pm 8 percent.	400	1000 Nos	0.8091	323.64	0
BRM340 : Cement	0.672	1 Qntl.	30.732	20.651904	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	471.31	131.9668	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM002 : Well burnt clamp burnt bricks (23 Cm. x 11Cm. x 8Cm.) having crushing strength not less than 35 Kg./Cm2 with dimensional tolerance \pm 8 percent.	400	1000 Nos	0.04025	16.1	0
BRM340 : Cement	0.672	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	205.25	57.47	0

Total Amount (a+b+c)	4865.271664
Total GST (a)	68.7331008
LABOUR CESS @ 1% (+)	49.340047648
Grand Total	4983.344812448
Say For Unit 1 (Grand Total/1)	4983.344812448

Item 7

Flooring (AR0817a): Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge

Sub-Item of Work

Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRMMR0027 : Wax Polish	10	1 Sqm	8.5	85	0
BRM130 : Tiles up to 30cm x 30cm / 40cm x 40cm special plain / printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755	10	1 Sqm.	450.08	4500.8	0
LR044 : Mason	3.25	Per day	612	1989	0
LR001 : Male mulia	3.25	Per day	462	1501.5	0

LR008 : Sangi mulia	7.6	Per day	512	3891.2	0
BRM340 : Cement	1.375	1 Qntl.	568.23	781.31625	140.636925
BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	66.23	9.9345	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM130 : Tiles up to 30cm x 30cm / 40cm x 40cm special plain / printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755	10	1 Sqm.	11.2375001	112.375001	0
BRM340 : Cement	1.375	1 Qntl.	30.732	42.2565	0
BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	341.11	51.1665	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM130 : Tiles up to 30cm x 30cm / 40cm x 40cm special plain / printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755	10	1 Sqm.	0	0	0
BRM340 : Cement	1.375	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	205.25	30.7875	0

Total Amount (a+b+c)	12995.336251
Total GST (a)	140.636925
LABOUR CESS @ 1% (+)	131.35973176
Grand Total	13267.33290776
Say For Unit 1 (Grand Total/10)	1326.733290776

Item 8

Flooring (AR0816): Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor , treads or steps and landing on a 25mm thick bed of cement mortar 1:1 (1cement: 1sand) jointed with neat cement slurry mixed with pigment to match the shades of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.

Sub-Item of Work

Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRMMR0027 : Wax Polish	10	1 Sqm	8.5	85	0

BRM130 : Tiles up to 30cm x 30cm / 40cm x 40cm special plain / printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755	10	1 Sqm.	450.08	4500.8	0
LR001 : Male mulia	2.16	Per day	462	997.92	0
LR044 : Mason	2.16	Per day	612	1321.92	0
LR008 : Sangi mulia	5.5	Per day	512	2816	0
BRM340 : Cement	2.737	1 Qntl.	568.23	1555.24551	279.9441918
BRM028 : Screened and washed sharp sand for mortar	0.13	1 Cum	66.23	8.6099	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM130 : Tiles up to 30cm x 30cm / 40cm x 40cm special plain / printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755	10	1 Sqm.	11.2375001	112.375001	0
BRM340 : Cement	2.737	1 Qntl.	30.732	84.113484	0
BRM028 : Screened and washed sharp sand for mortar	0.13	1 Cum	341.11	44.3443	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM130 : Tiles up to 30cm x 30cm / 40cm x 40cm special plain / printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755	10	1 Sqm.	0	0	0
BRM340 : Cement	2.737	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.13	1 Cum	205.25	26.6825	0

Total Amount (a+b+c)	11553.010695
Total GST (a)	279.9441918
LABOUR CESS @ 1% (+)	118.329548868
Grand Total	11951.284435668
Say For Unit 1 (Grand Total/10)	1195.1284435668

Item 9

Painting (AR0903i): Painting two coats of enamel paint in outer surface paint including all costs of labour, Paint and brushes required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)

Sub-Item of Work

Painting two coats of enamel paint in outer surface paint (outer surface)

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR048 : Painter/ Polisher	1.25	Per day	612	765	0
LR001 : Male mulia	1.1	Per day	462	508.2	0
BRM141 : Enamel paint	1.1625	1 Litre	205.34	238.70775	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM141 : Enamel paint	1.1625	1 Litre	0.30732	0.3572595	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM141 : Enamel paint	1.1625	1 Litre	0	0	0

Total Amount (a+b+c)	1512.2650095				
Total GST (a)	0				
LABOUR CESS @ 1% (+)	15.122650095				
Grand Total	1527.387659595				
Say For Unit 1 (Grand Total/9.3)	164.23523221452				

Item 10
Plastering (AR1014): 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.
Sub-Item of Work 16mm thick cement Plaster in CM (1:6) over brick work in inside.

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.11	Per day	462	50.82	0
LR001 : Male mulia	0.13	Per day	462	60.06	0
LR025 : Mason	0.16	Per day	562	89.92	0
BRM340 : Cement	0.043	1 Qntl.	568.23	24.43389	4.3981002
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	66.23	1.19214	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.043	1 Qntl.	30.732	1.321476	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	341.11	6.13998	0

c) Royalty Rate Details					
--------------------------------	--	--	--	--	--

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.043	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	205.25	3.6945	0

Total Amount (a+b+c)	237.581986				
Total GST (a)	4.3981002				
LABOUR CESS @ 1% (+)	2.419800862				
Grand Total	244.399887062				
Say For Unit 1 (Grand Total/1)	244.399887062				

Item 11

Painting (AR0918i): Finishing wall waterproofing cement paint on the outer surface of approved shade on new work two coats to give an even shade including all costs of labour, Paint and Brushes required for the work, etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work

Two coat waterproofing cement paint on the outer surface

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR001 : Male mulia	0.32	Per day	462	147.84	0
LR048 : Painter/ Polisher	0.22	Per day	612	134.64	0
BRM143 : Cement paint	2.5	1 Kg.	47.83	119.575	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM143 : Cement paint	2.5	1 Kg.	0.30732	0.7683	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM143 : Cement paint	2.5	1 Kg.	0	0	0

Total Amount (a+b+c)	402.8233				
Total GST (a)	0				
LABOUR CESS @ 1% (+)	4.028233				
Grand Total	406.851533				
Say For Unit 1 (Grand Total/10)	40.6851533				

Item 12

miscellaneous (ARM295): Supplying, fitting and fixing of 5.5mm thick hexagonal Aluminum jally in windows as single groove, double groove and tapered clip as horizontal and vertical members for fixing of aluminum jally and jointing angle conforming to standard Aluminium sections etc. complete. (New miscellaneous items) and as directed by Engineer-in-Charge.

Sub-Item of Work

Supplying, fitting and fixing of 5.5mm thick hexagoanal Aluminum jally in windows as single groove, double groove and tapered clip as horizontal and vertical members for fixing of aluminum jally and jointing angle conforming to standard Aluminium sections

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRMM295 : Supplying, fitting and fixing of 5.5mm thick hexagoanal Aluminum jally in windows as single groove, double groove and tapered clip as horizontal and vertical members for fixing of aluminum jally and jointing angle conforming to standard Aluminium sections etc. complete. (New miscellaneous items)	1	1 Sqm	1841	1841	0

Total Amount (a+b+c)					1841
Total GST (a)					0
Grand Total					1841
Say For Unit 1 (Grand Total/1)					1841

Item 13

miscellaneous (ARM053): Labour only for fixing in position flush shutters fixtures of any thickness and any quality.(Doors and Window) and as directed by Engineer-in-Charge.

Sub-Item of Work

Labour only for fixing in position flush shutters fixtures of any thickness and any quality.(Doors and Window) and as directed by Engineer-in-Charge.

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRMM053 : Labour only for fixing in position flush shutters fixtures of any thickness and any quality.(Doors and Window)	1	Sqm	58.82	58.82	0

Total Amount (a+b+c)					58.82
Total GST (a)					0
Grand Total					58.82
Say For Unit 1 (Grand Total/1)					58.82

ASWIN SUBUDHI
JE
Kukudakhandi Block

ANURAG RATH
AEE
Kukudakhandi Block

PALLAVI SWAIN
BDO
Kukudakhandi Block