

Analysis

**OD/362/3465/275252/408165/00065158 : Construction of CC road from Bimala Temple to
Taradevi road of Mangalajodi G.P.
Block : Tangi, Gram Panchayat : Mangalajodi
Created By: Rumana Jafri**

Item 1
Earth Work (AR0115): Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work Filling foundation and plinth with sand well watered and rammed

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	56.19	5619	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	1091.91	109191	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	75.25	7525	0

Total Amount (a+b+c)	128045.32
Total GST (a)	0
LABOUR CESS @ 1% (+)	1280.4532
Grand Total	129325.7732
Say For Unit 1 (Grand Total/100)	1293.257732

Item 2
Concrete (AR0303): Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST

LR025 : Mason	0.18	Per day	562	101.16	0
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	2.5	Per day	462	1155	0
BRM340 : Cement	2.29	1 Qntl.	544.6	1247.134	224.48412
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	62.58	30.0384	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	995.25	955.44	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	24.787	56.76223	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	1091.91	524.1168	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	341.11	327.4656	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	75.25	36.12	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	279.5	268.32	0

Total Amount (a+b+c)	5348.35703
Total GST (a)	224.48412
LABOUR CESS @ 1% (+)	55.7284115
Grand Total	5628.5695615
Say For Unit 1 (Grand Total/1)	5628.5695615

Item 3

R.C.C. Work (AR0410c): Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc

Sub-Item of Work

R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	58374.79	1558.606893	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	1.26	1Mtr.	30.81	38.8206	0
LR008 : Sangi mulia	0.5	Per day	512	256	0
LR027 : Carpenter	0.5	Per day	562	281	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	198.296	5.2945032	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	198.296	1.21753744	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	0	0	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	0	0	0

Total Amount (a+b+c)	2140.93953364				
Total GST (a)	0				
LABOUR CESS @ 1% (+)	21.4093953364				
Grand Total	2162.3489289764				
Say For Unit 1 (Grand Total/10)	216.23489289764				

Item 4
Earth Work (AR0110): Fine dressing of earth work in ordinary or hard soil in road formaton according to the direction of the department including cutting or filling earth upto 0.15m depth of surface.
Sub-Item of Work Fine dressing of earth work in ordinary or hard soil in road formation

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR001 : Male mulia	1	Per day	462	462	0

Total Amount (a+b+c)	462				
Total GST (a)	0				
LABOUR CESS @ 1% (+)	4.62				
Grand Total	466.62				
Say For Unit 1 (Grand Total/100)	4.6662				

Item 5
Concrete (AR0307): Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaicon and direction of Engineer-in charge.
Sub-Item of Work Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	3.2	Per day	462	1478.4	0
LR025 : Mason	0.68	Per day	562	382.16	0
BRM340 : Cement	3.23	1 Qntl.	544.6	1759.058	316.63044
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	62.58	28.161	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	1372.71	1235.439	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	24.787	80.06201	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	1091.91	491.3595	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	341.11	306.999	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	75.25	33.8625	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	279.5	251.55	0

Total Amount (a+b+c)	6693.85101
Total GST (a)	316.63044
LABOUR CESS @ 1% (+)	70.1048145
Grand Total	7080.5862645
Say For Unit 1 (Grand Total/1)	7080.5862645

SUBHASHREE SAMANTARAY
JE
Tangi Block

ASHOK KUMAR NANDA
AEE
Tangi Block

Rumana Jafri
BDO
Tangi Block