

Analysis

OD/346/3307/116276/393076/00066817 : R/R OF BASUKHUNTA CC ROAD TO BASUKHUNTA
PRY,SCHOOL

Block : Remuna, Gram Panchayat : Kharid Mukhura

Created By:Sourav Sarthak Mohapatra

Item 1
Earth Work (AR0102aa): Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge
Sub-Item of Work Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	25.8	Per day	462	11919.6	0
LR001 : Male mulia	25.8	Per day	462	11919.6	0
Total Amount (a+b+c)				23839.2	
Total GST (a)				0	
OVERHEAD CHARGES @ 7.5% (+)				1787.94	
CONTRACTOR PROFIT @ 7.5% (+)				1922.0355	
LABOUR CESS @ 1% (+)				275.491755	
Grand Total				27824.667255	
Say For Unit 1 (Grand Total/100)				278.24667255	

Item 2
Earth Work (AR0115): Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work Filling foundation and plinth with sand well watered and rammed

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	71.94	7194	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0
b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	536.41	53641	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	427.25	42725	0

Total Amount (a+b+c)	109270.32				
Total GST (a)	0				
OVERHEAD CHARGES @ 7.5% (+)	8195.274				
CONTRACTOR PROFIT @ 7.5% (+)	8809.91955				
LABOUR CESS @ 1% (+)	1262.7551355				
Grand Total	127538.2686855				
Say For Unit 1 (Grand Total/100)	1275.382686855				

Item 3

Concrete (AR0309a): Cement Concrete (1:3:6) with 12mm size hard granite (Hand Broken) chips including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.

Sub-Item of Work

Cement Concrete (1:3:6) with 12mm size hard broken granite Hand Broken chips

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM057 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve)(Hand broken)	0.9	1 Cum.	1050	945	0
LR025 : Mason	0.68	Per day	562	382.16	0
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	3.2	Per day	462	1478.4	0
BRM340 : Cement	2.15	1 Qntl.	537.2	1154.98	207.8964
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM057 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve)(Hand broken)	0.9	1 Cum.	835.87	752.283	0
BRM340 : Cement	2.15	1 Qntl.	30.732	66.0738	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	536.41	241.3845	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM057 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve)(Hand broken)	0.9	1 Cum.	522.5	470.25	0
BRM340 : Cement	2.15	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	427.25	192.2625	0

Total Amount (a+b+c)	6364.1898
Total GST (a)	207.8964
OVERHEAD CHARGES @ 7.5% (+)	492.906465
CONTRACTOR PROFIT @ 7.5% (+)	529.874449875
LABOUR CESS @ 1% (+)	75.94867114875
Grand Total	7670.8157860237
Say For Unit 1 (Grand Total/1)	7670.8157860237

Item 4

Concrete (AR0307): Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.

Sub-Item of Work

Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	3.2	Per day	462	1478.4	0
LR025 : Mason	0.68	Per day	562	382.16	0
BRM340 : Cement	3.23	1 Qntl.	537.2	1735.156	312.32808
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	1396.62	1256.958	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	30.732	99.26436	0

BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	536.41	241.3845	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	835.87	752.283	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	427.25	192.2625	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	522.5	470.25	0

Total Amount (a+b+c)	7289.51436
Total GST (a)	312.32808
OVERHEAD CHARGES @ 7.5% (+)	570.138183
CONTRACTOR PROFIT @ 7.5% (+)	612.898546725
LABOUR CESS @ 1% (+)	87.84879169725
Grand Total	8872.7279614222
Say For Unit 1 (Grand Total/1)	8872.7279614222

Item 5

R.C.C. Work (AR0410c): Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc

Sub-Item of Work

R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	58374.79	1558.606893	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	1.26	1Mtr.	30.81	38.8206	0
LR008 : Sangi mulia	0.5	Per day	512	256	0
LR027 : Carpenter	0.5	Per day	562	281	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	198.296	5.2945032	0

BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	198.296	1.21753744	0
---	---------	-------	---------	------------	---

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	0	0	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	0	0	0

Total Amount (a+b+c)	2140.93953364				
Total GST (a)	0				
OVERHEAD CHARGES @ 7.5% (+)	160.570465023				
CONTRACTOR PROFIT @ 7.5% (+)	172.61324989972				
LABOUR CESS @ 1% (+)	24.741232485627				
Grand Total	2498.8644810484				
Say For Unit 1 (Grand Total/10)	249.88644810484				

SUSHREE SANGITA MAHANTA
JE
Remuna Block

AJAY KUMAR BEHERA
AEE
Remuna Block

Sourav Sarthak Mohapatra
BDO
Remuna Block