

Analysis

OD/356/3402/118478/401510/00069412 : Repair and maintenance of Takuathenga Primary School at Takuathenga.

Block : Rasulpur, Gram Panchayat : Nathuabar

Created By: Satyananda Dash

Item 1
Other Building Items. (AR1901B): Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)
Sub-Item of Work Vitrified Tile 600mmx600mm Plain Ivory

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM174 : White Cement.	0.076	1Qntl	2006	152.456	0
BRM340 : Cement	1.074	1 Qntl.	543.88	584.12712	105.1428816
BRM028 : Screened and washed sharp sand for mortar	0.21	1 Cum	76.88	16.1448	0
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	651.08	6510.8	0
LR001 : Male mulia	2.16	Per day	462	997.92	0
LR044 : Mason	2.16	Per day	612	1321.92	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM174 : White Cement.	0.076	1Qntl	24.787	1.883812	0
BRM340 : Cement	1.074	1 Qntl.	24.787	26.621238	0
BRM028 : Screened and washed sharp sand for mortar	0.21	1 Cum	341.11	71.6331	0
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	9.6011111	96.011111	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM174 : White Cement.	0.076	1Qntl	0	0	0
BRM340 : Cement	1.074	1 Qntl.	0	0	0

BRM028 : Screened and washed sharp sand for mortar	0.21	1 Cum	274.25	57.5925	0
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm conforming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	0	0	0

Total Amount (a+b+c)	9837.109681
Total GST (a)	105.1428816
OVERHEAD CHARGES @ 7.5% (+)	745.668942195
CONTRACTOR PROFIT @ 7.5% (+)	801.59411285963
LABOUR CESS @ 1% (+)	114.89515617655
Grand Total	11604.410773831
Say For Unit 1 (Grand Total/10)	1160.4410773831

Item 2

Dismantling (AR1620): Dismantling and removing 2.5 cm thick grading concrete from roof slab cleaning the surface lowering and removing the debris within 50m lead and as per direction of Engineer-in-Charge.

Sub-Item of Work

Dismantling and removing 2.5 cm thick grading concrete from roof

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.5	Per day	462	693	0
LR001 : Male mulia	0.75	Per day	462	346.5	0

Total Amount (a+b+c)	1039.5
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	77.9625
CONTRACTOR PROFIT @ 7.5% (+)	83.8096875
LABOUR CESS @ 1% (+)	12.012721875
Grand Total	1213.284909375
Say For Unit 1 (Grand Total/9.3)	130.46074294355

Item 3

Concrete (AR0318): 4cm thick grading concrete (1:2:4) on roof slab with 12mm size hard granite chips (Crusher Broken) including hoisting and laying in position compacting and curing for the proper period with cost conveyance, royalty, taxes of all materials, labor and T&P required for the work etc. complete as per specification and direction of Engineer-in charge. (Old Work)

Sub-Item of Work

4cm thick grading concrete (1:2:4) on roof slab with 12mm size hard granite chips (Crusher Broken)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
------------	----------	------	------	--------	-----

LR001 : Male mulia	1.008	Per day	462	465.696	0
LR044 : Mason	0.165	Per day	612	100.98	0
BRM340 : Cement	0.1287	1 Qntl.	543.88	69.997356	12.59952408
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	76.88	1.38384	0
BRM064 : Granite stone broken chips of 4.7 mm size passing through 6.7 mm sieve (crusher broken.) and retained on 2.36 mm sieve.	0.018	1 Cum.	850.2	15.3036	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.018	1 Cum.	1386.4	24.9552	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.1287	1 Qntl.	24.787	3.1900869	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	341.11	6.13998	0
BRM064 : Granite stone broken chips of 4.7 mm size passing through 6.7 mm sieve (crusher broken.) and retained on 2.36 mm sieve.	0.018	1 Cum.	835.87	15.04566	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.018	1 Cum.	835.87	15.04566	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.1287	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	274.25	4.9365	0
BRM064 : Granite stone broken chips of 4.7 mm size passing through 6.7 mm sieve (crusher broken.) and retained on 2.36 mm sieve.	0.018	1 Cum.	444.5	8.001	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.018	1 Cum.	444.5	8.001	0

Total Amount (a+b+c)	738.6758829
Total GST (a)	12.59952408
OVERHEAD CHARGES @ 7.5% (+)	56.345655235
CONTRACTOR PROFIT @ 7.5% (+)	60.571579687762
LABOUR CESS @ 1% (+)	8.6819264219126
Grand Total	876.87456861318
Say For Unit 1 (Grand Total/1)	876.87456861318

Bandana Tanty
JE
Rasulpur Block

AEsabitadhal
AEE
Rasulpur Block

Satyananda Dash
BDO
Rasulpur Block