

Analysis

**OD/354/3380/117905/411499/00065551 : Repair & Maintenance of AWC Building at
Kaniapalli under Dhunkapada GP
Block : Polosara, Gram Panchayat : Dhumkapada
Created By:SASI BHUSAN MAHAPATRO**

Item 1					
Concrete (AR0303a): Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.					
Sub-Item of Work Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal					
a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	2.5	Per day	462	1155	0
LR025 : Mason	0.18	Per day	562	101.16	0
BRM340 : Cement	2.29	1 Qntl.	567.71	1300.0559	234.010062
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	66.23	31.7904	0
BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	1 Cum.	787.36	755.8656	0
b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	30.732	70.37628	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	341.11	163.7328	0
BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	1 Cum.	341.11	327.4656	0
c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	40.25	19.32	0
BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	1 Cum.	149.5	143.52	0
Total Amount (a+b+c)				4715.08658	
Total GST (a)				234.010062	
OVERHEAD CHARGES @ 7.5% (+)				371.18224815	
CONTRACTOR PROFIT @ 7.5% (+)				399.02091676125	
LABOUR CESS @ 1% (+)				57.192998069113	

Grand Total	5776.4928049804
Say For Unit 1 (Grand Total/1)	5776.4928049804

Item 2

Concrete (AR0307): Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.

Sub-Item of Work

Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	3.2	Per day	462	1478.4	0
LR025 : Mason	0.68	Per day	562	382.16	0
BRM340 : Cement	3.23	1 Qntl.	567.71	1833.7033	330.066594
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	66.23	29.8035	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	1396.62	1256.958	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	30.732	99.26436	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	341.11	153.4995	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	341.11	306.999	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	40.25	18.1125	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	149.5	134.55	0

Total Amount (a+b+c)

6340.25016

Total GST (a)	330.066594
OVERHEAD CHARGES @ 7.5% (+)	500.27375655
CONTRACTOR PROFIT @ 7.5% (+)	537.79428829125
LABOUR CESS @ 1% (+)	77.083847988413
Grand Total	7785.4686468297
Say For Unit 1 (Grand Total/1)	7785.4686468297

Item 3

Masonry Brick Work (AR0603bi): Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work

Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.14	Per day	462	64.68	0
BRMMR0025 : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK	1	1 Cum	33	33	0
LR001 : Male mulia	2.82	Per day	462	1302.84	0
LR025 : Mason	1.05	Per day	562	590.1	0
LR044 : Mason	0.35	Per day	612	214.2	0
BRM340 : Cement	0.672	1 Qntl.	567.71	381.50112	68.6702016
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	66.23	18.5444	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance ± 2 %	350	1000 Nos	5.14255	1799.8925	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.672	1 Qntl.	30.732	20.651904	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	341.11	95.5108	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance ± 2 %	350	1000 Nos	1.01135	353.9725	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.672	1 Qntl.	0	0	0

BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	40.25	11.27	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	350	1000 Nos	0	0	0

Total Amount (a+b+c)	4886.163224
Total GST (a)	68.6702016
OVERHEAD CHARGES @ 7.5% (+)	371.61250692
CONTRACTOR PROFIT @ 7.5% (+)	399.483444939
LABOUR CESS @ 1% (+)	57.25929377459
Grand Total	5783.1886712336
Say For Unit 1 (Grand Total/1)	5783.1886712336

Item 4

Plastering (AR1014): 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.

Sub-Item of Work
16mm thick cement Plaster in CM (1:6) over brick work in inside.

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.11	Per day	462	50.82	0
LR001 : Male mulia	0.13	Per day	462	60.06	0
LR025 : Mason	0.16	Per day	562	89.92	0
BRM340 : Cement	0.043	1 Qntl.	567.71	24.41153	4.3940754
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	66.23	1.19214	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.043	1 Qntl.	30.732	1.321476	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	341.11	6.13998	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.043	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	40.25	0.7245	0

Total Amount (a+b+c)	234.589626
Total GST (a)	4.3940754
OVERHEAD CHARGES @ 7.5% (+)	17.923777605

CONTRACTOR PROFIT @ 7.5% (+)	19.268060925375
LABOUR CESS @ 1% (+)	2.7617553993038
Grand Total	278.93729532968
Say For Unit 1 (Grand Total/1)	278.93729532968

Indramani Sahu
JE
Polosara Block

Laxmi Narayan Pattanayak
AEE
Polosara Block

SASI BHUSAN MAHAPATRO
BDO
Polosara Block