

Analysis

OD/353/3357/117456/414691/00066955 : Construction of paver block road from hanuman temple to harijan sahi
Block : Gosani, Gram Panchayat : Tatipetti
Created By:GOURA CHANDRA PATNAIK

Item 1
Earth Work (AR0122Ai): Earth work in all kinds of soil within 50m, initial lead and 1.5m, initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per direction of the Engineer-in-charge.
Sub-Item of Work Earth work in all kinds of soil within 50m, initial lead and 1.5m, initial lift

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	23.6767	Per day	462	10938.6354	0
LR001 : Male mulia	23.6767	Per day	462	10938.6354	0
Total Amount (a+b+c)				21877.2708	
Total GST (a)					0
OVERHEAD CHARGES @ 7.5% (+)				1640.79531	
CONTRACTOR PROFIT @ 7.5% (+)				1763.85495825	
LABOUR CESS @ 1% (+)				252.8192106825	
Grand Total				25534.740278933	
Say For Unit 1 (Grand Total/100)				255.34740278933	

Item 2
Earth Work (AR0115): Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work Filling foundation and plinth with sand well watered and rammed

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	71.94	7194	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	666.61	66661	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	279.25	27925	0

Total Amount (a+b+c)	107490.32				
Total GST (a)	0				
OVERHEAD CHARGES @ 7.5% (+)	8061.774				
CONTRACTOR PROFIT @ 7.5% (+)	8666.40705				
LABOUR CESS @ 1% (+)	1242.1850105				
Grand Total	125460.6860605				
Say For Unit 1 (Grand Total/100)	1254.606860605				

Item 3
miscellaneous (ARM287): Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.
Sub-Item of Work Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	0.03	1 Cum	71.94	2.1582	0
BRMM287 : Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items)	1	1 Sqm	608.4	608.4	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	0.03	1 Cum	666.61	19.9983	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	0.03	1 Cum	279.25	8.3775	0
Total Amount (a+b+c)	638.934				
Total GST (a)	0				
Grand Total	125460.6860605				
Say For Unit 1 (Grand Total/1)	125460.6860605				

Item 4

Road Work (AR1339): Construction of granular sub-base by providing Close graded Granular subbase Grading-III material as per table 400-1, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with vibratory roller to achieve the desired density complete including cost conveyance, royalty, taxes, cess etc. of all materials, etc. as per Clause 401 of MoRT&H Specifications for Road & Bridge works (Last Revision).

Sub-Item of Work

Construction of granular sub-base by providing Close graded Granular subbase Grading-III material as per table 400-1

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRMMR0037 : Cost of water	18	KL	10	180	0
BRM026 : Stone screened Dust passing through 2.36 mm sieve and retained on 0.075 mm sieve	201.6	1 Cum	136.33	27484.128	0
BRM064 : Granite stone broken chips of 4.7 mm size passing through 6.7 mm sieve (crusher broken.) and retained on 2.36 mm sieve.	48	1 Cum.	850.2	40809.6	0
BRM062 : Granite Stone broken chips 6.7mm size (Passing through 11.2mm sieve & retained on 2.8mm sieve)	134.4	1 Cum.	957.46	128682.624	0
PM027 : Truck mounted water tanker Water transport 6KL	3	per hour	900.84	2702.52	0
PM029 : Rotavator Mixing 25cum/hour	12	per hour	16	192	0
PM028 : Tractor Pulling 50HP	12	per hour	357.55	4290.6	0
PM022 : Vibratory Roller 8-10 tonne GSB 60cum/hour	6	per hour	1538.54	9231.24	0
PM009 : Motor Grader 3.35meter blade GSB 50cum/hour	6	per hour	2391.39	14348.34	0
LR001 : Male mulia	10	Per day	462	4620	0
LR025 : Mason	2	Per day	562	1124	0
LR010 : Mate	0.48	Per day	512	245.76	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM026 : Stone screened Dust passing through 2.36 mm sieve and retained on 0.075 mm sieve	201.6	1 Cum	471.31	95016.096	0
BRM064 : Granite stone broken chips of 4.7 mm size passing through 6.7 mm sieve (crusher broken.) and retained on 2.36 mm sieve.	48	1 Cum.	471.31	22622.88	0
BRM062 : Granite Stone broken chips 6.7mm size (Passing through 11.2mm sieve & retained on 2.8mm sieve)	134.4	1 Cum.	471.31	63344.064	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
------------	----------	------	------	--------	-----

BRM026 : Stone screened Dust passing through 2.36 mm sieve and retained on 0.075 mm sieve	201.6	1 Cum	160.25	32306.4	0
BRM064 : Granite stone broken chips of 4.7 mm size passing through 6.7 mm sieve (crusher broken.) and retained on 2.36 mm sieve.	48	1 Cum.	269.5	12936	0
BRM062 : Granite Stone broken chips 6.7mm size (Passing through 11.2mm sieve & retained on 2.8mm sieve)	134.4	1 Cum.	269.5	36220.8	0

Total Amount (a+b+c)	496357.052
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	37226.7789
CONTRACTOR PROFIT @ 7.5% (+)	40018.7873175
LABOUR CESS @ 1% (+)	5736.026182175
Grand Total	579338.64439968
Say For Unit 1 (Grand Total/300)	1931.1288146656

Item 5

Concrete (AR0307): Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.

Sub-Item of Work

Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	3.2	Per day	462	1478.4	0
LR025 : Mason	0.68	Per day	562	382.16	0
BRM340 : Cement	3.23	1 Qntl.	569.86	1840.6478	331.316604
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	1396.62	1256.958	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	48.567	156.87141	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	666.61	299.9745	0

BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	471.31	424.179	0
--	-----	-----------	--------	---------	---

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	279.25	125.6625	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	269.5	242.55	0

Total Amount (a+b+c)	6888.79921
Total GST (a)	331.316604
OVERHEAD CHARGES @ 7.5% (+)	541.50868605
CONTRACTOR PROFIT @ 7.5% (+)	582.12183750375
LABOUR CESS @ 1% (+)	83.437463375537
Grand Total	8427.1838009293
Say For Unit 1 (Grand Total/1)	8427.1838009293

Item 6

R.C.C. Work (AR0410c): Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc

Sub-Item of Work

R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	58374.79	1558.606893	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	1.26	1Mtr.	30.81	38.8206	0
LR008 : Sangi mulia	0.5	Per day	512	256	0
LR027 : Carpenter	0.5	Per day	562	281	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	388.536	10.3739112	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	388.536	2.38561104	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	0	0	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	0	0	0
Total Amount (a+b+c)	2147.18701524				
Total GST (a)	0				
OVERHEAD CHARGES @ 7.5% (+)	161.039026143				
CONTRACTOR PROFIT @ 7.5% (+)	173.11695310372				
LABOUR CESS @ 1% (+)	24.813429944867				
Grand Total	2506.1564244316				
Say For Unit 1 (Grand Total/10)	250.61564244316				

SUBHAM SARANGI
JE
Gosani Block

SASMITA KUMARI JENA
AEE
Gosani Block

GOURA CHANDRA PATNAIK
BDO
Gosani Block