

## Analysis

**OD/346/3305/116231/393259/00068471 : repair and restoration of Badapalsa primary school arabandha**

**Block : Nilgiri, Gram Panchayat : Arbandh**

**Created By: Bikram Kishore Parida**

### Item 1

**Earth Work (AR0102aa):** Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge

Sub-Item of Work

**Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift**

#### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	25.8	Per day	462	11919.6	0
LR001 : Male mulia	25.8	Per day	462	11919.6	0

**Total Amount (a+b+c)**

23839.2

**Total GST (a)**

0

**OVERHEAD CHARGES @ 7.5% (+)**

1787.94

**CONTRACTOR PROFIT @ 7.5% (+)**

1922.0355

**LABOUR CESS @ 1% (+)**

275.491755

**Grand Total**

27824.667255

**Say For Unit 1 (Grand Total/100)**

278.24667255

### Item 2

**Earth Work (AR0115):** Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

**Filling foundation and plinth with sand well watered and rammed**

#### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	71.94	7194	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0

#### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	406.21	40621	0

<b>c) Royalty Rate Details</b>					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	442.25	44225	0

<b>Total Amount (a+b+c)</b>	97750.32				
<b>Total GST (a)</b>	0				
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	7331.274				
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	7881.11955				
<b>LABOUR CESS @ 1% (+)</b>	1129.6271355				
<b>Grand Total</b>	114092.3406855				
<b>Say For Unit 1 (Grand Total/100)</b>	1140.923406855				

<b>Item 3</b>
<b>Concrete (AR0303):</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work <b>Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal</b>

<b>a) Specific Rate Details</b>					
Particular	Quantity	Unit	Rate	Amount	GST
LR025 : Mason	0.18	Per day	562	101.16	0
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	2.5	Per day	462	1155	0
BRM340 : Cement	2.29	1 Qntl.	537.2	1230.188	221.43384
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	76.88	36.9024	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	995.25	955.44	0

<b>b) Carriage Rate Details</b>					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	48.567	111.21843	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	406.21	194.9808	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	953.91	915.7536	0

<b>c) Royalty Rate Details</b>					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	442.25	212.28	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	522.5	501.6	0

<b>Total Amount (a+b+c)</b>	6061.32323
<b>Total GST (a)</b>	221.43384
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	471.20678025
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	506.54728876875
<b>LABOUR CESS @ 1% (+)</b>	72.605111390187
<b>Grand Total</b>	7333.1162504089
<b>Say For Unit 1 (Grand Total/1)</b>	7333.1162504089

#### Item 4

**Concrete (AR0307):** Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.

Sub-Item of Work

**Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum**

#### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>LR002</b> : Female mulia	1.4	Per day	462	646.8	0
<b>LR001</b> : Male mulia	3.2	Per day	462	1478.4	0
<b>LR025</b> : Mason	0.68	Per day	562	382.16	0
<b>BRM340</b> : Cement	3.23	1 Qntl.	537.2	1735.156	312.32808
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0
<b>BRM056</b> : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	1396.62	1256.958	0

#### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	3.23	1 Qntl.	48.567	156.87141	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	406.21	182.7945	0
<b>BRM056</b> : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	953.91	858.519	0

#### c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	3.23	1 Qntl.	0	0	0

<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	442.25	199.0125	0
<b>BRM056</b> : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	522.5	470.25	0

<b>Total Amount (a+b+c)</b>	7401.51741
<b>Total GST (a)</b>	312.32808
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	578.53841175
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	621.92879263125
<b>LABOUR CESS @ 1% (+)</b>	89.143126943812
<b>Grand Total</b>	9003.4558213251
<b>Say For Unit 1 (Grand Total/1)</b>	9003.4558213251

### Item 5

**Masonry Brick Work (AR0603b):** Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm<sup>2</sup> with dimensional tolerance  $\pm 8$  percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work

**Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth**

#### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>LR002</b> : Female mulia	0.14	Per day	462	64.68	0
<b>LR001</b> : Male mulia	2.82	Per day	462	1302.84	0
<b>LR025</b> : Mason	1.05	Per day	562	590.1	0
<b>LR044</b> : Mason	0.35	Per day	612	214.2	0
<b>BRM340</b> : Cement	0.672	1 Qntl.	537.2	360.9984	64.979712
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.28	1 Cum	76.88	21.5264	0
<b>BRM005</b> : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm <sup>2</sup> with dimensional tolerance $\pm 2$ %	350	1000 Nos	5.14255	1799.8925	0

#### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	0.672	1 Qntl.	48.567	32.637024	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.28	1 Cum	406.21	113.7388	0
<b>BRM005</b> : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm <sup>2</sup> with dimensional tolerance $\pm 2$ %	350	1000 Nos	1.7476	611.66	0

<b>c) Royalty Rate Details</b>					
<b>Particular</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate</b>	<b>Amount</b>	<b>GST</b>
<b>BRM340</b> : Cement	0.672	1 Qntl.	0	0	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.28	1 Cum	442.25	123.83	0
<b>BRM005</b> : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	350	1000 Nos	0	0	0

<b>Total Amount (a+b+c)</b>	5236.103124
<b>Total GST (a)</b>	64.979712
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	397.5812127
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	427.3998036525
<b>LABOUR CESS @ 1% (+)</b>	61.260638523525
<b>Grand Total</b>	6187.324490876
<b>Say For Unit 1 (Grand Total/1)</b>	6187.324490876

### Item 6

**Flooring (AR0816):** Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor , treads or steps and landing on a 25mm thick bed of cement mortar 1:1 (1cement: 1sand) jointed with neat cement slurry mixed with pigment to match the shades of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.

Sub-Item of Work

**Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor**

### a) Specific Rate Details

<b>Particular</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate</b>	<b>Amount</b>	<b>GST</b>
<b>BRMMR0027</b> : Wax Polish	10	1 Sqm	8.5	85	0
<b>BRM130</b> : Tiles up to 30cm x 30cm / 40cm x 40cm special plain / printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755	10	1 Sqm.	450.08	4500.8	0
<b>LR001</b> : Male mulia	2.16	Per day	462	997.92	0
<b>LR044</b> : Mason	2.16	Per day	612	1321.92	0
<b>LR008</b> : Sangi mulia	5.5	Per day	512	2816	0
<b>BRM340</b> : Cement	2.737	1 Qntl.	537.2	1470.3164	264.656952
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.13	1 Cum	76.88	9.9944	0

### b) Carriage Rate Details

<b>Particular</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate</b>	<b>Amount</b>	<b>GST</b>
-------------------	-----------------	-------------	-------------	---------------	------------

<b>BRM130</b> : Tiles up to 30cm x 30cm / 40cm x 40cm special plain / printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755	10	1 Sqm.	22.6922231	226.922231	0
<b>BRM340</b> : Cement	2.737	1 Qntl.	48.567	132.927879	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.13	1 Cum	406.21	52.8073	0

### c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM130</b> : Tiles up to 30cm x 30cm / 40cm x 40cm special plain / printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755	10	1 Sqm.	0	0	0
<b>BRM340</b> : Cement	2.737	1 Qntl.	0	0	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.13	1 Cum	442.25	57.4925	0

<b>Total Amount (a+b+c)</b>	11672.10071
<b>Total GST (a)</b>	264.656952
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	895.25682465
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	962.40108649875
<b>LABOUR CESS @ 1% (+)</b>	137.94415573149
<b>Grand Total</b>	13932.35972888
<b>Say For Unit 1 (Grand Total/10)</b>	1393.235972888

### Item 7

**Flooring (AR0817aa):** Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.

Sub-Item of Work

**Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3)**

### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM131</b> : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	651.08	6510.8	0
<b>BRMMR0027</b> : Wax Polish	10	1 Sqm	8.5	85	0
<b>LR044</b> : Mason	3.25	Per day	612	1989	0
<b>LR001</b> : Male mulia	3.25	Per day	462	1501.5	0

<b>LR008</b> : Sangi mulia	7.6	Per day	512	3891.2	0
<b>BRM340</b> : Cement	1.375	1 Qntl.	537.2	738.65	132.957
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.15	1 Cum	76.88	11.532	0

**b) Carriage Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM131</b> : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	22.6922231	226.922231	0
<b>BRM340</b> : Cement	1.375	1 Qntl.	48.567	66.779625	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.15	1 Cum	406.21	60.9315	0

**c) Royalty Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM131</b> : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	0	0	0
<b>BRM340</b> : Cement	1.375	1 Qntl.	0	0	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.15	1 Cum	442.25	66.3375	0

<b>Total Amount (a+b+c)</b>	15148.652856
<b>Total GST (a)</b>	132.957
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	1146.1207392
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	1232.07979464
<b>LABOUR CESS @ 1% (+)</b>	176.5981038984
<b>Grand Total</b>	17836.408493738
<b>Say For Unit 1 (Grand Total/10)</b>	1783.6408493738

**Item 8**

**miscellaneous (ARM066):** Fitting and fixing of R.C.C. doors frame and as directed by Engineer-in-Charge.

Sub-Item of Work

**Fitting and fixing of R.C.C. doors frame and as directed by Engineer-in-Charge.**

**a) Specific Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRMM066</b> : Fitting and fixing of R.C.C. doors frame .	1	Each	119.84	119.84	0

<b>Total Amount (a+b+c)</b>	119.84
<b>Total GST (a)</b>	0
<b>Grand Total</b>	17836.408493738
<b>Say For Unit 1 (Grand Total/1)</b>	17836.408493738

**Ramesh Singh**  
**JE**  
**Nilgiri Block**

**Sarat kumar Upadhyay**  
**AEE**  
**Nilgiri Block**

**Bikram Kishore Parida**  
**BDO**  
**Nilgiri Block**