

Analysis

OD/356/3403/118505/400408/00064469 : CONST. OF BUS STAND SHED AT LEMBO
Block : Sukinda, Gram Panchayat : Lambo
Created By:Prangyan Primita Prusty

Item 1
Earth Work (AR0102aa): Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge
Sub-Item of Work Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	25.8	Per day	462	11919.6	0
LR001 : Male mulia	25.8	Per day	462	11919.6	0
Total Amount (a+b+c)				23839.2	
Total GST (a)					0
OVERHEAD CHARGES @ 7.5% (+)					1787.94
CONTRACTOR PROFIT @ 7.5% (+)					1922.0355
LABOUR CESS @ 1% (+)					275.491755
Grand Total					27824.667255
Say For Unit 1 (Grand Total/100)					278.24667255

Item 2
Earth Work (AR0115): Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work Filling foundation and plinth with sand well watered and rammed

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	71.94	7194	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	757.75	75775	0

c) Royalty Rate Details					

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	274.25	27425	0
Total Amount (a+b+c)				116104.32	
Total GST (a)					0
OVERHEAD CHARGES @ 7.5% (+)				8707.824	
CONTRACTOR PROFIT @ 7.5% (+)				9360.9108	
LABOUR CESS @ 1% (+)				1341.730548	
Grand Total				135514.785348	
Say For Unit 1 (Grand Total/100)				1355.14785348	

Item 3

Concrete (AR0303): Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work
Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR025 : Mason	0.18	Per day	562	101.16	0
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	2.5	Per day	462	1155	0
BRM340 : Cement	2.29	1 Qntl.	543.88	1245.4852	224.187336
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	76.88	36.9024	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	940.6	902.976	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	39.055	89.43595	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	757.75	363.72	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	822.85	789.936	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	274.25	131.64	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	444.5	426.72	0

Total Amount (a+b+c)	5889.77555
-----------------------------	------------

Total GST (a)	224.187336
OVERHEAD CHARGES @ 7.5% (+)	458.54721645
CONTRACTOR PROFIT @ 7.5% (+)	492.93825768375
LABOUR CESS @ 1% (+)	70.654483601338
Grand Total	7136.1028437351
Say For Unit 1 (Grand Total/1)	7136.1028437351

Item 4

Masonry Brick Work (AR0603b): Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work

Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.14	Per day	462	64.68	0
LR001 : Male mulia	2.82	Per day	462	1302.84	0
LR025 : Mason	1.05	Per day	562	590.1	0
LR044 : Mason	0.35	Per day	612	214.2	0
BRM340 : Cement	0.672	1 Qntl.	543.88	365.48736	65.7877248
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	76.88	21.5264	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance ± 2 %	350	1000 Nos	5.0305	1760.675	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.672	1 Qntl.	39.055	26.24496	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	757.75	212.17	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance ± 2 %	350	1000 Nos	1.01135	353.9725	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.672	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	274.25	76.79	0

BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	350	1000 Nos	0	0	0
---	-----	----------	---	---	---

Total Amount (a+b+c)	4988.68622
Total GST (a)	65.7877248
OVERHEAD CHARGES @ 7.5% (+)	379.08554586
CONTRACTOR PROFIT @ 7.5% (+)	407.5169617995
LABOUR CESS @ 1% (+)	58.410764524595
Grand Total	5899.4872169841
Say For Unit 1 (Grand Total/1)	5899.4872169841

Item 5

Masonry Brick Work (AR0603bi): Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm2 with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work

Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.14	Per day	462	64.68	0
BRMMR0025 : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK	1	1 Cum	33	33	0
LR001 : Male mulia	2.82	Per day	462	1302.84	0
LR025 : Mason	1.05	Per day	562	590.1	0
LR044 : Mason	0.35	Per day	612	214.2	0
BRM340 : Cement	0.672	1 Qntl.	543.88	365.48736	65.7877248
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	76.88	21.5264	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	350	1000 Nos	5.0305	1760.675	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.672	1 Qntl.	39.055	26.24496	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	757.75	212.17	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	350	1000 Nos	1.01135	353.9725	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.672	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	274.25	76.79	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	350	1000 Nos	0	0	0

Total Amount (a+b+c)	5021.68622
Total GST (a)	65.7877248
OVERHEAD CHARGES @ 7.5% (+)	381.56054586
CONTRACTOR PROFIT @ 7.5% (+)	410.1775867995
LABOUR CESS @ 1% (+)	58.792120774595
Grand Total	5938.0041982341
Say For Unit 1 (Grand Total/1)	5938.0041982341

Item 6

R.C.C. Work (AR0404Aa): Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)

Sub-Item of Work

Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
Combine :: R.C.C. Work (AR0404A)					
PM096 : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0
PM083 : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0
LR001 : Male mulia	1.3333	Per day	462	615.9846	0
LR025 : Mason	0.1	Per day	562	56.2	0
LR010 : Mate	0.0573	Per day	512	29.3376	0
BRM340 : Cement	3.4733	1 Qntl.	543.88	1889.058404	340.03051272
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1415.1	509.436	0

BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1382.29	746.4366	0
Combine :: R.C.C. Work (AR0410c)					
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	1Cum.	58374.79	233.79103395	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.189	1Mtr.	30.81	5.82309	0
LR008 : Sangi mulia	0.075	Per day	512	38.4	0
LR027 : Carpenter	0.075	Per day	562	42.15	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	39.055	135.6497315	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	757.75	340.9875	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	822.85	296.226	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	822.85	444.339	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	1Cum.	245.856	0.98465328	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.000921	1Mtr.	245.856	0.226433376	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	274.25	123.4125	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	444.5	160.02	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	444.5	240.03	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	1Cum.	0	0	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.000921	1Mtr.	0	0	0

Total Amount (a+b+c)	6314.909146106
Total GST (a)	340.03051272
OVERHEAD CHARGES @ 7.5% (+)	499.12047441195
CONTRACTOR PROFIT @ 7.5% (+)	536.55450999285
LABOUR CESS @ 1% (+)	76.906146432308

Grand Total	7767.5207896631
Say For Unit 1 (Grand Total/1)	7767.5207896631

Item 7

R.C.C. Work (AR0404Ab): Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Plinth band)

Sub-Item of Work

Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
Combine :: R.C.C. Work (AR0404A)					
PM096 : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0
PM083 : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0
LR001 : Male mulia	1.3333	Per day	462	615.9846	0
LR025 : Mason	0.1	Per day	562	56.2	0
LR010 : Mate	0.0573	Per day	512	29.3376	0
BRM340 : Cement	3.4733	1 Qntl.	543.88	1889.058404	340.03051272
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1415.1	509.436	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1382.29	746.4366	0
Combine :: R.C.C. Work (AR0410c)					
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.01335	1Cum.	58374.79	779.3034465	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.63	1Mtr.	30.81	19.4103	0
LR008 : Sangi mulia	0.25	Per day	512	128	0
LR027 : Carpenter	0.25	Per day	562	140.5	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	39.055	135.6497315	0

BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	757.75	340.9875	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	822.85	296.226	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	822.85	444.339	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.01335	1Cum.	245.856	3.2821776	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00307	1Mtr.	245.856	0.75477792	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	274.25	123.4125	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	444.5	160.02	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	444.5	240.03	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.01335	1Cum.	0	0	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00307	1Mtr.	0	0	0

Total Amount (a+b+c)	7064.78463752
Total GST (a)	340.03051272
OVERHEAD CHARGES @ 7.5% (+)	555.361136268
CONTRACTOR PROFIT @ 7.5% (+)	597.0132214881
LABOUR CESS @ 1% (+)	85.571895079961
Grand Total	8642.7614030761
Say For Unit 1 (Grand Total/1)	8642.7614030761

Item 8

R.C.C. Work (AR0404Ac): Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge. (RCC Beams, Column, Girder & Bressmer etc)

Sub-Item of Work

Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
Combine :: R.C.C. Work (AR0404A)					

PM096 : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0
PM083 : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0
LR001 : Male mulia	1.3333	Per day	462	615.9846	0
LR025 : Mason	0.1	Per day	562	56.2	0
LR010 : Mate	0.0573	Per day	512	29.3376	0
BRM340 : Cement	3.4733	1 Qntl.	543.88	1889.058404	340.03051272
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1415.1	509.436	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1382.29	746.4366	0
Combine :: R.C.C. Work (AR0410d)					
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	4.4196	1Mtr	51.87	229.244652	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.041529	1Cum.	58374.79	2424.24665391	0
LR008 : Sangi mulia	5.23875	Per day	512	2682.24	0
LR027 : Carpenter	5.23875	Per day	562	2944.1775	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	39.055	135.6497315	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	757.75	340.9875	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	822.85	296.226	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	822.85	444.339	0
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.045339	1Mtr	245.856	11.146865184	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.041529	1Cum.	245.856	10.210153824	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	0	0	0

BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	274.25	123.4125	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	444.5	160.02	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	444.5	240.03	0
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.045339	1Mtr	0	0	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.041529	1Cum.	0	0	0

Total Amount (a+b+c)	14294.799760418
Total GST (a)	340.03051272
OVERHEAD CHARGES @ 7.5% (+)	1097.6122704854
CONTRACTOR PROFIT @ 7.5% (+)	1179.9331907718
LABOUR CESS @ 1% (+)	169.12375734395
Grand Total	17081.499491739
Say For Unit 1 (Grand Total/1)	17081.499491739

Item 9

R.C.C. Work (AR0404Ag): Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Roof slab, landing, balcony, sun shade)

Sub-Item of Work

Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
Combine :: R.C.C. Work (AR0404A)					
PM096 : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0
PM083 : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0
LR001 : Male mulia	1.3333	Per day	462	615.9846	0
LR025 : Mason	0.1	Per day	562	56.2	0
LR010 : Mate	0.0573	Per day	512	29.3376	0
BRM340 : Cement	3.4733	1 Qntl.	543.88	1889.058404	340.03051272
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1415.1	509.436	0

BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1382.29	746.4366	0
Combine :: R.C.C. Work (AR0410a)					
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	6.2216	1Mtr	51.87	322.714392	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0502172	1Cum.	58374.79	2931.418504388	0
LR008 : Sangi mulia	3.05525	Per day	512	1564.288	0
LR027 : Carpenter	3.05525	Per day	562	1717.0505	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	39.055	135.6497315	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	757.75	340.9875	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	822.85	296.226	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	822.85	444.339	0
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.076659	1Mtr	245.856	18.847075104	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0502172	1Cum.	245.856	12.3461999232	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	274.25	123.4125	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	444.5	160.02	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	444.5	240.03	0
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.076659	1Mtr	0	0	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0502172	1Cum.	0	0	0

Total Amount (a+b+c)	12560.198606915
Total GST (a)	340.03051272
OVERHEAD CHARGES @ 7.5% (+)	967.51718397264
CONTRACTOR PROFIT @ 7.5% (+)	1040.0809727706
LABOUR CESS @ 1% (+)	149.07827276378

Grand Total	15056.905549142
Say For Unit 1 (Grand Total/1)	15056.905549142

Item 10

Plastering (AR1027): 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.

Sub-Item of Work

6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR001 : Male mulia	0.12	Per day	462	55.44	0
LR002 : Female mulia	0.05	Per day	462	23.1	0
LR025 : Mason	0.14	Per day	562	78.68	0
BRM340 : Cement	0.0372	1 Qntl.	543.88	20.232336	3.64182048
BRM028 : Screened and washed sharp sand for mortar	0.0075	1 Cum	76.88	0.5766	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0372	1 Qntl.	39.055	1.452846	0
BRM028 : Screened and washed sharp sand for mortar	0.0075	1 Cum	757.75	5.683125	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0372	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.0075	1 Cum	274.25	2.056875	0

Total Amount (a+b+c)	187.221782
Total GST (a)	3.64182048
OVERHEAD CHARGES @ 7.5% (+)	14.314770186
CONTRACTOR PROFIT @ 7.5% (+)	15.38837794995
LABOUR CESS @ 1% (+)	2.2056675061595
Grand Total	222.77241812211
Say For Unit 1 (Grand Total/1)	222.77241812211

Item 11

Plastering (AR1004): 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp. and as per direction of Engineer-in-charge.

Sub-Item of Work
12mm thick cement plaster (1:6) over Brick work in inside

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.05	Per day	462	23.1	0
LR001 : Male mulia	0.07	Per day	462	32.34	0
LR025 : Mason	0.14	Per day	562	78.68	0
BRM340 : Cement	0.0358	1 Qntl.	543.88	19.470904	3.50476272
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	76.88	1.1532	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0358	1 Qntl.	39.055	1.398169	0
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	757.75	11.36625	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0358	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	274.25	4.11375	0

Total Amount (a+b+c)	171.622273
Total GST (a)	3.50476272
OVERHEAD CHARGES @ 7.5% (+)	13.134527679
CONTRACTOR PROFIT @ 7.5% (+)	14.119617254925
LABOUR CESS @ 1% (+)	2.0238118065393
Grand Total	204.40499246046
Say For Unit 1 (Grand Total/1)	204.40499246046

Item 12

Plastering (AR1014): 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.

Sub-Item of Work
16mm thick cement Plaster in CM (1:6) over brick work in inside.

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.11	Per day	462	50.82	0
LR001 : Male mulia	0.13	Per day	462	60.06	0
LR025 : Mason	0.16	Per day	562	89.92	0

BRM340 : Cement	0.043	1 Qntl.	543.88	23.38684	4.2096312
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	76.88	1.38384	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.043	1 Qntl.	39.055	1.679365	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	757.75	13.6395	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.043	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	274.25	4.9365	0

Total Amount (a+b+c)	245.826045
Total GST (a)	4.2096312
OVERHEAD CHARGES @ 7.5% (+)	18.752675715
CONTRACTOR PROFIT @ 7.5% (+)	20.159126393625
LABOUR CESS @ 1% (+)	2.8894747830862
Grand Total	291.83695309171
Say For Unit 1 (Grand Total/1)	291.83695309171

Item 13

Other Building Items. (AR1901B): Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)

Sub-Item of Work

Vitrified Tile 600mmx600mm Plain Ivory

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM174 : White Cement.	0.076	1Qntl	2006	152.456	0
BRM340 : Cement	1.074	1 Qntl.	543.88	584.12712	105.1428816
BRM028 : Screened and washed sharp sand for mortar	0.21	1 Cum	76.88	16.1448	0
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	651.08	6510.8	0
LR001 : Male mulia	2.16	Per day	462	997.92	0
LR044 : Mason	2.16	Per day	612	1321.92	0

b) Carriage Rate Details						
Particular	Quantity	Unit	Rate	Amount	GST	
BRM174 : White Cement.	0.076	1Qntl	39.055	2.96818	0	
BRM340 : Cement	1.074	1 Qntl.	39.055	41.94507	0	
BRM028 : Screened and washed sharp sand for mortar	0.21	1 Cum	757.75	159.1275	0	
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	13.5284447	135.284447	0	

c) Royalty Rate Details						
Particular	Quantity	Unit	Rate	Amount	GST	
BRM174 : White Cement.	0.076	1Qntl	0	0	0	
BRM340 : Cement	1.074	1 Qntl.	0	0	0	
BRM028 : Screened and washed sharp sand for mortar	0.21	1 Cum	274.25	57.5925	0	
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	0	0	0	

Total Amount (a+b+c)	9980.285617					
Total GST (a)	105.1428816					
OVERHEAD CHARGES @ 7.5% (+)	756.407137395					
CONTRACTOR PROFIT @ 7.5% (+)	813.13767269963					
LABOUR CESS @ 1% (+)	116.54973308695					
Grand Total	11771.523041782					
Say For Unit 1 (Grand Total/10)	1177.1523041782					

Item 14

Flooring (AR0817aa): Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.

Sub-Item of Work

Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3)

a) Specific Rate Details						
Particular	Quantity	Unit	Rate	Amount	GST	
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	651.08	6510.8	0	

BRMMR0027 : Wax Polish	10	1 Sqm	8.5	85	0
LR044 : Mason	3.25	Per day	612	1989	0
LR001 : Male mulia	3.25	Per day	462	1501.5	0
LR008 : Sangi mulia	7.6	Per day	512	3891.2	0
BRM340 : Cement	1.375	1 Qntl.	543.88	747.835	134.6103
BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	76.88	11.532	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	13.5284447	135.284447	0
BRM340 : Cement	1.375	1 Qntl.	39.055	53.700625	0
BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	757.75	113.6625	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	0	0	0
BRM340 : Cement	1.375	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	274.25	41.1375	0

Total Amount (a+b+c)	15080.652072
Total GST (a)	134.6103
OVERHEAD CHARGES @ 7.5% (+)	1141.1446779
CONTRACTOR PROFIT @ 7.5% (+)	1226.7305287425
LABOUR CESS @ 1% (+)	175.83137578642
Grand Total	17758.968954429
Say For Unit 1 (Grand Total/10)	1775.8968954429

Item 15

Flooring (AR0816j): Fixing Chequered Tiles in floor , treads or steps and landing on a 25mm thick bed of cement mortar 1:1 (1cement: 1sand) jointed with neat cement slurry mixed with pigment to match the shades of the Chequered tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.

Sub-Item of Work

Fixing Chequered Tiles in floor , treads or steps and landing on a 25mm thick bed of cement mortar 1:1

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM134 : Chequered Tiles.	10	1 Sqm.	225.5	2255	0
BRMMR0027 : Wax Polish	10	1 Sqm	8.5	85	0
LR001 : Male mulia	2.16	Per day	462	997.92	0
LR044 : Mason	2.16	Per day	612	1321.92	0
LR008 : Sangi mulia	5.5	Per day	512	2816	0
BRM340 : Cement	2.737	1 Qntl.	543.88	1488.59956	267.9479208
BRM028 : Screened and washed sharp sand for mortar	0.13	1 Cum	76.88	9.9944	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.737	1 Qntl.	39.055	106.893535	0
BRM028 : Screened and washed sharp sand for mortar	0.13	1 Cum	757.75	98.5075	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.737	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.13	1 Cum	274.25	35.6525	0

Total Amount (a+b+c)

9215.487495

Total GST (a)

267.9479208

OVERHEAD CHARGES @ 7.5% (+)

711.257656185

CONTRACTOR PROFIT @ 7.5% (+)

764.60198039887

LABOUR CESS @ 1% (+)

109.59295052384

Grand Total

11068.888002908

Say For Unit 1 (Grand Total/10)

1106.8888002908

Item 16

Painting (AR0901d): Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.

Sub-Item of Work

Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
------------	----------	------	------	--------	-----

BRM253 : Wall cement primer (I.S.I.) Water bound	0.7812	1 Ltr	155.6	121.55472	0
LR048 : Painter/ Polisher	0.5	Per day	612	306	0
LR001 : Male mulia	0.5	Per day	462	231	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM253 : Wall cement primer (I.S.I.) Water bound	0.7812	1 Ltr	0.39055	0.30509766	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM253 : Wall cement primer (I.S.I.) Water bound	0.7812	1 Ltr	0	0	0

Total Amount (a+b+c)	658.85981766
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	49.4144863245
CONTRACTOR PROFIT @ 7.5% (+)	53.120572798837
LABOUR CESS @ 1% (+)	7.6139487678334
Grand Total	769.00882555117
Say For Unit 1 (Grand Total/9.3)	82.689121027008

Item 17

Painting (AR0920): Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)

Sub-Item of Work

Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM140 : Plastic Emulsion paint	1.25	1 Litre	249.34	311.675	0
LR048 : Painter/ Polisher	0.54	Per day	612	330.48	0
LR001 : Male mulia	0.64	Per day	462	295.68	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM140 : Plastic Emulsion paint	1.25	1 Litre	0.39055	0.4881875	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM140 : Plastic Emulsion paint	1.25	1 Litre	0	0	0

Total Amount (a+b+c)	938.3231875
-----------------------------	-------------

Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	70.3742390625
CONTRACTOR PROFIT @ 7.5% (+)	75.652306992188
LABOUR CESS @ 1% (+)	10.843497335547
Grand Total	1095.1932308902
Say For Unit 1 (Grand Total/10)	109.51932308902

Item 18

Painting (AR0918cb): Finishing wall two coats with weather coat with one coat waterbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)

Sub-Item of Work

Finishing wall two coats with weather coat with one coat waterbound Primer

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
Combine :: Painting (AR0918f)					
BRM255 : Weather Coat (I.S.I.)	0.125	1 Ltr	193	24.125	0
LR001 : Male mulia	0.064	Per day	462	29.568	0
LR048 : Painter/ Polisher	0.054	Per day	612	33.048	0
Combine :: Painting (AR0901di)					
BRM253 : Wall cement primer (I.S.I.) Water bound	0.090322580645161	1 Ltr	155.6	14.054193548387	0
LR048 : Painter/ Polisher	0.053763440860215	Per day	612	32.903225806452	0
LR001 : Male mulia	0.053763440860215	Per day	462	24.838709677419	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	0.125	1 Ltr	0.39055	0.04881875	0
BRM253 : Wall cement primer (I.S.I.) Water bound	0.090322580645161	1 Ltr	0.39055	0.035275483870968	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	0.125	1 Ltr	0	0	0
BRM253 : Wall cement primer (I.S.I.) Water bound	0.090322580645161	1 Ltr	0	0	0

Total Amount (a+b+c)	158.62122326613
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	11.89659174496
CONTRACTOR PROFIT @ 7.5% (+)	12.788836125832
LABOUR CESS @ 1% (+)	1.8330665113692

Grand Total	185.13971764829
Say For Unit 1 (Grand Total/1)	185.13971764829

Item 19

Other Building Items. (AR1911): Supplying, fitting and fixing of Stainless steel of 304 grade in hand railing using 50mm dia of 2mm thick circular pipe with Balustrade of size 32mm x 32mm x 2mm @ 0.90mtr. C/C and stainless square pipe bracing of size 32mm x 32mm x 2mm in 3 rows in staircase as per approved design and specification, buffing, polishing etc with cost, conveyance, taxes of all materials, labour, T&P etc. required for the complete in all respect. and as per direction of Engineer in Charge

Sub-Item of Work

Stainless steel of 304 grade in hand railing using 50mm dia of 2mm

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR011 : Helper to carpenter or Blacksmith/ Painter/ Blaster/Plumber/ Electrician/ Fitter/Welder	0.89	Per day	512	455.68	0
LR047 : Fitter	0.89	Per day	612	544.68	0
BRMMR0024 : Buffing, Polishing etc.	1	L.S.	178.42	178.42	0
BRMMR0023 : Fabrication	34.16	kg	10	341.6	0
BRMMR0022 : Stainless steel square pipe bracing of size 32mmx32mmx2mm in 3 rows	16.63	kg	256.62	4267.5906	0
BRMMR0021 : Balustrade of size 30mmx32mmx2mm	6.12	kg	256.62	1570.5144	0
BRMMR0020 : Railing 50mm outer dia of 2mm thick	11.41	kg	240.24	2741.1384	0

Total Amount (a+b+c)	10099.6234
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	757.471755
CONTRACTOR PROFIT @ 7.5% (+)	814.282136625
LABOUR CESS @ 1% (+)	116.71377291625
Grand Total	11788.091064541
Say For Unit 1 (Grand Total/3.26)	3615.9788541538

Item 20

R.C.C. Work (AR0409): Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.

Sub-Item of Work

Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
------------	----------	------	------	--------	-----

LR001 : Male mulia	8	Per day	462	3696	0
LR046 : Blacksmith	3	Per day	612	1836	0
LR010 : Mate	0.44	Per day	512	225.28	0
BRM162 : Binding Wire.	8	1 Kg.	90.1	720.8	0
BRM341 : Steel	10.5	1 Qntl.	6192.55	65021.775	11703.9195

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	10.5	1 Qntl.	39.055	410.0775	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	10.5	1 Qntl.	0	0	0

Total Amount (a+b+c)	71909.9325				
Total GST (a)	11703.9195				
OVERHEAD CHARGES @ 7.5% (+)	6271.0389				
CONTRACTOR PROFIT @ 7.5% (+)	6741.3668175				
LABOUR CESS @ 1% (+)	966.262577175				
Grand Total	97592.520294675				
Say For Unit 1 (Grand Total/10)	9759.2520294675				

Smruti Sucharita Krishnamurty
JE
Sukinda Block

Asish Kumar Biswal
AEE
Sukinda Block

Prangyan Primita Prusty
BDO
Sukinda Block