

Analysis

OD/361/3449/119387/387061/00066679 : repair and maint. of barahi PM School at bancho
Block : Hatadihi, Gram Panchayat : Bancho
Created By: RANJAN KUMAR PARIDA

Item 1
Concrete (AR0318): 4cm thick grading concrete (1:2:4) on roof slab with 12mm size hard granite chips (Crusher Broken) including hoisting and laying in position compacting and curing for the proper period with cost conveyance, royalty, taxes of all materials, labor and T&P required for the work etc. complete as per specification and direction of Engineer-in charge. (Old Work)
Sub-Item of Work 4cm thick grading concrete (1:2:4) on roof slab with 12mm size hard granite chips (Crusher Broken)

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR001 : Male mulia	1.008	Per day	462	465.696	0
LR044 : Mason	0.165	Per day	612	100.98	0
BRM340 : Cement	0.1287	1 Qntl.	567.52	73.039824	13.14716832
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	65	1.17	0
BRM064 : Granite stone broken chips of 4.7 mm size passing through 6.7 mm sieve (crusher broken.) and retained on 2.36 mm sieve.	0.018	1 Cum.	850.2	15.3036	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.018	1 Cum.	1370	24.66	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.1287	1 Qntl.	24.787	3.1900869	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	666.61	11.99898	0
BRM064 : Granite stone broken chips of 4.7 mm size passing through 6.7 mm sieve (crusher broken.) and retained on 2.36 mm sieve.	0.018	1 Cum.	731.71	13.17078	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.018	1 Cum.	731.71	13.17078	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.1287	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	190.25	3.4245	0

BRM064 : Granite stone broken chips of 4.7 mm size passing through 6.7 mm sieve (crusher broken.) and retained on 2.36 mm sieve.	0.018	1 Cum.	244.5	4.401	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.018	1 Cum.	244.5	4.401	0

Total Amount (a+b+c)	734.6065509
Total GST (a)	13.14716832
OVERHEAD CHARGES @ 7.5% (+)	56.0815289415
CONTRACTOR PROFIT @ 7.5% (+)	60.287643612112
LABOUR CESS @ 1% (+)	8.6412289177361
Grand Total	872.76412069135
Say For Unit 1 (Grand Total/1)	872.76412069135

Item 2

Dismantling (AR1620): Dismantling and removing 2.5 cm thick grading concrete from roof slab cleaning the surface lowering and removing the debris within 50m lead and as per direction of Engineer-in-Charge.

Sub-Item of Work
Second floor

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.65375	Per day	462	764.0325	0
LR001 : Male mulia	0.826875	Per day	462	382.01625	0

Total Amount (a+b+c)	1146.04875
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	85.95365625
CONTRACTOR PROFIT @ 7.5% (+)	92.40018046875
LABOUR CESS @ 1% (+)	13.244025867187
Grand Total	1337.6466125859
Say For Unit 1 (Grand Total/9.3)	143.83296909526

Item 3

miscellaneous (ARM122): Scraping old paint with scrapers, sand papering and washing with soap water or soda including scaffolding charges upto 5M height (Painting) and as directed by Engineer-in-Charge.

Sub-Item of Work
Scraping old paint with scrapers, sand papering and washing with soap water or soda including scaffolding charges upto 5M height (Painting) and as directed by Engineer-in-Charge.

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
------------	----------	------	------	--------	-----

BRMM122 : Scraping old paint with scrapers, sand papering and washing with soap water or soda including scaffolding charges upto 5M height (Painting)	1	Sqm	5.12	5.12	0
--	---	-----	------	------	---

Total Amount (a+b+c)	5.12
Total GST (a)	0
Grand Total	1337.6466125859
Say For Unit 1 (Grand Total/1)	1337.6466125859

Item 4

Painting (AR0905): Painting two coats of enamel paint on old wood work in inner surface paint including all costs of labour, Paint and brushes required for the work etc. complete and as per direction of Engineer-in-charge.(Inside)

Sub-Item of Work

Painting two coats of enamel on old wood work in inner surface paint

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR048 : Painter/ Polisher	1.25	Per day	612	765	0
LR001 : Male mulia	1.1	Per day	462	508.2	0
BRM141 : Enamel paint	1.1625	1 Litre	205.34	238.70775	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM141 : Enamel paint	1.1625	1 Litre	0.30732	0.3572595	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM141 : Enamel paint	1.1625	1 Litre	0	0	0

Total Amount (a+b+c)	1512.2650095
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	113.4198757125
CONTRACTOR PROFIT @ 7.5% (+)	121.92636639094
LABOUR CESS @ 1% (+)	17.476112516034
Grand Total	1765.0873641195
Say For Unit 1 (Grand Total/9.3)	189.7943402279

Item 5

Painting (AR0921bk): Finishing wall One Coat with distemper of approved shades with one coat water bound Primer on old work to give an even shade including all costs of labor, Paint, Primer, Brushes and putty required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)(For repair and maintenance).

Sub-Item of Work
Finishing wall One Coat with distemper of approved shades with one coat water bound Primer on old work (Inside)(For repair and maintenance).

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
Combine :: Painting (AR0921k)					
BRM142 : Distemper	0.166	1 Kg.	70.1	11.6366	0
LR001 : Male mulia	0.0408	Per day	462	18.8496	0
LR048 : Painter/ Polisher	0.03366	Per day	612	20.59992	0
Combine :: Painting (AR0901dk)					
BRM253 : Wall cement primer (I.S.I.) Water bound	0.084	1 Ltr	159.03	13.35852	0
LR048 : Painter/ Polisher	0.054838709677419	Per day	612	33.561290322581	0
LR001 : Male mulia	0.054838709677419	Per day	462	25.335483870968	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM142 : Distemper	0.166	1 Kg.	0.30732	0.05101512	0
BRM253 : Wall cement primer (I.S.I.) Water bound	0.084	1 Ltr	0.30732	0.02581488	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM142 : Distemper	0.166	1 Kg.	0	0	0
BRM253 : Wall cement primer (I.S.I.) Water bound	0.084	1 Ltr	0	0	0

Total Amount (a+b+c)	123.41824419355
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	9.2563683145161
CONTRACTOR PROFIT @ 7.5% (+)	9.9505959381048
LABOUR CESS @ 1% (+)	1.4262520844617
Grand Total	144.05146053063
Say For Unit 1 (Grand Total/1)	144.05146053063

Item 6

Painting (AR0918hk): Finishing wall with two coats weather coat paint of approved shade including one coat of water bound primer in the outer surface of old work to give an even shade including all costs of labour, Paint, Brushes, and putty required for the work, etc. complete and as per direction of Engineer-in-charge(Outside)(For repair and maintenance).

Sub-Item of Work
Finishing wall with two coats weather coat paint of approved shade including one coat of water bound primer in the outer surface of old work(Outside)(For repair and maintenance).

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
Combine :: Painting (AR0918fk)					
BRM255 : Weather Coat (I.S.I.)	0.125	1 Ltr	194.79	24.34875	0
LR001 : Male mulia	0.06528	Per day	462	30.15936	0
LR048 : Painter/ Polisher	0.05508	Per day	612	33.70896	0
Combine :: Painting (AR0901dik)					
BRM253 : Wall cement primer (I.S.I.) Water bound	0.090322580645161	1 Ltr	159.03	14.364	0
LR048 : Painter/ Polisher	0.054838709677419	Per day	612	33.561290322581	0
LR001 : Male mulia	0.054838709677419	Per day	462	25.335483870968	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	0.125	1 Ltr	0.30732	0.038415	0
BRM253 : Wall cement primer (I.S.I.) Water bound	0.090322580645161	1 Ltr	0.30732	0.027757935483871	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	0.125	1 Ltr	0	0	0
BRM253 : Wall cement primer (I.S.I.) Water bound	0.090322580645161	1 Ltr	0	0	0

Total Amount (a+b+c)	161.54401712903				
Total GST (a)	0				
OVERHEAD CHARGES @ 7.5% (+)	12.115801284677				
CONTRACTOR PROFIT @ 7.5% (+)	13.024486381028				
LABOUR CESS @ 1% (+)	1.8668430479474				
Grand Total	188.55114784269				
Say For Unit 1 (Grand Total/1)	188.55114784269				

Item 7

Concrete (AR0307): Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.

Sub-Item of Work

Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	3.2	Per day	462	1478.4	0

LR025 : Mason	0.68	Per day	562	382.16	0
BRM340 : Cement	3.23	1 Qntl.	567.52	1833.0896	329.956128
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	65	29.25	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	1370	1233	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	24.787	80.06201	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	666.61	299.9745	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	731.71	658.539	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	190.25	85.6125	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	244.5	220.05	0

Total Amount (a+b+c)	6946.93761
Total GST (a)	329.956128
OVERHEAD CHARGES @ 7.5% (+)	545.76703035
CONTRACTOR PROFIT @ 7.5% (+)	586.69955762625
LABOUR CESS @ 1% (+)	84.093603259762
Grand Total	8493.453929236
Say For Unit 1 (Grand Total/1)	8493.453929236

Item 8

Other Building Items. (AR1901B): Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)

Sub-Item of Work

Vitrified Tile 600mmx600mm Plain Ivory

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM174 : White Cement.	0.076	1Qntl	2017.18	153.30568	0
BRM340 : Cement	1.074	1 Qntl.	567.52	609.51648	109.7129664
BRM028 : Screened and washed sharp sand for mortar	0.21	1 Cum	65	13.65	0
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	651.08	6510.8	0
LR001 : Male mulia	2.16	Per day	462	997.92	0
LR044 : Mason	2.16	Per day	612	1321.92	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM174 : White Cement.	0.076	1Qntl	24.787	1.883812	0
BRM340 : Cement	1.074	1 Qntl.	24.787	26.621238	0
BRM028 : Screened and washed sharp sand for mortar	0.21	1 Cum	666.61	139.9881	0
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	11.2375001	112.375001	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM174 : White Cement.	0.076	1Qntl	0	0	0
BRM340 : Cement	1.074	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.21	1 Cum	190.25	39.9525	0
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	0	0	0

Total Amount (a+b+c)	9927.932811
Total GST (a)	109.7129664
OVERHEAD CHARGES @ 7.5% (+)	752.823433305
CONTRACTOR PROFIT @ 7.5% (+)	809.28519080288
LABOUR CESS @ 1% (+)	115.99754401508
Grand Total	11715.751945523
Say For Unit 1 (Grand Total/10)	1171.5751945523

Item 9

Dismantling (AR1612): Dismantling and removing 2.5 cm. thick artificial stone flooring including stacking the useful materials for reuse and removing the debris within 50m lead and as per direction of Engineer-in-Charge.

Sub-Item of Work

Dismantling and removing 2.5 cm. thick artificial stone flooring

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.25	Per day	462	577.5	0
LR001 : Male mulia	0.75	Per day	462	346.5	0

Total Amount (a+b+c)					924
Total GST (a)					0
OVERHEAD CHARGES @ 7.5% (+)					69.3
CONTRACTOR PROFIT @ 7.5% (+)					74.4975
LABOUR CESS @ 1% (+)					10.677975
Grand Total					1078.475475
Say For Unit 1 (Grand Total/9.3)					115.96510483871

PRAFULLA CHANDRA BEHERA
JE
Hatadihi Block

MADAN MOHAN BEHERA
AEE
Hatadihi Block

RANJAN KUMAR PARIDA
BDO
Hatadihi Block