

## Analysis

OD/346/3309/116327/393981/00072853 : Const of CC road from Sirapur RD road to Bhaskar  
Rout house Vill-Sirapur  
Block : Soro, Gram Panchayat : Sajanpur  
Created By:Satyanath Naik

<b>Item 1</b>
<b>Earth Work (AR0102aa):</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge
Sub-Item of Work <b>Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift</b>

<b>a) Specific Rate Details</b>					
Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	25.8	Per day	462	11919.6	0
LR001 : Male mulia	25.8	Per day	462	11919.6	0
<b>Total Amount (a+b+c)</b>				23839.2	
<b>Total GST (a)</b>				0	
<b>OVERHEAD CHARGES @ 7.5% (+)</b>				1787.94	
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>				1922.0355	
<b>LABOUR CESS @ 1% (+)</b>				275.491755	
<b>Grand Total</b>				27824.667255	
<b>Say For Unit 1 (Grand Total/100)</b>				278.24667255	

<b>Item 2</b>
<b>Earth Work (AR0115):</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work <b>Filling foundation and plinth with sand well watered and rammed</b>

<b>a) Specific Rate Details</b>					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	71.94	7194	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0
<b>b) Carriage Rate Details</b>					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	907.91	90791	0

<b>c) Royalty Rate Details</b>					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	442.25	44225	0

<b>Total Amount (a+b+c)</b>	147920.32				
<b>Total GST (a)</b>	0				
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	11094.024				
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	11926.0758				
<b>LABOUR CESS @ 1% (+)</b>	1709.404198				
<b>Grand Total</b>	172649.823998				
<b>Say For Unit 1 (Grand Total/100)</b>	1726.49823998				

<b>Item 3</b>
<b>Concrete (AR0303):</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work <b>Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal</b>

<b>a) Specific Rate Details</b>					
Particular	Quantity	Unit	Rate	Amount	GST
LR025 : Mason	0.18	Per day	562	101.16	0
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	2.5	Per day	462	1155	0
BRM340 : Cement	2.29	1 Qntl.	537.2	1230.188	221.43384
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	76.88	36.9024	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	995.25	955.44	0

<b>b) Carriage Rate Details</b>					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	24.787	56.76223	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	907.91	435.7968	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	471.31	452.4576	0

<b>c) Royalty Rate Details</b>					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	442.25	212.28	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	552.5	530.4	0

<b>Total Amount (a+b+c)</b>	5813.18703
<b>Total GST (a)</b>	221.43384
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	452.59656525
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	486.54130764375
<b>LABOUR CESS @ 1% (+)</b>	69.737587428937
<b>Grand Total</b>	7043.4963303227
<b>Say For Unit 1 (Grand Total/1)</b>	7043.4963303227

#### Item 4

**R.C.C. Work (AR0410d):** Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. beams, column, grider and bressmer, etc. Data for 4.2sqm

Sub-Item of Work

**Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting**

#### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM084</b> : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	2.32	1Mtr	51.87	120.3384	0
<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0218	1Cum.	58374.79	1272.570422	0
<b>LR008</b> : Sangi mulia	2.75	Per day	512	1408	0
<b>LR027</b> : Carpenter	2.75	Per day	562	1545.5	0

#### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM084</b> : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.0238	1Mtr	198.296	4.7194448	0
<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0218	1Cum.	198.296	4.3228528	0

#### c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM084</b> : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.0238	1Mtr	0	0	0
<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0218	1Cum.	0	0	0

<b>Total Amount (a+b+c)</b>	4355.4511196
<b>Total GST (a)</b>	0
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	326.65883397
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	351.15824651775
<b>LABOUR CESS @ 1% (+)</b>	50.332682000878
<b>Grand Total</b>	5083.6008820886

Say For Unit 1 (Grand Total/4.2)	1210.3811624021
----------------------------------	-----------------

**Item 5**

**Concrete (AR0307):** Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaicon and direction of Engineer-in charge.

Sub-Item of Work  
**Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum**

**a) Specific Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	3.2	Per day	462	1478.4	0
LR025 : Mason	0.68	Per day	562	382.16	0
BRM340 : Cement	3.23	1 Qntl.	537.2	1735.156	312.32808
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	1396.62	1256.958	0

**b) Carriage Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	24.787	80.06201	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	907.91	408.5595	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	471.31	424.179	0

**c) Royalty Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	442.25	199.0125	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	552.5	497.25	0

<b>Total Amount (a+b+c)</b>	7143.13301
-----------------------------	------------

Total GST (a)	312.32808
OVERHEAD CHARGES @ 7.5% (+)	559.15958175
CONTRACTOR PROFIT @ 7.5% (+)	601.09655038125
LABOUR CESS @ 1% (+)	86.157172221312
Grand Total	8701.8743943526
Say For Unit 1 (Grand Total/1)	8701.8743943526

**Monalisa Pati**  
**JE**  
**Soro Block**

**Nirmala Kanta Parida**  
**AEE**  
**Soro Block**

**Satyanath Naik**  
**BDO**  
**Soro Block**