

Analysis

**OD/356/3394/118253/401759/00071455 : Completion and restoration of PEO quarter and
BNRGSK Seva Kendra Chhatia
Block : Badchana, Gram Panchayat : Chhatia
Created By: Rabindra Kumar Pradhan**

Item 1
Earth Work (AR0102aa): Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge
Sub-Item of Work Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	25.8	Per day	462	11919.6	0
LR001 : Male mulia	25.8	Per day	462	11919.6	0

Total Amount (a+b+c)	23839.2
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	1787.94
CONTRACTOR PROFIT @ 7.5% (+)	1922.0355
LABOUR CESS @ 1% (+)	275.491755
Grand Total	27824.667255
Say For Unit 1 (Grand Total/100)	278.24667255

Item 2
Earth Work (AR0115): Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work Filling foundation and plinth with sand well watered and rammed

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	71.94	7194	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	536.41	53641	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	274.25	27425	0

Total Amount (a+b+c)	93970.32				
Total GST (a)	0				
OVERHEAD CHARGES @ 7.5% (+)	7047.774				
CONTRACTOR PROFIT @ 7.5% (+)	7576.35705				
LABOUR CESS @ 1% (+)	1085.9445105				
Grand Total	109680.3955605				
Say For Unit 1 (Grand Total/100)	1096.803955605				

Item 3

Concrete (AR0307): Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge.

Sub-Item of Work

Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	3.2	Per day	462	1478.4	0
LR025 : Mason	0.68	Per day	562	382.16	0
BRM340 : Cement	3.23	1 Qntl.	543.88	1756.7324	316.211832
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	1386.4	1247.76	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	24.787	80.06201	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	536.41	241.3845	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	666.61	599.949	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	274.25	123.4125	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	444.5	400.05	0

Total Amount (a+b+c)	6991.30641
Total GST (a)	316.211832
OVERHEAD CHARGES @ 7.5% (+)	548.06386815
CONTRACTOR PROFIT @ 7.5% (+)	589.16865826125
LABOUR CESS @ 1% (+)	84.447507684112
Grand Total	8529.1982760954
Say For Unit 1 (Grand Total/1)	8529.1982760954

Item 4

R.C.C. Work (AR0410c): Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc

Sub-Item of Work

R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	58374.79	1558.606893	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	1.26	1Mtr.	30.81	38.8206	0
LR008 : Sangi mulia	0.5	Per day	512	256	0
LR027 : Carpenter	0.5	Per day	562	281	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	198.296	5.2945032	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	198.296	1.21753744	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
------------	----------	------	------	--------	-----

BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	0	0	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	0	0	0

Total Amount (a+b+c)	2140.93953364
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	160.570465023
CONTRACTOR PROFIT @ 7.5% (+)	172.61324989972
LABOUR CESS @ 1% (+)	24.741232485627
Grand Total	2498.8644810484
Say For Unit 1 (Grand Total/10)	249.88644810484

Item 5

Flooring (AR0817b): Fixing ceramic tiles (20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) in wall cladding on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.

Sub-Item of Work

Fixing ceramic tiles (20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM129 : Tiles up to 20cmx30cm / 20cm x 20cm special plain /printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753	10	1 Sqm.	405.2	4052	0
LR001 : Male mulia	3.25	Per day	462	1501.5	0
LR044 : Mason	3.25	Per day	612	1989	0
BRM340 : Cement	1.375	1 Qntl.	543.88	747.835	134.6103
BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	76.88	11.532	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM129 : Tiles up to 20cmx30cm / 20cm x 20cm special plain /printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753	10	1 Sqm.	16.1466671	161.466671	0
BRM340 : Cement	1.375	1 Qntl.	24.787	34.082125	0
BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	536.41	80.4615	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM129 : Tiles up to 20cmx30cm / 20cm x 20cm special plain /printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753	10	1 Sqm.	0	0	0
BRM340 : Cement	1.375	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	274.25	41.1375	0

Total Amount (a+b+c)	8619.014796
Total GST (a)	134.6103
OVERHEAD CHARGES @ 7.5% (+)	656.5218822
CONTRACTOR PROFIT @ 7.5% (+)	705.761023365
LABOUR CESS @ 1% (+)	101.15908001565
Grand Total	10217.067081581
Say For Unit 1 (Grand Total/10)	1021.7067081581

Item 6

Other Building Items. (AR1901B): Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)

Sub-Item of Work
Vitrified Tile 600mmx600mm Plain Ivory

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM174 : White Cement.	0.076	1Qntl	2006	152.456	0
BRM340 : Cement	1.074	1 Qntl.	543.88	584.12712	105.1428816
BRM028 : Screened and washed sharp sand for mortar	0.21	1 Cum	76.88	16.1448	0
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	651.08	6510.8	0
LR001 : Male mulia	2.16	Per day	462	997.92	0
LR044 : Mason	2.16	Per day	612	1321.92	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM174 : White Cement.	0.076	1Qntl	24.787	1.883812	0
BRM340 : Cement	1.074	1 Qntl.	24.787	26.621238	0

BRM028 : Screened and washed sharp sand for mortar	0.21	1 Cum	536.41	112.6461	0
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	16.1466671	161.466671	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM174 : White Cement.	0.076	1Qntl	0	0	0
BRM340 : Cement	1.074	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.21	1 Cum	274.25	57.5925	0
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	0	0	0

Total Amount (a+b+c)	9943.578241
Total GST (a)	105.1428816
OVERHEAD CHARGES @ 7.5% (+)	753.654084195
CONTRACTOR PROFIT @ 7.5% (+)	810.17814050963
LABOUR CESS @ 1% (+)	116.12553347305
Grand Total	11728.678880778
Say For Unit 1 (Grand Total/10)	1172.8678880778

Item 7
Flooring (AR0816): Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor , treads or steps and landing on a 25mm thick bed of cement mortar 1:1 (1cement: 1sand) jointed with neat cement slurry mixed with pigment to match the shades of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.
Sub-Item of Work Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRMMR0027 : Wax Polish	10	1 Sqm	8.5	85	0
BRM130 : Tiles up to 30cm x 30cm / 40cm x 40cm special plain / printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755	10	1 Sqm.	450.08	4500.8	0
LR001 : Male mulia	2.16	Per day	462	997.92	0
LR044 : Mason	2.16	Per day	612	1321.92	0

LR008 : Sangi mulia	5.5	Per day	512	2816	0
BRM340 : Cement	2.737	1 Qntl.	543.88	1488.59956	267.9479208
BRM028 : Screened and washed sharp sand for mortar	0.13	1 Cum	76.88	9.9944	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM130 : Tiles up to 30cm x 30cm / 40cm x 40cm special plain / printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755	10	1 Sqm.	16.1466671	161.466671	0
BRM340 : Cement	2.737	1 Qntl.	24.787	67.842019	0
BRM028 : Screened and washed sharp sand for mortar	0.13	1 Cum	536.41	69.7333	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM130 : Tiles up to 30cm x 30cm / 40cm x 40cm special plain / printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755	10	1 Sqm.	0	0	0
BRM340 : Cement	2.737	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.13	1 Cum	274.25	35.6525	0

Total Amount (a+b+c)	11554.92845
Total GST (a)	267.9479208
OVERHEAD CHARGES @ 7.5% (+)	886.71572781
CONTRACTOR PROFIT @ 7.5% (+)	953.21940739575
LABOUR CESS @ 1% (+)	136.62811506006
Grand Total	13799.439621066
Say For Unit 1 (Grand Total/10)	1379.9439621066

Item 8

miscellaneous (ARM286): Supplying and fixing of 60mm thick cement concrete interlocking paver block of M-30 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.

Sub-Item of Work

Supplying and fixing of 60mm thick cement concrete interlocking paver block of M-30 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
------------	----------	------	------	--------	-----

BRM029 : Sand for filling and road blinding	0.05	1 Cum	71.94	3.597	0
BRMM286 : Supplying and fixing of 60mm thick cement concrete interlocking paver block of M-30 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items)	1	1 Sqm	485.28	485.28	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	0.05	1 Cum	536.41	26.8205	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	0.05	1 Cum	274.25	13.7125	0

Total Amount (a+b+c)	529.41				
Total GST (a)	0				
Grand Total	13799.439621066				
Say For Unit 1 (Grand Total/1)	13799.439621066				

Anita Behura
JE
Badchana Block

Parthasarathi Panda
AEE
Badchana Block

Rabindra Kumar Pradhan
BDO
Badchana Block