

Analysis

OD/363/3468/119738/428283/00069836 : CONSTRUCTION OF APPROACH ROAD TO BLOCK FACILITY CENTER

Block : Borigumma, Gram Panchayat : Borigumma

Created By: SUKANTA KUMAR PATNAIK

Item 1
Earth Work (AR0102aa): Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge
Sub-Item of Work Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	25.8	Per day	462	11919.6	0
LR001 : Male mulia	25.8	Per day	462	11919.6	0

Total Amount (a+b+c)	23839.2
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	1787.94
CONTRACTOR PROFIT @ 7.5% (+)	1922.0355
LABOUR CESS @ 1% (+)	275.491755
Grand Total	27824.667255
Say For Unit 1 (Grand Total/100)	278.24667255

Item 2
Earth Work (AR0115): Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work Filling foundation and plinth with sand well watered and rammed

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	71.94	7194	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	406.21	40621	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	272.55	27255	0

Total Amount (a+b+c)	80780.32				
Total GST (a)	0				
OVERHEAD CHARGES @ 7.5% (+)	6058.524				
CONTRACTOR PROFIT @ 7.5% (+)	6512.9133				
LABOUR CESS @ 1% (+)	933.517573				
Grand Total	94285.274873				
Say For Unit 1 (Grand Total/100)	942.85274873				

Item 3
Concrete (AR0303): Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR025 : Mason	0.18	Per day	562	101.16	0
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	2.5	Per day	462	1155	0
BRM340 : Cement	2.29	1 Qntl.	547.5	1253.775	225.6795
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	75.86	36.4128	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	995.25	955.44	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	36.677	83.99033	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	406.21	194.9808	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	406.21	389.9616	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	272.55	130.824	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	248.4	238.464	0

Total Amount (a+b+c)	5186.80853
Total GST (a)	225.6795
OVERHEAD CHARGES @ 7.5% (+)	405.93660225
CONTRACTOR PROFIT @ 7.5% (+)	436.38184741875
LABOUR CESS @ 1% (+)	62.548064796687
Grand Total	6317.3545444654
Say For Unit 1 (Grand Total/1)	6317.3545444654

Item 4

R.C.C. Work (AR0410c): Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc

Sub-Item of Work

R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	58374.79	1558.606893	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	1.26	1Mtr.	30.81	38.8206	0
LR008 : Sangi mulia	0.5	Per day	512	256	0
LR027 : Carpenter	0.5	Per day	562	281	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	293.416	7.8342072	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	293.416	1.80157424	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	0	0	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	0	0	0

Total Amount (a+b+c)	2144.06327444
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	160.804745583
CONTRACTOR PROFIT @ 7.5% (+)	172.86510150173
LABOUR CESS @ 1% (+)	24.777331215247
Grand Total	2502.51045274

Say For Unit 1 (Grand Total/10)	250.251045274
---------------------------------	---------------

Item 5

Concrete (AR0307): Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.

Sub-Item of Work
Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	3.2	Per day	462	1478.4	0
LR025 : Mason	0.68	Per day	562	382.16	0
BRM340 : Cement	3.23	1 Qntl.	547.5	1768.425	318.3165
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	75.86	34.137	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	1396.62	1256.958	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	36.677	118.46671	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	406.21	182.7945	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	406.21	365.589	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	272.55	122.6475	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	248.4	223.56	0

Total Amount (a+b+c)	6579.93771
-----------------------------	------------

Total GST (a)	318.3165
OVERHEAD CHARGES @ 7.5% (+)	517.36906575
CONTRACTOR PROFIT @ 7.5% (+)	556.17174568125
LABOUR CESS @ 1% (+)	79.717950214312
Grand Total	8051.5129716456
Say For Unit 1 (Grand Total/1)	8051.5129716456

RATINDRA PANIGRAHI
JE
Borigumma Block

Prakash Kumar Pradhan
AEE
Borigumma Block

SUKANTA KUMAR PATNAIK
BDO
Borigumma Block