

Analysis

OD/371/3560/121330/381938/00073885 : Const. of CC Road from Birsa House at
Kumbharpada, Ghusuraguda, Tiklipada GP
Block : Jamankira, Gram Panchayat : Tiklipada
Created By:Rabindra Kumar Sethy

Item 1

Earth Work (AR0102aa): Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge

Sub-Item of Work

Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	25.8	Per day	462	11919.6	0
LR001 : Male mulia	25.8	Per day	462	11919.6	0

Total Amount (a+b+c)

23839.2

Total GST (a)

0

OVERHEAD CHARGES @ 7.5% (+)

1787.94

CONTRACTOR PROFIT @ 7.5% (+)

1922.0355

LABOUR CESS @ 1% (+)

275.491755

Grand Total

27824.667255

Say For Unit 1 (Grand Total/100)

278.24667255

Item 2

Earth Work (AR0115): Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

Filling foundation and plinth with sand well watered and rammed

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	70	7000	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	796.81	79681	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	85.25	8525	0

Total Amount (a+b+c)	100916.32				
Total GST (a)	0				
OVERHEAD CHARGES @ 7.5% (+)	7568.724				
CONTRACTOR PROFIT @ 7.5% (+)	8136.3783				
LABOUR CESS @ 1% (+)	1166.214223				
Grand Total	117787.636523				
Say For Unit 1 (Grand Total/100)	1177.87636523				

Item 3
Concrete (AR0303): Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR025 : Mason	0.18	Per day	562	101.16	0
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	2.5	Per day	462	1155	0
BRM340 : Cement	2.29	1 Qntl.	538	1232.02	221.7636
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	76.88	36.9024	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	950	912	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	30.732	70.37628	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	796.81	382.4688	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	601.51	577.4496	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	85.25	40.92	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	201.5	193.44	0

Total Amount (a+b+c)	5348.53708
Total GST (a)	221.7636
OVERHEAD CHARGES @ 7.5% (+)	417.772551
CONTRACTOR PROFIT @ 7.5% (+)	449.105492325
LABOUR CESS @ 1% (+)	64.37178723325
Grand Total	6501.5505105582
Say For Unit 1 (Grand Total/1)	6501.5505105582

Item 4

R.C.C. Work (AR0410c): Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc

Sub-Item of Work

R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	58374.79	1558.606893	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	1.26	1Mtr.	30.81	38.8206	0
LR008 : Sangi mulia	0.5	Per day	512	256	0
LR027 : Carpenter	0.5	Per day	562	281	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	198.296	5.2945032	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	198.296	1.21753744	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	0	0	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	0	0	0

Total Amount (a+b+c)	2140.93953364
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	160.570465023
CONTRACTOR PROFIT @ 7.5% (+)	172.61324989972
LABOUR CESS @ 1% (+)	24.741232485627
Grand Total	2498.8644810484

Say For Unit 1 (Grand Total/10)	249.88644810484
---------------------------------	-----------------

Item 5

Concrete (AR0307): Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.

Sub-Item of Work
Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	3.2	Per day	462	1478.4	0
LR025 : Mason	0.68	Per day	562	382.16	0
BRM340 : Cement	3.23	1 Qntl.	538	1737.74	312.7932
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	1396.62	1256.958	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	30.732	99.26436	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	796.81	358.5645	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	601.51	541.359	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	85.25	38.3625	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	201.5	181.35	0

Total Amount (a+b+c)	6755.55436
-----------------------------	------------

Total GST (a)	312.7932
OVERHEAD CHARGES @ 7.5% (+)	530.126067
CONTRACTOR PROFIT @ 7.5% (+)	569.885522025
LABOUR CESS @ 1% (+)	81.68359149025
Grand Total	8250.0427405152
Say For Unit 1 (Grand Total/1)	8250.0427405152

BIDYA TUDU
JE
Jamankira Block

Satyajit Sahoo
AEE
Jamankira Block

Rabindra Kumar Sethy
BDO
Jamankira Block