

Analysis

OD/346/3299/116066/392691/00064142 : Completion of Mardaraj Community Center, Parikul,
GP: Buanl
Block : Baleshwar, Gram Panchayat : Buanl
Created By:Uttam Kumar Jena

Item 1
Plastering (AR1004): 12mm thick cement plster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.
Sub-Item of Work 12mm thick cement plster (1:6) over Brick work in inside

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.05	Per day	462	23.1	0
LR001 : Male mulia	0.07	Per day	462	32.34	0
LR025 : Mason	0.14	Per day	562	78.68	0
BRM340 : Cement	0.0358	1 Qntl.	537.2	19.23176	3.4617168
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	76.88	1.1532	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0358	1 Qntl.	24.787	0.8873746	0
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	419.23	6.28845	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0358	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	427.25	6.40875	0

Total Amount (a+b+c)	168.0895346
Total GST (a)	3.4617168
OVERHEAD CHARGES @ 7.5% (+)	12.866343855
CONTRACTOR PROFIT @ 7.5% (+)	13.831319644125
LABOUR CESS @ 1% (+)	1.9824891489912
Grand Total	200.23140404812
Say For Unit 1 (Grand Total/1)	200.23140404812

Item 2

Plastering (AR1014): 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.

Sub-Item of Work

16mm thick cement Plaster in CM (1:6) over brick work in inside.

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.11	Per day	462	50.82	0
LR001 : Male mulia	0.13	Per day	462	60.06	0
LR025 : Mason	0.16	Per day	562	89.92	0
BRM340 : Cement	0.043	1 Qntl.	537.2	23.0996	4.157928
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	76.88	1.38384	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.043	1 Qntl.	24.787	1.065841	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	419.23	7.54614	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.043	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	427.25	7.6905	0

Total Amount (a+b+c)

241.585921

Total GST (a)

4.157928

OVERHEAD CHARGES @ 7.5% (+)

18.430788675

CONTRACTOR PROFIT @ 7.5% (+)

19.813097825625

LABOUR CESS @ 1% (+)

2.8398773550062

Grand Total

286.82761285563

Say For Unit 1 (Grand Total/1)

286.82761285563

Item 3

Plastering (AR1027): 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.

Sub-Item of Work

6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR001 : Male mulia	0.12	Per day	462	55.44	0
LR002 : Female mulia	0.05	Per day	462	23.1	0
LR025 : Mason	0.14	Per day	562	78.68	0
BRM340 : Cement	0.0372	1 Qntl.	537.2	19.98384	3.5970912
BRM028 : Screened and washed sharp sand for mortar	0.0075	1 Cum	76.88	0.5766	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0372	1 Qntl.	24.787	0.9220764	0
BRM028 : Screened and washed sharp sand for mortar	0.0075	1 Cum	419.23	3.144225	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0372	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.0075	1 Cum	427.25	3.204375	0

Total Amount (a+b+c)				185.0511164	
Total GST (a)				3.5970912	
OVERHEAD CHARGES @ 7.5% (+)				14.14861557	
CONTRACTOR PROFIT @ 7.5% (+)				15.20976173775	
LABOUR CESS @ 1% (+)				2.1800658490775	
Grand Total				220.18665075683	
Say For Unit 1 (Grand Total/1)				220.18665075683	

Item 4

Plastering (AR1017): 20mm thick cement Plaster in CM (1:4) over stone work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.

Sub-Item of Work

20mm thick cement Plaster in CM (1:4) over masonry work in inside.

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.11	Per day	462	50.82	0
LR001 : Male mulia	0.13	Per day	462	60.06	0
LR025 : Mason	0.16	Per day	562	89.92	0
BRM340 : Cement	0.0744	1 Qntl.	537.2	39.96768	7.1941824
BRM028 : Screened and washed sharp sand for mortar	0.021	1 Cum	76.88	1.61448	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0744	1 Qntl.	24.787	1.8441528	0
BRM028 : Screened and washed sharp sand for mortar	0.021	1 Cum	419.23	8.80383	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0744	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.021	1 Cum	427.25	8.97225	0

Total Amount (a+b+c)	262.0023928				
Total GST (a)	7.1941824				
OVERHEAD CHARGES @ 7.5% (+)	20.18974314				
CONTRACTOR PROFIT @ 7.5% (+)	21.7039738755				
LABOUR CESS @ 1% (+)	3.110902922155				
Grand Total	314.20119513766				
Say For Unit 1 (Grand Total/1)	314.20119513766				

Item 5

Flooring (AR0817aa): Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.

Sub-Item of Work

Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3)

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	651.08	6510.8	0
BRMMR0027 : Wax Polish	10	1 Sqm	8.5	85	0
LR044 : Mason	3.25	Per day	612	1989	0
LR001 : Male mulia	3.25	Per day	462	1501.5	0
LR008 : Sangi mulia	7.6	Per day	512	3891.2	0
BRM340 : Cement	1.375	1 Qntl.	537.2	738.65	132.957
BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	76.88	11.532	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	11.2375001	112.375001	0
BRM340 : Cement	1.375	1 Qntl.	24.787	34.082125	0
BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	419.23	62.8845	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	0	0	0
BRM340 : Cement	1.375	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	427.25	64.0875	0

Total Amount (a+b+c)	15001.111126
Total GST (a)	132.957
OVERHEAD CHARGES @ 7.5% (+)	1135.05510945
CONTRACTOR PROFIT @ 7.5% (+)	1220.1842426588
LABOUR CESS @ 1% (+)	174.89307478109
Grand Total	17664.20055289
Say For Unit 1 (Grand Total/10)	1766.420055289

Item 6
Masonry Brick Work (AR0603b): Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.
Sub-Item of Work Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.14	Per day	462	64.68	0
LR001 : Male mulia	2.82	Per day	462	1302.84	0
LR025 : Mason	1.05	Per day	562	590.1	0

LR044 : Mason	0.35	Per day	612	214.2	0
BRM340 : Cement	0.672	1 Qntl.	537.2	360.9984	64.979712
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	76.88	21.5264	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	350	1000 Nos	5.14255	1799.8925	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.672	1 Qntl.	24.787	16.656864	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	419.23	117.3844	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	350	1000 Nos	1.18805	415.8175	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.672	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	427.25	119.63	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	350	1000 Nos	0	0	0

Total Amount (a+b+c)	5023.726064
Total GST (a)	64.979712
OVERHEAD CHARGES @ 7.5% (+)	381.6529332
CONTRACTOR PROFIT @ 7.5% (+)	410.27690319
LABOUR CESS @ 1% (+)	58.8063561239
Grand Total	5939.4419685139
Say For Unit 1 (Grand Total/1)	5939.4419685139

Item 7

Other Building Items. (AR1907): Supplying, fitting, fixing up window (sliding type) made up aluminum Section 9778, as windows frame, section No. 4095, 4096 and 9777, 3994 as shutter frame with 5mm thick black glass as panel fitted with rubber beading including locking arrangement including all fitting including cost of materials all taxes labour, T&P etc. complete as per direction of Engineer-in-charge.

Sub-Item of Work
aluminum sliding window (sliding type)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRMMR0005 : Handel with lock	2	Each	40	80	0
LR001 : Male mulia	1.5	Per day	462	693	0

LR011 : Helper to carpenter or Blacksmith/ Painter/ Blaster/Plumber/ Electrician/ Fitter/Welder	1.5	Per day	512	768	0
LR028 : Fitter	0.5	Per day	562	281	0
LR045 : Carpenter	0.5	Per day	612	306	0
BRM271 : Black glass (I.S.I.) 5mm	1.64	Sqm	705.01	1156.2164	0
BRMMR0008 : Hire charges of drills machine	1	Day	100	100	0
BRMMR0013 : Al. wheel runner	8	Each	25	200	0
BRMMR0012 : Window pile	7.5	Mtr	10	75	0
BRMMR0011 : U rubber beading	9.75	Mtr	15	146.25	0
BRMMR0010 : Al. Screws of different sizes	1	L.S.	30	30	0
BRMMR0009 : PVC Plug	8	Each	1.5	12	0
BRM304 : Aluminium extruded section	7.6482	kg	297.97	2278.934154	0

Total Amount (a+b+c)	6126.400554
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	459.48004155
CONTRACTOR PROFIT @ 7.5% (+)	493.94104466625
LABOUR CESS @ 1% (+)	70.798216402163
Grand Total	7150.6198566184
Say For Unit 1 (Grand Total/1.49)	4799.0737292741

Item 8

Other Building Items. (AR1911): Supplying, fitting and fixing of Stainless steel of 304 grade in hand railing using 50mm dia of 2mm thick circular pipe with Balustrade of size 32mm x 32mm x 2mm @ 0.90mtr. C/C and stainless square pipe bracing of size 32mm x 32mm x 2mm in 3 rows in staircase as per approved design and specification, buffing, polishing etc with cost, conveyance, taxes of all materials, labour, T&P etc. required for the complete in all respect. and as per direction of Engineer in Charge

Sub-Item of Work

Stainless steel of 304 grade in hand railing using 50mm dia of 2mm

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR011 : Helper to carpenter or Blacksmith/ Painter/ Blaster/Plumber/ Electrician/ Fitter/Welder	0.89	Per day	512	455.68	0
LR047 : Fitter	0.89	Per day	612	544.68	0
BRMMR0024 : Buffing, Polishing etc.	1	L.S.	178.42	178.42	0
BRMMR0023 : Fabrication	34.16	kg	10	341.6	0
BRMMR0022 : Stainless steel square pipe bracing of size 32mmx32mmx2mm in 3 rows	16.63	kg	256.62	4267.5906	0

BRMMR0021 : Balustrade of size 30mmx32mmx2mm	6.12	kg	256.62	1570.5144	0
BRMMR0020 : Railing 50mm outer dia of 2mm thick	11.41	kg	240.24	2741.1384	0

Total Amount (a+b+c)	10099.6234
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	757.471755
CONTRACTOR PROFIT @ 7.5% (+)	814.282136625
LABOUR CESS @ 1% (+)	116.71377291625
Grand Total	11788.091064541
Say For Unit 1 (Grand Total/3.26)	3615.9788541538

Item 9

Painting (AR0901d): Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.

Sub-Item of Work

Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM253 : Wall cement primer (I.S.I.) Water bound	0.7812	1 Ltr	159.03	124.234236	0
LR048 : Painter/ Polisher	0.5	Per day	612	306	0
LR001 : Male mulia	0.5	Per day	462	231	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM253 : Wall cement primer (I.S.I.) Water bound	0.7812	1 Ltr	0.37866	0.295809192	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM253 : Wall cement primer (I.S.I.) Water bound	0.7812	1 Ltr	0	0	0

Total Amount (a+b+c)	661.530045192
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	49.6147533894
CONTRACTOR PROFIT @ 7.5% (+)	53.335859893605
LABOUR CESS @ 1% (+)	7.64480658475
Grand Total	772.12546505976
Say For Unit 1 (Grand Total/9.3)	83.024243554812

Item 10

Painting (AR0920): Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)

Sub-Item of Work

Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM140 : Plastic Emulsion paint	1.25	1 Litre	249.34	311.675	0
LR048 : Painter/ Polisher	0.54	Per day	612	330.48	0
LR001 : Male mulia	0.64	Per day	462	295.68	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM140 : Plastic Emulsion paint	1.25	1 Litre	0.37866	0.473325	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM140 : Plastic Emulsion paint	1.25	1 Litre	0	0	0

Total Amount (a+b+c)

938.308325

Total GST (a)

0

OVERHEAD CHARGES @ 7.5% (+)

70.373124375

CONTRACTOR PROFIT @ 7.5% (+)

75.651108703125

LABOUR CESS @ 1% (+)

10.843325580781

Grand Total

1095.1758836589

Say For Unit 1 (Grand Total/10)

109.51758836589

Item 11

Flooring (AR0817b): Fixing ceramic tiles (20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) in wall cladding on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.

Sub-Item of Work

Fixing ceramic tiles (20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM129 : Tiles up to 20cmx30cm / 20cm x 20cm special plain /printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753	10	1 Sqm.	405.2	4052	0

LR001 : Male mulia	3.25	Per day	462	1501.5	0
LR044 : Mason	3.25	Per day	612	1989	0
BRM340 : Cement	1.375	1 Qntl.	537.2	738.65	132.957
BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	76.88	11.532	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM129 : Tiles up to 20cmx30cm / 20cm x 20cm special plain /printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753	10	1 Sqm.	13.2011669	132.011669	0
BRM340 : Cement	1.375	1 Qntl.	24.787	34.082125	0
BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	419.23	62.8845	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM129 : Tiles up to 20cmx30cm / 20cm x 20cm special plain /printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753	10	1 Sqm.	0	0	0
BRM340 : Cement	1.375	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	427.25	64.0875	0

Total Amount (a+b+c)	8585.747794
Total GST (a)	132.957
OVERHEAD CHARGES @ 7.5% (+)	653.90285955
CONTRACTOR PROFIT @ 7.5% (+)	702.94557401625
LABOUR CESS @ 1% (+)	100.75553227566
Grand Total	10176.308759842
Say For Unit 1 (Grand Total/10)	1017.6308759842

Item 12

Concrete (AR0303a): Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	2.5	Per day	462	1155	0
LR025 : Mason	0.18	Per day	562	101.16	0
BRM340 : Cement	2.29	1 Qntl.	537.2	1230.188	221.43384
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	76.88	36.9024	0
BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	1 Cum.	787.36	755.8656	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	24.787	56.76223	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	419.23	201.2304	0
BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	1 Cum.	861.91	827.4336	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	427.25	205.08	0
BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	1 Cum.	522.5	501.6	0

Total Amount (a+b+c)	5718.02223
Total GST (a)	221.43384
OVERHEAD CHARGES @ 7.5% (+)	445.45920525
CONTRACTOR PROFIT @ 7.5% (+)	478.86864564375
LABOUR CESS @ 1% (+)	68.637839208938
Grand Total	6932.4217601027
Say For Unit 1 (Grand Total/1)	6932.4217601027

Item 13

Concrete (AR0307a): Cement concrete work with (1:2:4) using 12mm size hard granite(hand broken) chips including hoisting and laying in position compacting to proper thickness and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.

Sub-Item of Work

Cement concrete (1:2:4)with 12mm size hard granite(Hand broken)chips per 1cum

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM057 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve)(Hand broken)	0.9	1 Cum.	1050	945	0

LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	3.2	Per day	462	1478.4	0
LR025 : Mason	0.68	Per day	562	382.16	0
BRM340 : Cement	3.23	1 Qntl.	537.2	1735.156	312.32808
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM057 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve)(Hand broken)	0.9	1 Cum.	861.91	775.719	0
BRM340 : Cement	3.23	1 Qntl.	24.787	80.06201	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	419.23	188.6535	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM057 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve)(Hand broken)	0.9	1 Cum.	522.5	470.25	0
BRM340 : Cement	3.23	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	427.25	192.2625	0

Total Amount (a+b+c)	6929.05901
Total GST (a)	312.32808
OVERHEAD CHARGES @ 7.5% (+)	543.10403175
CONTRACTOR PROFIT @ 7.5% (+)	583.83683413125
LABOUR CESS @ 1% (+)	83.683279558813
Grand Total	8452.0112354401
Say For Unit 1 (Grand Total/1)	8452.0112354401

NIHARIKA MOHAPATRA
JE
Baleshwar Block

PURUSOTTAM KARAN
AEE
Baleshwar Block

Uttam Kumar Jena
BDO
Baleshwar Block