

Analysis

**OD/346/3304/116215/393410/00076288 : Beautification of Hanuman Temple at
Patharakhunta
Block : Khaira, Gram Panchayat : Kaithagadia
Created By:Narayan Sahu**

Item 1
Earth Work (AR0102aa): Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge
Sub-Item of Work Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	25.8	Per day	462	11919.6	0
LR001 : Male mulia	25.8	Per day	462	11919.6	0
Total Amount (a+b+c)				23839.2	
Total GST (a)				0	
OVERHEAD CHARGES @ 7.5% (+)				1787.94	
CONTRACTOR PROFIT @ 7.5% (+)				1922.0355	
LABOUR CESS @ 1% (+)				275.491755	
Grand Total				27824.667255	
Say For Unit 1 (Grand Total/100)				278.24667255	

Item 2
Earth Work (AR0115): Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work Filling foundation and plinth with sand well watered and rammed

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	71.94	7194	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0
b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	917.11	91711	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	442.25	44225	0

Total Amount (a+b+c)	148840.32				
Total GST (a)	0				
OVERHEAD CHARGES @ 7.5% (+)	11163.024				
CONTRACTOR PROFIT @ 7.5% (+)	12000.2508				
LABOUR CESS @ 1% (+)	1720.035948				
Grand Total	173723.630748				
Say For Unit 1 (Grand Total/100)	1737.23630748				

Item 3
Concrete (AR0303a): Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work Cement concrete (1:3:6) with 4 cm. hard granite(Hand Broken) metal

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	2.5	Per day	462	1155	0
LR025 : Mason	0.18	Per day	562	101.16	0
BRM340 : Cement	2.29	1 Qntl.	537.2	1230.188	221.43384
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	76.88	36.9024	0
BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	1 Cum.	787.36	755.8656	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	24.787	56.76223	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	917.11	440.2128	0
BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	1 Cum.	757.75	727.44	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	442.25	212.28	0
BRM045 : Granite Stone broken metal 40mm. size (Hand broken)	0.96	1 Cum.	1125.5	1080.48	0

Total Amount (a+b+c)	6443.09103
Total GST (a)	221.43384
OVERHEAD CHARGES @ 7.5% (+)	499.83936525
CONTRACTOR PROFIT @ 7.5% (+)	537.32731764375
LABOUR CESS @ 1% (+)	77.016915528937
Grand Total	7778.7084684227
Say For Unit 1 (Grand Total/1)	7778.7084684227

Item 4

Concrete (AR0307): Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaicon and direction of Engineer-in charge.

Sub-Item of Work

Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	3.2	Per day	462	1478.4	0
LR025 : Mason	0.68	Per day	562	382.16	0
BRM340 : Cement	3.23	1 Qntl.	537.2	1735.156	312.32808
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	1396.62	1256.958	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	24.787	80.06201	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	917.11	412.6995	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	757.75	681.975	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	0	0	0

BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	442.25	199.0125	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	1125.5	1012.95	0

Total Amount (a+b+c)	7920.76901
Total GST (a)	312.32808
OVERHEAD CHARGES @ 7.5% (+)	617.48228175
CONTRACTOR PROFIT @ 7.5% (+)	663.79345288125
LABOUR CESS @ 1% (+)	95.143728246312
Grand Total	9609.5165528776
Say For Unit 1 (Grand Total/1)	9609.5165528776

Item 5

Other Building Items. (AR1907): Supplying, fitting, fixing up window (sliding type) made up aluminum Section 9778, as windows frame, section No. 4095,4096 and 9777, 3994 as shutter frame with 5mm thick black glass as panel fitted with rubber beading including locking arrangement including all fitting including cost of materials all taxes labour, T&P etc. complete as per direction of Engineer-in-charge.

Sub-Item of Work
aluminum sliding window (sliding type)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRMMR0005 : Handel with lock	2	Each	40	80	0
LR001 : Male mulia	1.5	Per day	462	693	0
LR011 : Helper to carpenter or Blacksmith/ Painter/ Blaster/Plumber/ Electrician/ Fitter/Welder	1.5	Per day	512	768	0
LR028 : Fitter	0.5	Per day	562	281	0
LR045 : Carpenter	0.5	Per day	612	306	0
BRM271 : Black glass (I.S.I.) 5mm	1.64	Sqm	705.01	1156.2164	0
BRMMR0008 : Hire charges of drills machine	1	Day	100	100	0
BRMMR0013 : Al. wheel runner	8	Each	25	200	0
BRMMR0012 : Window pile	7.5	Mtr	10	75	0
BRMMR0011 : U rubber beading	9.75	Mtr	15	146.25	0
BRMMR0010 : Al. Screws of different sizes	1	L.S.	30	30	0
BRMMR0009 : PVC Plug	8	Each	1.5	12	0
BRM304 : Aluminium extruded section	7.6482	kg	297.97	2278.934154	0

Total Amount (a+b+c)	6126.400554
-----------------------------	-------------

Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	459.48004155
CONTRACTOR PROFIT @ 7.5% (+)	493.94104466625
LABOUR CESS @ 1% (+)	70.798216402163
Grand Total	7150.6198566184
Say For Unit 1 (Grand Total/1.49)	4799.0737292741

Item 6

Masonry Brick Work (AR0603bi): Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work

Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.14	Per day	462	64.68	0
BRMMR0025 : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK	1	1 Cum	33	33	0
LR001 : Male mulia	2.82	Per day	462	1302.84	0
LR025 : Mason	1.05	Per day	562	590.1	0
LR044 : Mason	0.35	Per day	612	214.2	0
BRM340 : Cement	0.672	1 Qntl.	537.2	360.9984	64.979712
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	76.88	21.5264	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance ± 2 %	350	1000 Nos	5.14255	1799.8925	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.672	1 Qntl.	24.787	16.656864	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	917.11	256.7908	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance ± 2 %	350	1000 Nos	2.0421	714.735	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.672	1 Qntl.	0	0	0

BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	442.25	123.83	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	350	1000 Nos	0	0	0

Total Amount (a+b+c)	5499.249964
Total GST (a)	64.979712
OVERHEAD CHARGES @ 7.5% (+)	417.3172257
CONTRACTOR PROFIT @ 7.5% (+)	448.6160176275
LABOUR CESS @ 1% (+)	64.301629193275
Grand Total	6494.4645485208
Say For Unit 1 (Grand Total/1)	6494.4645485208

Item 7

Plastering (AR1004): 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.

Sub-Item of Work
12mm thick cement plaster (1:6) over Brick work in inside

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.05	Per day	462	23.1	0
LR001 : Male mulia	0.07	Per day	462	32.34	0
LR025 : Mason	0.14	Per day	562	78.68	0
BRM340 : Cement	0.0358	1 Qntl.	537.2	19.23176	3.4617168
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	76.88	1.1532	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0358	1 Qntl.	24.787	0.8873746	0
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	917.11	13.75665	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0358	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	442.25	6.63375	0

Total Amount (a+b+c)	175.7827346
Total GST (a)	3.4617168
OVERHEAD CHARGES @ 7.5% (+)	13.443333855
CONTRACTOR PROFIT @ 7.5% (+)	14.451583894125

LABOUR CESS @ 1% (+)	2.0713936914913
Grand Total	209.21076284062
Say For Unit 1 (Grand Total/1)	209.21076284062

Item 8

Plastering (AR1014): 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.

Sub-Item of Work
16mm thick cement Plaster in CM (1:6) over brick work in inside.

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.11	Per day	462	50.82	0
LR001 : Male mulia	0.13	Per day	462	60.06	0
LR025 : Mason	0.16	Per day	562	89.92	0
BRM340 : Cement	0.043	1 Qntl.	537.2	23.0996	4.157928
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	76.88	1.38384	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.043	1 Qntl.	24.787	1.065841	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	917.11	16.50798	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.043	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	442.25	7.9605	0

Total Amount (a+b+c)	250.817761
Total GST (a)	4.157928
OVERHEAD CHARGES @ 7.5% (+)	19.123176675
CONTRACTOR PROFIT @ 7.5% (+)	20.557414925625
LABOUR CESS @ 1% (+)	2.9465628060062
Grand Total	297.60284340663
Say For Unit 1 (Grand Total/1)	297.60284340663

Item 9

Painting (AR0901di): Priming one coat with outer surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.

Sub-Item of Work

Priming one coat with outer surface primer of approved quality water-bound primer over plastering surfaces(outer surface)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM253 : Wall cement primer (I.S.I.) Water bound	0.84	1 Ltr	159.03	133.5852	0
LR048 : Painter/ Polisher	0.5	Per day	612	306	0
LR001 : Male mulia	0.5	Per day	462	231	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM253 : Wall cement primer (I.S.I.) Water bound	0.84	1 Ltr	0.24787	0.2082108	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM253 : Wall cement primer (I.S.I.) Water bound	0.84	1 Ltr	0	0	0

Total Amount (a+b+c)	670.7934108				
Total GST (a)	0				
OVERHEAD CHARGES @ 7.5% (+)	50.30950581				
CONTRACTOR PROFIT @ 7.5% (+)	54.08271874575				
LABOUR CESS @ 1% (+)	7.7518563535575				
Grand Total	782.93749170931				
Say For Unit 1 (Grand Total/9.3)	84.186827065517				

Item 10

Painting (AR0918Ai): Finishing wall one coat with weather coat including all costs of labour, Paint, Primer and Brushes required for the work etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work

Finishing wall one coat with weather coat

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	0.75	1 Ltr	194.79	146.0925	0
LR001 : Male mulia	0.43	Per day	462	198.66	0
LR048 : Painter/ Polisher	0.36	Per day	612	220.32	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	0.75	1 Ltr	0.24787	0.1859025	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	0.75	1 Ltr	0	0	0

Total Amount (a+b+c)	565.2584025				
Total GST (a)	0				
OVERHEAD CHARGES @ 7.5% (+)	42.3943801875				
CONTRACTOR PROFIT @ 7.5% (+)	45.573958701562				
LABOUR CESS @ 1% (+)	6.5322674138906				
Grand Total	659.75900880295				
Say For Unit 1 (Grand Total/10)	65.975900880295				

KARTIK BEHERA
JE
Khaira Block

Uttam Ku Sahoo
AEE
Khaira Block

Narayan Sahu
BDO
Khaira Block