

Analysis

OD/350/3340/117031/398664/00063336 : Development of Binikei CC Ekadal
Block : Narasinghpur, Gram Panchayat : Ekadal
Created By:PRALAYANANDA SATPATHY

Item 1
Other Building Items. (AR1902): Finishing surface of walls with cement based wall putty (water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes,labour,T&P,etc.complete. and as per the direction of Engineer in Charge.
Sub-Item of Work cement based wall putty (water based)

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRMMR0038 : Cement based putty	8	kg	30	240	0
LR001 : Male mulia	0.57	Per day	462	263.34	0
LR025 : Mason	0.5	Per day	562	281	0

Total Amount (a+b+c)	784.34
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	58.8255
CONTRACTOR PROFIT @ 7.5% (+)	63.2374125
LABOUR CESS @ 1% (+)	9.064029125
Grand Total	915.466941625
Say For Unit 1 (Grand Total/10)	91.5466941625

Item 2
Painting (AR0920): Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)
Sub-Item of Work Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside)

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM140 : Plastic Emulsion paint	1.25	1 Litre	249.34	311.675	0
LR048 : Painter/ Polisher	0.54	Per day	612	330.48	0
LR001 : Male mulia	0.64	Per day	462	295.68	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST

BRM140 : Plastic Emulsion paint	1.25	1 Litre	0.30732	0.38415	0
---------------------------------	------	---------	---------	---------	---

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM140 : Plastic Emulsion paint	1.25	1 Litre	0	0	0

Total Amount (a+b+c)	938.21915				
Total GST (a)	0				
OVERHEAD CHARGES @ 7.5% (+)	70.36643625				
CONTRACTOR PROFIT @ 7.5% (+)	75.64391896875				
LABOUR CESS @ 1% (+)	10.842295052188				
Grand Total	1095.0718002709				
Say For Unit 1 (Grand Total/10)	109.50718002709				

Item 3

Painting (AR0918ca): Finishing wall surface two coats with weather coat with one coat oilbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)

Sub-Item of Work

Finishing wall two coats with weather coat with one coat oilbound Primer

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
Combine :: Painting (AR0918f)					
BRM255 : Weather Coat (I.S.I.)	0.125	1 Ltr	194.79	24.34875	0
LR001 : Male mulia	0.064	Per day	462	29.568	0
LR048 : Painter/ Polisher	0.054	Per day	612	33.048	0
Combine :: Painting (AR0901ci)					
BRM252 : Wall cement primer (I.S.I.) Oil bound	0.084	1 Ltr	125.5	10.542	0
LR048 : Painter/ Polisher	0.053763440860215	Per day	612	32.903225806452	0
LR001 : Male mulia	0.053763440860215	Per day	462	24.838709677419	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	0.125	1 Ltr	0.30732	0.038415	0
BRM252 : Wall cement primer (I.S.I.) Oil bound	0.084	1 Ltr	0.30732	0.02581488	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	0.125	1 Ltr	0	0	0
BRM252 : Wall cement primer (I.S.I.) Oil bound	0.084	1 Ltr	0	0	0

Total Amount (a+b+c)	155.31291536387
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	11.64846865229
CONTRACTOR PROFIT @ 7.5% (+)	12.522103801212
LABOUR CESS @ 1% (+)	1.7948348781737
Grand Total	181.27832269555
Say For Unit 1 (Grand Total/1)	181.27832269555

Item 4

Painting (AR0901ci): Priming one coat with outer surface primer of approved quality oil-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.

Sub-Item of Work

Priming one coat with outer surface primer of approved quality oil-bound primer over plastering surfaces(Outer surface)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM252 : Wall cement primer (I.S.I.) Oil bound	0.7812	1 Ltr	125.5	98.0406	0
LR048 : Painter/ Polisher	0.5	Per day	612	306	0
LR001 : Male mulia	0.5	Per day	462	231	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM252 : Wall cement primer (I.S.I.) Oil bound	0.7812	1 Ltr	0.30732	0.240078384	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM252 : Wall cement primer (I.S.I.) Oil bound	0.7812	1 Ltr	0	0	0

Total Amount (a+b+c)	635.280678384
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	47.6460508788
CONTRACTOR PROFIT @ 7.5% (+)	51.21950469471
LABOUR CESS @ 1% (+)	7.3414623395751
Grand Total	741.48769629709
Say For Unit 1 (Grand Total/9.3)	79.729859816891

Item 5

Painting (AR0903b): Painting two coats of enamel paint with a coat of red oxide primer over iron surface including all costs of labour, Paint, Primer, brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work

Painting two coats of enamel paint with a coat of red oxide primer over iron surface

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
Combine :: Painting (AR0901b)					
LR048 : Painter/ Polisher	0.053763440860215	Per day	612	32.903225806452	0
BRM137 : Red oxide Primer	0.054	1 Litre	142.7	7.7058	0
LR001 : Male mulia	0.053763440860215	Per day	462	24.838709677419	0
Combine :: Painting (AR0903)					
LR048 : Painter/ Polisher	0.13440860215054	Per day	612	82.258064516129	0
LR001 : Male mulia	0.11827956989247	Per day	462	54.645161290323	0
BRM141 : Enamel paint	0.125	1 Litre	203.5	25.4375	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM137 : Red oxide Primer	0.054	1 Litre	0.30732	0.01659528	0
BRM141 : Enamel paint	0.125	1 Litre	0.30732	0.038415	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM137 : Red oxide Primer	0.054	1 Litre	0	0	0
BRM141 : Enamel paint	0.125	1 Litre	0	0	0

Total Amount (a+b+c)

227.84347157032

Total GST (a)

0

OVERHEAD CHARGES @ 7.5% (+)

17.088260367774

CONTRACTOR PROFIT @ 7.5% (+)

18.369879895357

LABOUR CESS @ 1% (+)

2.6330161183345

Grand Total

265.93462795179

Say For Unit 1 (Grand Total/1)

265.93462795179

Item 6

Flooring (AR0817b): Fixing ceramic tiles (20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753) in wall cladding on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.

Sub-Item of Work

Fixing ceramic tiles (20cmx30cm / 20cmx20cm special plain/printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM129 : Tiles up to 20cmx30cm / 20cm x 20cm special plain /printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753	10	1 Sqm.	385	3850	0
LR001 : Male mulia	3.25	Per day	462	1501.5	0
LR044 : Mason	3.25	Per day	612	1989	0
BRM340 : Cement	1.375	1 Qntl.	538.98	741.0975	133.39755
BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	76.88	11.532	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM129 : Tiles up to 20cmx30cm / 20cm x 20cm special plain /printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753	10	1 Sqm.	11.2375001	112.375001	0
BRM340 : Cement	1.375	1 Qntl.	30.732	42.2565	0
BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	471.31	70.6965	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM129 : Tiles up to 20cmx30cm / 20cm x 20cm special plain /printed series ceramic wall tiles of premium grade having thickness 6.5mm to 6.7mm confirming to IS 13753	10	1 Sqm.	0	0	0
BRM340 : Cement	1.375	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	169.25	25.3875	0

Total Amount (a+b+c)	8343.845001
Total GST (a)	133.39755
OVERHEAD CHARGES @ 7.5% (+)	635.793191325
CONTRACTOR PROFIT @ 7.5% (+)	683.47768067437
LABOUR CESS @ 1% (+)	97.965134229994
Grand Total	9894.4785572294
Say For Unit 1 (Grand Total/10)	989.44785572294

PRIYARANJAN
JE
Narasinghpur Block

SUSHIL
AEE
Narasinghpur Block

PRALAYANANDA SATPATHY
BDO
Narasinghpur Block