

## Analysis

**OD/367/3523/117261/403347/00070224 : CONST. OF CC ROAD AT DRUGAPUR  
ADIBASISAH VILLAGE ROAD  
Block : Bhapur, Gram Panchayat : Bhapur  
Created By:SARADA PRASANNA PANDA**

### Item 1

**Earth Work (AR0102aa):** Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge

Sub-Item of Work

**Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift**

#### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	25.8	Per day	462	11919.6	0
LR001 : Male mulia	25.8	Per day	462	11919.6	0

**Total Amount (a+b+c)**

23839.2

**Total GST (a)**

0

**OVERHEAD CHARGES @ 7.5% (+)**

1787.94

**CONTRACTOR PROFIT @ 7.5% (+)**

1922.0355

**LABOUR CESS @ 1% (+)**

275.491755

**Grand Total**

27824.667255

**Say For Unit 1 (Grand Total/100)**

278.24667255

### Item 2

**Earth Work (AR0115):** Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

**Filling foundation and plinth with sand well watered and rammed**

#### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	56.57	5657	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0

#### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	367.15	36715	0

<b>c) Royalty Rate Details</b>					
Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM029</b> : Sand for filling and road blinding	100	1 Cum	305.25	30525	0

<b>Total Amount (a+b+c)</b>	78607.32				
<b>Total GST (a)</b>	0				
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	5895.549				
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	6337.715175				
<b>LABOUR CESS @ 1% (+)</b>	908.40584175				
<b>Grand Total</b>	91748.99001675				
<b>Say For Unit 1 (Grand Total/100)</b>	917.4899001675				

<b>Item 3</b>
<b>Concrete (AR0303):</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work <b>Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal</b>

<b>a) Specific Rate Details</b>					
Particular	Quantity	Unit	Rate	Amount	GST
<b>LR025</b> : Mason	0.18	Per day	562	101.16	0
<b>LR002</b> : Female mulia	1.4	Per day	462	646.8	0
<b>LR001</b> : Male mulia	2.5	Per day	462	1155	0
<b>BRM340</b> : Cement	2.29	1 Qntl.	523.07	1197.8303	215.609454
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.48	1 Cum	63	30.24	0
<b>BRM044</b> : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	954	915.84	0

<b>b) Carriage Rate Details</b>					
Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	2.29	1 Qntl.	24.787	56.76223	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.48	1 Cum	367.15	176.232	0
<b>BRM044</b> : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	406.21	389.9616	0

<b>c) Royalty Rate Details</b>					
Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	2.29	1 Qntl.	0	0	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.48	1 Cum	305.25	146.52	0
<b>BRM044</b> : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	199.5	191.52	0

<b>Total Amount (a+b+c)</b>	5007.86613
<b>Total GST (a)</b>	215.609454
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	391.7606688
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	421.14271896
<b>LABOUR CESS @ 1% (+)</b>	60.3637897176
<b>Grand Total</b>	6096.7427614776
<b>Say For Unit 1 (Grand Total/1)</b>	6096.7427614776

#### Item 4

**Concrete (AR0307):** Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.

Sub-Item of Work  
**First floor**

#### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>LR002</b> : Female mulia	1.61	Per day	462	743.82	0
<b>LR001</b> : Male mulia	3.68	Per day	462	1700.16	0
<b>LR025</b> : Mason	0.782	Per day	562	439.484	0
<b>BRM340</b> : Cement	3.23	1 Qntl.	523.07	1689.5161	304.112898
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	63	28.35	0
<b>BRM056</b> : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	1396.62	1256.958	0

#### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	3.23	1 Qntl.	24.787	80.06201	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	367.15	165.2175	0
<b>BRM056</b> : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	406.21	365.589	0

#### c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	3.23	1 Qntl.	0	0	0

<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	305.25	137.3625	0
<b>BRM056</b> : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	199.5	179.55	0

<b>Total Amount (a+b+c)</b>	6786.06911				
<b>Total GST (a)</b>	304.112898				
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	531.7636506				
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	571.645924395				
<b>LABOUR CESS @ 1% (+)</b>	81.93591582995				
<b>Grand Total</b>	8275.5274988249				
<b>Say For Unit 1 (Grand Total/1)</b>	8275.5274988249				

**Santosh Kumar Mallick**  
**JE**  
**Bhapur Block**

**Ritimukta Swain**  
**AEE**  
**Bhapur Block**

**SARADA PRASANNA PANDA**  
**BDO**  
**Bhapur Block**