

## Analysis

**OD/373/3583/121675/384592/00067367 : Construction of Cultural Centre at Fikodchundi**  
**Block : Lathikata, Gram Panchayat : Bad-Dalki**  
**Created By: BDO LATHIKATA**

<b>Item 1</b>
<b>Earth Work (AR0102aa):</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge
Sub-Item of Work <b>Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift</b>

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	25.8	Per day	462	11919.6	0
LR001 : Male mulia	25.8	Per day	462	11919.6	0
<b>Total Amount (a+b+c)</b>				23839.2	
<b>Total GST (a)</b>					0
<b>OVERHEAD CHARGES @ 7.5% (+)</b>					1787.94
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>					1922.0355
<b>LABOUR CESS @ 1% (+)</b>					275.491755
<b>Grand Total</b>					27824.667255
<b>Say For Unit 1 (Grand Total/100)</b>					278.24667255

<b>Item 2</b>
<b>Earth Work (AR0115):</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work <b>Filling foundation and plinth with sand well watered and rammed</b>

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	71.94	7194	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	445.27	44527	0

c) Royalty Rate Details					

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM029</b> : Sand for filling and road blinding	100	1 Cum	110.25	11025	0
<b>Total Amount (a+b+c)</b>				68456.32	
<b>Total GST (a)</b>					0
<b>OVERHEAD CHARGES @ 7.5% (+)</b>				5134.224	
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>				5519.2908	
<b>LABOUR CESS @ 1% (+)</b>				791.098348	
<b>Grand Total</b>				79900.933148	
<b>Say For Unit 1 (Grand Total/100)</b>				799.00933148	

### Item 3

**Concrete (AR0303):** Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work  
**Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal**

#### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>LR025</b> : Mason	0.18	Per day	562	101.16	0
<b>LR002</b> : Female mulia	1.4	Per day	462	646.8	0
<b>LR001</b> : Male mulia	2.5	Per day	462	1155	0
<b>BRM340</b> : Cement	2.29	1 Qntl.	530.51	1214.8679	218.676222
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.48	1 Cum	76.88	36.9024	0
<b>BRM044</b> : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	995.25	955.44	0

#### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	2.29	1 Qntl.	24.787	56.76223	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.48	1 Cum	445.27	213.7296	0
<b>BRM044</b> : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	549.43	527.4528	0

#### c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	2.29	1 Qntl.	0	0	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.48	1 Cum	110.25	52.92	0
<b>BRM044</b> : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	409.5	393.12	0

<b>Total Amount (a+b+c)</b>	5354.15493
-----------------------------	------------

<b>Total GST (a)</b>	218.676222
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	417.9623364
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	449.30951163
<b>LABOUR CESS @ 1% (+)</b>	64.4010300003
<b>Grand Total</b>	6504.5040300303
<b>Say For Unit 1 (Grand Total/1)</b>	6504.5040300303

#### Item 4

**Masonry Brick Work (AR0603b):** Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm<sup>2</sup> with dimensional tolerance  $\pm 8$  percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work

**Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth**

#### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.14	Per day	462	64.68	0
LR001 : Male mulia	2.82	Per day	462	1302.84	0
LR025 : Mason	1.05	Per day	562	590.1	0
LR044 : Mason	0.35	Per day	612	214.2	0
BRM340 : Cement	0.672	1 Qntl.	530.51	356.50272	64.1704896
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	76.88	21.5264	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm <sup>2</sup> with dimensional tolerance $\pm 2$ %	350	1000 Nos	5.14255	1799.8925	0

#### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.672	1 Qntl.	24.787	16.656864	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	445.27	124.6756	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm <sup>2</sup> with dimensional tolerance $\pm 2$ %	350	1000 Nos	1.1586	405.51	0

#### c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.672	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	110.25	30.87	0

<b>BRM005</b> : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	350	1000 Nos	0	0	0
---	-----	----------	---	---	---

<b>Total Amount (a+b+c)</b>	4927.454084
<b>Total GST (a)</b>	64.1704896
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	374.37184302
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	402.4497312465
<b>LABOUR CESS @ 1% (+)</b>	57.684461478665
<b>Grand Total</b>	5826.1306093452
<b>Say For Unit 1 (Grand Total/1)</b>	5826.1306093452

### Item 5

**Masonry Brick Work (AR0603bi):** Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm2 with dimensional tolerance  $\pm 8$  percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work

**Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure**

#### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>LR002</b> : Female mulia	0.14	Per day	462	64.68	0
<b>BRMMR0025</b> : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK	1	1 Cum	33	33	0
<b>LR001</b> : Male mulia	2.82	Per day	462	1302.84	0
<b>LR025</b> : Mason	1.05	Per day	562	590.1	0
<b>LR044</b> : Mason	0.35	Per day	612	214.2	0
<b>BRM340</b> : Cement	0.672	1 Qntl.	530.51	356.50272	64.1704896
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.28	1 Cum	76.88	21.5264	0
<b>BRM005</b> : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	350	1000 Nos	5.14255	1799.8925	0

#### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	0.672	1 Qntl.	24.787	16.656864	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.28	1 Cum	445.27	124.6756	0
<b>BRM005</b> : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	350	1000 Nos	1.1586	405.51	0

<b>c) Royalty Rate Details</b>					
<b>Particular</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate</b>	<b>Amount</b>	<b>GST</b>
<b>BRM340</b> : Cement	0.672	1 Qntl.	0	0	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.28	1 Cum	110.25	30.87	0
<b>BRM005</b> : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	350	1000 Nos	0	0	0

<b>Total Amount (a+b+c)</b>	4960.454084
<b>Total GST (a)</b>	64.1704896
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	376.84684302
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	405.1103562465
<b>LABOUR CESS @ 1% (+)</b>	58.065817728665
<b>Grand Total</b>	5864.6475905952
<b>Say For Unit 1 (Grand Total/1)</b>	5864.6475905952

### Item 6

**R.C.C. Work (AR0404Aa):** Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)

Sub-Item of Work

**Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips**

### a) Specific Rate Details

<b>Particular</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate</b>	<b>Amount</b>	<b>GST</b>
<b>Combine :: R.C.C. Work (AR0404A)</b>					
<b>PM096</b> : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0
<b>PM083</b> : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0
<b>LR001</b> : Male mulia	1.3333	Per day	462	615.9846	0
<b>LR025</b> : Mason	0.1	Per day	562	56.2	0
<b>LR010</b> : Mate	0.0573	Per day	512	29.3376	0
<b>BRM340</b> : Cement	3.4733	1 Qntl.	530.51	1842.620383	331.67166894
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0
<b>BRM060</b> : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1390	500.4	0

<b>BRM052</b> : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1382.29	746.4366	0
<b>Combine :: R.C.C. Work (AR0410c)</b>					
<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	1Cum.	58374.79	233.79103395	0
<b>BRM092</b> : Non-sal bullahs 75mm. mean dia of any length.	0.189	1Mtr.	30.81	5.82309	0
<b>LR008</b> : Sangi mulia	0.075	Per day	512	38.4	0
<b>LR027</b> : Carpenter	0.075	Per day	562	42.15	0

#### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	3.4733	1 Qntl.	30.732	106.7414556	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	445.27	200.3715	0
<b>BRM060</b> : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	549.43	197.7948	0
<b>BRM052</b> : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	549.43	296.6922	0
<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	1Cum.	455.12	1.8227556	0
<b>BRM092</b> : Non-sal bullahs 75mm. mean dia of any length.	0.000921	1Mtr.	455.12	0.41916552	0

#### c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	3.4733	1 Qntl.	0	0	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	110.25	49.6125	0
<b>BRM060</b> : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	409.5	147.42	0
<b>BRM052</b> : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	409.5	221.13	0
<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	1Cum.	0	0	0
<b>BRM092</b> : Non-sal bullahs 75mm. mean dia of any length.	0.000921	1Mtr.	0	0	0

<b>Total Amount (a+b+c)</b>	5739.56368367
<b>Total GST (a)</b>	331.67166894
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	455.34265144575
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	489.49335030418
<b>LABOUR CESS @ 1% (+)</b>	70.160713543599

<b>Grand Total</b>	7086.2320679035
<b>Say For Unit 1 (Grand Total/1)</b>	7086.2320679035

### Item 7

**R.C.C. Work (AR0404Ac):** Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge. (RCC Beams, Column, Girder & Bressmer etc)

Sub-Item of Work

**Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips**

#### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>Combine :: R.C.C. Work (AR0404A)</b>					
<b>PM096</b> : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0
<b>PM083</b> : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0
<b>LR001</b> : Male mulia	1.3333	Per day	462	615.9846	0
<b>LR025</b> : Mason	0.1	Per day	562	56.2	0
<b>LR010</b> : Mate	0.0573	Per day	512	29.3376	0
<b>BRM340</b> : Cement	3.4733	1 Qntl.	530.51	1842.620383	331.67166894
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0
<b>BRM060</b> : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1390	500.4	0
<b>BRM052</b> : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1382.29	746.4366	0
<b>Combine :: R.C.C. Work (AR0410d)</b>					
<b>BRM084</b> : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	4.4196	1Mtr	51.87	229.244652	0
<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.041529	1Cum.	58374.79	2424.24665391	0
<b>LR008</b> : Sangi mulia	5.23875	Per day	512	2682.24	0
<b>LR027</b> : Carpenter	5.23875	Per day	562	2944.1775	0

#### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
------------	----------	------	------	--------	-----

<b>BRM340</b> : Cement	3.4733	1 Qntl.	30.732	106.7414556	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	445.27	200.3715	0
<b>BRM060</b> : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	549.43	197.7948	0
<b>BRM052</b> : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	549.43	296.6922	0
<b>BRM084</b> : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.045339	1Mtr	455.12	20.63468568	0
<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.041529	1Cum.	455.12	18.90067848	0

**c) Royalty Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	3.4733	1 Qntl.	0	0	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	110.25	49.6125	0
<b>BRM060</b> : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	409.5	147.42	0
<b>BRM052</b> : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	409.5	221.13	0
<b>BRM084</b> : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.045339	1Mtr	0	0	0
<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.041529	1Cum.	0	0	0

<b>Total Amount (a+b+c)</b>	13736.60180867
<b>Total GST (a)</b>	331.67166894
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	1055.1205108207
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	1134.2545491323
<b>LABOUR CESS @ 1% (+)</b>	162.57648537563
<b>Grand Total</b>	16420.225022939
<b>Say For Unit 1 (Grand Total/1)</b>	16420.225022939

**Item 8**

**R.C.C. Work (AR0404Ad):** Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Lintels)

Sub-Item of Work

**Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips**

**a) Specific Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>Combine :: R.C.C. Work (AR0404A)</b>					

<b>PM096</b> : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0
<b>PM083</b> : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0
<b>LR001</b> : Male mulia	1.3333	Per day	462	615.9846	0
<b>LR025</b> : Mason	0.1	Per day	562	56.2	0
<b>LR010</b> : Mate	0.0573	Per day	512	29.3376	0
<b>BRM340</b> : Cement	3.4733	1 Qntl.	530.51	1842.620383	331.67166894
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0
<b>BRM060</b> : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1390	500.4	0
<b>BRM052</b> : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1382.29	746.4366	0
<b>Combine :: R.C.C. Work (AR0410e)</b>					
<b>BRM094</b> : Non-sal bullahs 125mm. mean dia of any length.	3.7695	1Mtr.	41.81	157.602795	0
<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0741335	1Cum.	58374.79	4327.527494465	0
<b>LR008</b> : Sangi mulia	2.24375	Per day	512	1148.8	0
<b>LR027</b> : Carpenter	2.24375	Per day	562	1260.9875	0

#### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	3.4733	1 Qntl.	24.787	86.0926871	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	445.27	200.3715	0
<b>BRM060</b> : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	549.43	197.7948	0
<b>BRM052</b> : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	549.43	296.6922	0
<b>BRM094</b> : Non-sal bullahs 125mm. mean dia of any length.	0.049542	1Mtr.	455.12	22.54755504	0
<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0741335	1Cum.	455.12	33.73963852	0

#### c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	3.4733	1 Qntl.	0	0	0

<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	110.25	49.6125	0
<b>BRM060</b> : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	409.5	147.42	0
<b>BRM052</b> : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	409.5	221.13	0
<b>BRM094</b> : Non-sal bullahs 125mm. mean dia of any length.	0.049542	1Mtr.	0	0	0
<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0741335	1Cum.	0	0	0

<b>Total Amount (a+b+c)</b>	12347.713853125
<b>Total GST (a)</b>	331.67166894
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	950.95391415487
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	1022.2754577165
<b>LABOUR CESS @ 1% (+)</b>	146.52614893936
<b>Grand Total</b>	14799.141042876
<b>Say For Unit 1 (Grand Total/1)</b>	14799.141042876

### Item 9

**Concrete (AR0307):** Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaicon and direction of Engineer-in charge.

Sub-Item of Work

**Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum**

#### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>LR002</b> : Female mulia	1.4	Per day	462	646.8	0
<b>LR001</b> : Male mulia	3.2	Per day	462	1478.4	0
<b>LR025</b> : Mason	0.68	Per day	562	382.16	0
<b>BRM340</b> : Cement	3.23	1 Qntl.	530.51	1713.5473	308.438514
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0
<b>BRM056</b> : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	1396.62	1256.958	0

#### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	3.23	1 Qntl.	24.787	80.06201	0

<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	445.27	200.3715	0
<b>BRM056</b> : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	549.43	494.487	0

<b>c) Royalty Rate Details</b>					
Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	3.23	1 Qntl.	0	0	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	110.25	49.6125	0
<b>BRM056</b> : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	409.5	368.55	0

<b>Total Amount (a+b+c)</b>	6705.54431
<b>Total GST (a)</b>	308.438514
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	526.0487118
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	565.502365185
<b>LABOUR CESS @ 1% (+)</b>	81.05533900985
<b>Grand Total</b>	8186.5892399948
<b>Say For Unit 1 (Grand Total/1)</b>	8186.5892399948

<b>Item 10</b>
<b>R.C.C. Work (AR0409):</b> Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.
Sub-Item of Work <b>Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position</b>

<b>a) Specific Rate Details</b>					
Particular	Quantity	Unit	Rate	Amount	GST
<b>LR001</b> : Male mulia	8	Per day	462	3696	0
<b>LR046</b> : Blacksmith	3	Per day	612	1836	0
<b>LR010</b> : Mate	0.44	Per day	512	225.28	0
<b>BRM162</b> : Binding Wire.	8	1 Kg.	90.1	720.8	0
<b>BRM341</b> : Steel	10.5	1 Qntl.	6379.83	66988.215	12057.8787

<b>b) Carriage Rate Details</b>					
Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM341</b> : Steel	10.5	1 Qntl.	56.89	597.345	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	10.5	1 Qntl.	0	0	0

Total Amount (a+b+c)	74063.64				
Total GST (a)	12057.8787				
OVERHEAD CHARGES @ 7.5% (+)	6459.1139025				
CONTRACTOR PROFIT @ 7.5% (+)	6943.5474451875				
LABOUR CESS @ 1% (+)	995.24180047688				
Grand Total	100519.42184816				
Say For Unit 1 (Grand Total/10)	10051.942184816				

### Item 11

**Plastering (AR1004):** 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.

Sub-Item of Work

**12mm thick cement plaster (1:6) over Brick work in inside**

### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.05	Per day	462	23.1	0
LR001 : Male mulia	0.07	Per day	462	32.34	0
LR025 : Mason	0.14	Per day	562	78.68	0
BRM340 : Cement	0.0358	1 Qntl.	530.51	18.992258	3.41860644
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	76.88	1.1532	0

### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0358	1 Qntl.	24.787	0.8873746	0
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	445.27	6.67905	0

### c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0358	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	110.25	1.65375	0

Total Amount (a+b+c)	163.4856326				
Total GST (a)	3.41860644				
OVERHEAD CHARGES @ 7.5% (+)	12.517817928				

<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	13.4566542726
<b>LABOUR CESS @ 1% (+)</b>	1.928787112406
<b>Grand Total</b>	194.80749835301
<b>Say For Unit 1 (Grand Total/1)</b>	194.80749835301

## Item 12

**Plastering (AR1014):** 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.

Sub-Item of Work

**16mm thick cement Plaster in CM (1:6) over brick work in inside.**

### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.11	Per day	462	50.82	0
LR001 : Male mulia	0.13	Per day	462	60.06	0
LR025 : Mason	0.16	Per day	562	89.92	0
BRM340 : Cement	0.043	1 Qntl.	530.51	22.81193	4.1061474
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	76.88	1.38384	0

### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.043	1 Qntl.	24.787	1.065841	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	445.27	8.01486	0

### c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.043	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	110.25	1.9845	0

<b>Total Amount (a+b+c)</b>	236.060971
<b>Total GST (a)</b>	4.1061474
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	18.01253388
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	19.363473921
<b>LABOUR CESS @ 1% (+)</b>	2.77543126201
<b>Grand Total</b>	280.31855746301
<b>Say For Unit 1 (Grand Total/1)</b>	280.31855746301

## Item 13

**Plastering (AR1027):** 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.

Sub-Item of Work

**6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside)**

**a) Specific Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
LR001 : Male mulia	0.12	Per day	462	55.44	0
LR002 : Female mulia	0.05	Per day	462	23.1	0
LR025 : Mason	0.14	Per day	562	78.68	0
BRM340 : Cement	0.0372	1 Qntl.	530.51	19.734972	3.55229496
BRM028 : Screened and washed sharp sand for mortar	0.0075	1 Cum	76.88	0.5766	0

**b) Carriage Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0372	1 Qntl.	24.787	0.9220764	0
BRM028 : Screened and washed sharp sand for mortar	0.0075	1 Cum	445.27	3.339525	0

**c) Royalty Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0372	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.0075	1 Cum	110.25	0.826875	0

<b>Total Amount (a+b+c)</b>				182.6200484	
<b>Total GST (a)</b>				3.55229496	
<b>OVERHEAD CHARGES @ 7.5% (+)</b>				13.962925752	
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>				15.0101451834	
<b>LABOUR CESS @ 1% (+)</b>				2.151454142954	
<b>Grand Total</b>				217.29686843835	
<b>Say For Unit 1 (Grand Total/1)</b>				217.29686843835	

**Item 14**

**Other Building Items. (AR1901A):** Supplying, fitting and fixing Vitrified Tile 600mmx600mm Plain (Ivory) of approved make conforming to IS :13755 with application of polymer modified quick set cement based water resistant adhesive conforming to IS :15477 of 3mm thick bed and filling joints with white cement of approved quality including cost of all materials, labour ,T&P,etc. required for the work all complete as per direction of Engineer-in-Charge(for repair work only)

Sub-Item of Work

**Supplying, fitting and fixing vitrified tile in floors of size 600mm x 600mm of approved make conforming to IS :13755 with application of polymer modified quick set cement based water resistant adhesive conforming to IS :15477 of 3mm thick bed and fillin**

**a) Specific Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
LR001 : Male mulia	2.16	Per day	462	997.92	0
LR044 : Mason	2.16	Per day	612	1321.92	0
BRM174 : White Cement.	0.076	1Qntl	2000	152	0
BRM256 : Adhesive (I.S.I.)	54	1 Kg	217.4	11739.6	0
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	650	6500	0

#### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM174 : White Cement.	0.076	1Qntl	24.787	1.883812	0
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	19.0921673	190.921673	0

#### c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM174 : White Cement.	0.076	1Qntl	0	0	0
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	0	0	0

<b>Total Amount (a+b+c)</b>	20904.245485
<b>Total GST (a)</b>	0
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	1567.818411375
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	1685.4047922281
<b>LABOUR CESS @ 1% (+)</b>	241.57468688603
<b>Grand Total</b>	24399.043375489
<b>Say For Unit 1 (Grand Total/10)</b>	2439.9043375489

#### Item 15

**Flooring (AR0817aa):** Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.

Sub-Item of Work  
**First floor**

#### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
------------	----------	------	------	--------	-----

<b>BRM131</b> : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	650	6500	0
<b>BRMMR0027</b> : Wax Polish	10	1 Sqm	8.5	85	0
<b>LR044</b> : Mason	3.4125	Per day	612	2088.45	0
<b>LR001</b> : Male mulia	3.4125	Per day	462	1576.575	0
<b>LR008</b> : Sangi mulia	7.98	Per day	512	4085.76	0
<b>BRM340</b> : Cement	1.375	1 Qntl.	530.51	729.45125	131.301225
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.15	1 Cum	76.88	11.532	0

**b) Carriage Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM131</b> : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	19.0921673	190.921673	0
<b>BRM340</b> : Cement	1.375	1 Qntl.	24.787	34.082125	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.15	1 Cum	445.27	66.7905	0

**c) Royalty Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM131</b> : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	0	0	0
<b>BRM340</b> : Cement	1.375	1 Qntl.	0	0	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.15	1 Cum	110.25	16.5375	0

<b>Total Amount (a+b+c)</b>	15385.100048
<b>Total GST (a)</b>	131.301225
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	1163.730095475
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	1251.0098526356
<b>LABOUR CESS @ 1% (+)</b>	179.31141221111
<b>Grand Total</b>	18110.452633322
<b>Say For Unit 1 (Grand Total/10)</b>	1811.0452633322

**Item 16**

**Painting (AR0922):** Finishing wall two coats with distemper of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)

Sub-Item of Work

**Finishing wall two coats with distemper of approved shades on new work (Inside)**

**a) Specific Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
LR048 : Painter/ Polisher	0.52	Per day	612	318.24	0
BRM142 : Distemper	2.5	1 Kg.	70.1	175.25	0
LR001 : Male mulia	0.62	Per day	462	286.44	0

**b) Carriage Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
BRM142 : Distemper	2.5	1 Kg.	0.5689	1.42225	0

**c) Royalty Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
BRM142 : Distemper	2.5	1 Kg.	0	0	0

<b>Total Amount (a+b+c)</b>	781.35225				
<b>Total GST (a)</b>	0				
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	58.60141875				
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	62.99652515625				
<b>LABOUR CESS @ 1% (+)</b>	9.0295019390625				
<b>Grand Total</b>	911.97969584531				
<b>Say For Unit 1 (Grand Total/10)</b>	91.197969584531				

**Item 17**

**Painting (AR0901c):** Priming one coat with inner surface primer of approved quality oil-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.

Sub-Item of Work

**Priming one coat with inner surface primer of approved quality oil-bound primer over plastering surfaces (Inner surface)**

**a) Specific Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
BRM252 : Wall cement primer (I.S.I.) Oil bound	0.7812	1 Ltr	125.5	98.0406	0
LR048 : Painter/ Polisher	0.5	Per day	612	306	0
LR001 : Male mulia	0.5	Per day	462	231	0

**b) Carriage Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
------------	----------	------	------	--------	-----

BRM252 : Wall cement primer (I.S.I.) Oil bound	0.7812	1 Ltr	0.5689	0.44442468	0
--	--------	-------	--------	------------	---

**c) Royalty Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
BRM252 : Wall cement primer (I.S.I.) Oil bound	0.7812	1 Ltr	0	0	0

<b>Total Amount (a+b+c)</b>	635.48502468				
<b>Total GST (a)</b>	0				
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	47.661376851				
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	51.235980114825				
<b>LABOUR CESS @ 1% (+)</b>	7.3438238164583				
<b>Grand Total</b>	741.72620546228				
<b>Say For Unit 1 (Grand Total/9.3)</b>	79.755505963686				

**Item 18**

**Iron Work (AR1704):** Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in-charge.

Sub-Item of Work  
**Iron Doors and windows fixing**

**a) Specific Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	0.508	1 Qntl.	6379.83	3240.95364	583.3716552
LR001 : Male mulia	3.25	Per day	462	1501.5	0
LR011 : Helper to carpenter or Blacksmith/ Painter/ Blaster/Plumber/ Electrician/ Fitter/Welder	1	Per day	512	512	0
LR028 : Fitter	1	Per day	562	562	0
LR047 : Fitter	1	Per day	612	612	0
LR026 : Black smith	1	Per day	562	562	0
LR046 : Blacksmith	0.75	Per day	612	459	0

**b) Carriage Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	0.508	1 Qntl.	56.89	28.90012	0

**c) Royalty Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
------------	----------	------	------	--------	-----

BRM341 : Steel	0.508	1 Qntl.	0	0	0
----------------	-------	---------	---	---	---

<b>Total Amount (a+b+c)</b>	7478.35376
<b>Total GST (a)</b>	583.3716552
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	604.62940614
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	649.9766116005
<b>LABOUR CESS @ 1% (+)</b>	93.163314329405
<b>Grand Total</b>	9409.4947472699
<b>Say For Unit 1 (Grand Total/0.508)</b>	18522.627455256

### Item 19

**Painting (AR0918ca):** Finishing wall surface two coats with weather coat with one coat oilbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)

Sub-Item of Work

**Finishing wall two coats with weather coat with one coat oilbound Primer**

#### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>Combine :: Painting (AR0918f)</b>					
BRM255 : Weather Coat (I.S.I.)	0.125	1 Ltr	194.79	24.34875	0
LR001 : Male mulia	0.064	Per day	462	29.568	0
LR048 : Painter/ Polisher	0.054	Per day	612	33.048	0
<b>Combine :: Painting (AR0901ci)</b>					
BRM252 : Wall cement primer (I.S.I.) Oil bound	0.084	1 Ltr	125.5	10.542	0
LR048 : Painter/ Polisher	0.053763440860215	Per day	612	32.903225806452	0
LR001 : Male mulia	0.053763440860215	Per day	462	24.838709677419	0

#### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	0.125	1 Ltr	0.5689	0.0711125	0
BRM252 : Wall cement primer (I.S.I.) Oil bound	0.084	1 Ltr	0.5689	0.0477876	0

#### c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	0.125	1 Ltr	0	0	0
BRM252 : Wall cement primer (I.S.I.) Oil bound	0.084	1 Ltr	0	0	0

<b>Total Amount (a+b+c)</b>	155.36758558387
<b>Total GST (a)</b>	0
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	11.65256891879

<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	12.5265115877
<b>LABOUR CESS @ 1% (+)</b>	1.7954666609036
<b>Grand Total</b>	181.34213275126
<b>Say For Unit 1 (Grand Total/1)</b>	181.34213275126

**Item 20**

**Other Building Items. (AR1902):** Finishing surface of walls with cement based wall putty (water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes,labour,T&P,etc.complete. and as per the direction of Engineer in Charge.

Sub-Item of Work  
**cement based wall putty (water based)**

**a) Specific Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRMMR0038 : Cement based putty</b>	8	kg	30	240	0
<b>LR001 : Male mulia</b>	0.57	Per day	462	263.34	0
<b>LR025 : Mason</b>	0.5	Per day	562	281	0

<b>Total Amount (a+b+c)</b>	784.34
<b>Total GST (a)</b>	0
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	58.8255
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	63.2374125
<b>LABOUR CESS @ 1% (+)</b>	9.064029125
<b>Grand Total</b>	915.466941625
<b>Say For Unit 1 (Grand Total/10)</b>	91.5466941625

**SMITA NATH**  
**JE**  
**Lathikata Block**

**LASA MARANDI**  
**AEE**  
**Lathikata Block**

**BDO LATHIKATA**  
**BDO**  
**Lathikata Block**