

Analysis

OD/346/3305/116241/393323/00068348 : Const of AWC Boundary wall Asoknal
Block : Nilgiri, Gram Panchayat : K.C.Pur
Created By: Bikram Kishore Parida

Item 1

Plastering (AR1004): 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.

Sub-Item of Work

12mm thick cement plaster (1:6) over Brick work in inside

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.05	Per day	462	23.1	0
LR001 : Male mulia	0.07	Per day	462	32.34	0
LR025 : Mason	0.14	Per day	562	78.68	0
BRM340 : Cement	0.0358	1 Qntl.	545.68	19.535344	3.51636192
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	76.88	1.1532	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0358	1 Qntl.	43.811	1.5684338	0
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	614.53	9.21795	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0358	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	442.25	6.63375	0

Total Amount (a+b+c)

172.2286778

Total GST (a)

3.51636192

OVERHEAD CHARGES @ 7.5% (+)

13.180877979

CONTRACTOR PROFIT @ 7.5% (+)

14.169443827425

LABOUR CESS @ 1% (+)

2.0309536152643

Grand Total

205.12631514169

Say For Unit 1 (Grand Total/1)

205.12631514169

Item 2

R.C.C. Work (AR0410c): Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc

Sub-Item of Work

R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	58374.79	1558.606893	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	1.26	1Mtr.	30.81	38.8206	0
LR008 : Sangi mulia	0.5	Per day	512	256	0
LR027 : Carpenter	0.5	Per day	562	281	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	198.296	5.2945032	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	198.296	1.21753744	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	0	0	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	0	0	0

Total Amount (a+b+c)				2140.93953364	
Total GST (a)					0
OVERHEAD CHARGES @ 7.5% (+)				160.570465023	
CONTRACTOR PROFIT @ 7.5% (+)				172.61324989972	
LABOUR CESS @ 1% (+)				24.741232485627	
Grand Total				2498.8644810484	
Say For Unit 1 (Grand Total/10)				249.88644810484	

Item 3

Masonry Brick Work (AR0603bi): Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work

Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.14	Per day	462	64.68	0
BRMMR0025 : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK	1	1 Cum	33	33	0
LR001 : Male mulia	2.82	Per day	462	1302.84	0
LR025 : Mason	1.05	Per day	562	590.1	0
LR044 : Mason	0.35	Per day	612	214.2	0
BRM340 : Cement	0.672	1 Qntl.	545.68	366.69696	66.0054528
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	76.88	21.5264	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	350	1000 Nos	5.14255	1799.8925	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.672	1 Qntl.	43.811	29.440992	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	614.53	172.0684	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	350	1000 Nos	1.89485	663.1975	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.672	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	442.25	123.83	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	350	1000 Nos	0	0	0

Total Amount (a+b+c)	5381.472752
Total GST (a)	66.0054528
OVERHEAD CHARGES @ 7.5% (+)	408.56086536
CONTRACTOR PROFIT @ 7.5% (+)	439.202930262
LABOUR CESS @ 1% (+)	62.95242000422
Grand Total	6358.1944204262
Say For Unit 1 (Grand Total/1)	6358.1944204262

Item 4

Painting (AR0918fk): Finishing wall with two coat weather coat paint of approved shade in the outer surface of old work to give an even shade including all costs of labour, Paint and Brushes required for the work, etc. complete and as per direction of Engineer-in-charge(Outside)(For repair and maintenance).

Sub-Item of Work

Finishing wall with two coat weather coat paint of approved shade in the outer surface of old work(Outside)(For repair and maintenance) .

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	1.25	1 Ltr	194.79	243.4875	0
LR001 : Male mulia	0.6528	Per day	462	301.5936	0
LR048 : Painter/ Polisher	0.5508	Per day	612	337.0896	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	1.25	1 Ltr	0.43811	0.5476375	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	1.25	1 Ltr	0	0	0

Total Amount (a+b+c)

882.7183375

Total GST (a)

0

OVERHEAD CHARGES @ 7.5% (+)

66.2038753125

CONTRACTOR PROFIT @ 7.5% (+)

71.169165960938

LABOUR CESS @ 1% (+)

10.200913787734

Grand Total

1030.2922925612

Say For Unit 1 (Grand Total/10)

103.02922925612

Item 5

Plastering (AR1014): 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.

Sub-Item of Work

16mm thick cement Plaster in CM (1:6) over brick work in inside.

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.11	Per day	462	50.82	0
LR001 : Male mulia	0.13	Per day	462	60.06	0
LR025 : Mason	0.16	Per day	562	89.92	0
BRM340 : Cement	0.043	1 Qntl.	545.68	23.46424	4.2235632
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	76.88	1.38384	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.043	1 Qntl.	43.811	1.883873	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	614.53	11.06154	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.043	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	442.25	7.9605	0

Total Amount (a+b+c)	246.553993				
Total GST (a)	4.2235632				
OVERHEAD CHARGES @ 7.5% (+)	18.808316715				
CONTRACTOR PROFIT @ 7.5% (+)	20.218940468625				
LABOUR CESS @ 1% (+)	2.8980481338362				
Grand Total	292.70286151746				
Say For Unit 1 (Grand Total/1)	292.70286151746				

Item 6

R.C.C. Work (AR0410d): Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. beams, column, grider and bressmer, etc. Data for 4.2sqm

Sub-Item of Work

Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	2.32	1Mtr	51.87	120.3384	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0218	1Cum.	58374.79	1272.570422	0
LR008 : Sangi mulia	2.75	Per day	512	1408	0
LR027 : Carpenter	2.75	Per day	562	1545.5	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.0238	1Mtr	198.296	4.7194448	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0218	1Cum.	198.296	4.3228528	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.0238	1Mtr	0	0	0

BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0218	1Cum.	0	0	0
--	--------	-------	---	---	---

Total Amount (a+b+c)	4355.4511196
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	326.65883397
CONTRACTOR PROFIT @ 7.5% (+)	351.15824651775
LABOUR CESS @ 1% (+)	50.332682000878
Grand Total	5083.6008820886
Say For Unit 1 (Grand Total/4.2)	1210.3811624021

Item 7

R.C.C. Work (AR0409): Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.

Sub-Item of Work

Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR001 : Male mulia	8	Per day	462	3696	0
LR046 : Blacksmith	3	Per day	612	1836	0
LR010 : Mate	0.44	Per day	512	225.28	0
BRM162 : Binding Wire.	8	1 Kg.	90	720	0
BRM341 : Steel	10.5	1 Qntl.	6354.22	66719.31	12009.4758

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	10.5	1 Qntl.	43.811	460.0155	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	10.5	1 Qntl.	0	0	0

Total Amount (a+b+c)	73656.6055
Total GST (a)	12009.4758
OVERHEAD CHARGES @ 7.5% (+)	6424.9560975
CONTRACTOR PROFIT @ 7.5% (+)	6906.8278048125
LABOUR CESS @ 1% (+)	989.97865202313
Grand Total	99987.843854336
Say For Unit 1 (Grand Total/10)	9998.7843854336

Item 8

R.C.C. Work (AR0404Aa): Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)

Sub-Item of Work

Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
Combine :: R.C.C. Work (AR0404A)					
PM096 : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0
PM083 : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0
LR001 : Male mulia	1.3333	Per day	462	615.9846	0
LR025 : Mason	0.1	Per day	562	56.2	0
LR010 : Mate	0.0573	Per day	512	29.3376	0
BRM340 : Cement	3.4733	1 Qntl.	545.68	1895.310344	341.15586192
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1418.67	510.7212	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1382.29	746.4366	0
Combine :: R.C.C. Work (AR0410c)					
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	1Cum.	58374.79	233.79103395	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.189	1Mtr.	30.81	5.82309	0
LR008 : Sangi mulia	0.075	Per day	512	38.4	0
LR027 : Carpenter	0.075	Per day	562	42.15	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	43.811	152.1687463	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	614.53	276.5385	0

BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	917.11	330.1596	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	917.11	495.2394	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	1Cum.	198.296	0.79417548	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.000921	1Mtr.	198.296	0.182630616	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	442.25	199.0125	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	522.5	188.1	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	522.5	282.15	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	1Cum.	0	0	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.000921	1Mtr.	0	0	0

Total Amount (a+b+c)	6504.916020346
Total GST (a)	341.15586192
OVERHEAD CHARGES @ 7.5% (+)	513.45539116995
CONTRACTOR PROFIT @ 7.5% (+)	551.9645455077
LABOUR CESS @ 1% (+)	79.114918189436
Grand Total	7990.6067371331
Say For Unit 1 (Grand Total/1)	7990.6067371331

Item 9

Pile Foundation (AR1501ca): Single under reamed pile foundation 250 mm dia and 3.0 metre long with RCC M-20 using 12mm size black hard granite (Crusher broken) stone chips including cost of boring but excluding cost of M.S./Tor steel and labour charges for cutting, bending and binding of steel including cost, convenience, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. (250mm dia and 3.0 meter long)

Sub-Item of Work

Single under reamed pile foundation 250 mm dia and 3.0 metre long with RCC M20 using 12mm size black hard granite (Crusher broken) stone chips

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM178 : Bentonite powder	0.588	1Qntl	337.87	198.66756	0
BRM342 : Tripod	0.235	Per day	450	105.75	0

LR063 : Winch operator	0.235	Per day	612	143.82	0
LR062 : Boring Mistry	0.94	Per day	612	575.28	0
PM096 : Generator 33KVA Generation of Electric Energy 50KVA	0.085	per hour	700	59.5	0
PM083 : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.085	per hour	229.55	19.51175	0
LR001 : Male mulia	0.283	Per day	462	130.746	0
LR025 : Mason	0.021	Per day	562	11.802	0
LR010 : Mate	0.013	Per day	512	6.656	0
BRM340 : Cement	0.805	1 Qntl.	545.68	439.2724	79.069032
BRM028 : Screened and washed sharp sand for mortar	0.096	1 Cum	76.88	7.38048	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.19	1 Cum.	1396.62	265.3578	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.805	1 Qntl.	43.811	35.267855	0
BRM028 : Screened and washed sharp sand for mortar	0.096	1 Cum	614.53	58.99488	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.19	1 Cum.	917.11	174.2509	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.805	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.096	1 Cum	442.25	42.456	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.19	1 Cum.	522.5	99.275	0

Total Amount (a+b+c)	2373.988625
Total GST (a)	79.069032
OVERHEAD CHARGES @ 7.5% (+)	183.979324275
CONTRACTOR PROFIT @ 7.5% (+)	197.77777359563

LABOUR CESS @ 1% (+)	28.348147548706
Grand Total	2863.1629024193
Say For Unit 1 (Grand Total/1)	2863.1629024193

BAIDYANATH SINGH
JE
Nilgiri Block

Sarat kumar Upadhyay
AEE
Nilgiri Block

Bikram Kishore Parida
BDO
Nilgiri Block