

## Analysis

**OD/361/3452/119449/386026/00067337 : CONST. OF MAJHIDHAN MANDAP AT UPARSAHI  
DUNGURI BALI TALAKUSUMITA  
Block : Kendujhar Sadar, Gram Panchayat : Baradapal  
Created By:Binod Chandra Panda**

<b>Item 1</b>
<b>Earth Work (AR0102aa):</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge
Sub-Item of Work <b>Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift</b>

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	25.8	Per day	462	11919.6	0
LR001 : Male mulia	25.8	Per day	462	11919.6	0
<b>Total Amount (a+b+c)</b>				23839.2	
<b>Total GST (a)</b>					0
<b>OVERHEAD CHARGES @ 7.5% (+)</b>					1787.94
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>					1922.0355
<b>LABOUR CESS @ 1% (+)</b>					275.491755
<b>Grand Total</b>					27824.667255
<b>Say For Unit 1 (Grand Total/100)</b>					278.24667255

<b>Item 2</b>
<b>Earth Work (AR0115):</b> Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work <b>Filling foundation and plinth with sand well watered and rammed</b>

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	55	5500	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	880.31	88031	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	50.25	5025	0

Total Amount (a+b+c)	104266.32				
Total GST (a)	0				
OVERHEAD CHARGES @ 7.5% (+)	7819.974				
CONTRACTOR PROFIT @ 7.5% (+)	8406.47205				
LABOUR CESS @ 1% (+)	1204.9276605				
Grand Total	121697.6937105				
Say For Unit 1 (Grand Total/100)	1216.976937105				

### Item 3

**Concrete (AR0303):** Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

**Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal**

### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR025 : Mason	0.18	Per day	562	101.16	0
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	2.5	Per day	462	1155	0
BRM340 : Cement	2.29	1 Qntl.	554.16	1269.0264	228.424752
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	65	31.2	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	995.25	955.44	0

### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	48.567	111.21843	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	880.31	422.5488	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	666.61	639.9456	0

### c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	50.25	24.12	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	424.5	407.52	0

<b>Total Amount (a+b+c)</b>	5763.97923
<b>Total GST (a)</b>	228.424752
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	449.43029865
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	483.13757104875
<b>LABOUR CESS @ 1% (+)</b>	69.249718516987
<b>Grand Total</b>	6994.2215702157
<b>Say For Unit 1 (Grand Total/1)</b>	6994.2215702157

#### Item 4

**Masonry Brick Work (AR0603b):** Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm<sup>2</sup> with dimensional tolerance  $\pm 8$  percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work

**Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in foundation and plinth**

#### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.14	Per day	462	64.68	0
LR001 : Male mulia	2.82	Per day	462	1302.84	0
LR025 : Mason	1.05	Per day	562	590.1	0
LR044 : Mason	0.35	Per day	612	214.2	0
BRM340 : Cement	0.672	1 Qntl.	554.16	372.39552	67.0311936
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	65	18.2	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm <sup>2</sup> with dimensional tolerance $\pm 2$ %	350	1000 Nos	5.14255	1799.8925	0

#### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.672	1 Qntl.	48.567	32.637024	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	880.31	246.4868	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm <sup>2</sup> with dimensional tolerance $\pm 2$ %	350	1000 Nos	1.30585	457.0475	0

#### c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.672	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	50.25	14.07	0

<b>BRM005</b> : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	350	1000 Nos	0	0	0
---	-----	----------	---	---	---

<b>Total Amount (a+b+c)</b>	5112.549344
<b>Total GST (a)</b>	67.0311936
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	388.46854032
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	417.603680844
<b>LABOUR CESS @ 1% (+)</b>	59.85652758764
<b>Grand Total</b>	6045.5092863516
<b>Say For Unit 1 (Grand Total/1)</b>	6045.5092863516

### Item 5

**R.C.C. Work (AR0404Aa):** Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)

Sub-Item of Work

**Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips**

#### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>Combine :: R.C.C. Work (AR0404A)</b>					
<b>PM096</b> : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0
<b>PM083</b> : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0
<b>LR001</b> : Male mulia	1.3333	Per day	462	615.9846	0
<b>LR025</b> : Mason	0.1	Per day	562	56.2	0
<b>LR010</b> : Mate	0.0573	Per day	512	29.3376	0
<b>BRM340</b> : Cement	3.4733	1 Qntl.	554.16	1924.763928	346.45750704
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	65	29.25	0
<b>BRM060</b> : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1418.67	510.7212	0
<b>BRM052</b> : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1335	720.9	0
<b>Combine :: R.C.C. Work (AR0410c)</b>					
<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	1Cum.	58374.79	233.79103395	0

<b>BRM092</b> : Non-sal bullahs 75mm. mean dia of any length.	0.189	1Mtr.	30.81	5.82309	0
<b>LR008</b> : Sangi mulia	0.075	Per day	512	38.4	0
<b>LR027</b> : Carpenter	0.075	Per day	562	42.15	0

**b) Carriage Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	3.4733	1 Qntl.	48.567	168.6877611	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	880.31	396.1395	0
<b>BRM060</b> : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	666.61	239.9796	0
<b>BRM052</b> : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	666.61	359.9694	0
<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	1Cum.	198.296	0.79417548	0
<b>BRM092</b> : Non-sal bullahs 75mm. mean dia of any length.	0.000921	1Mtr.	198.296	0.182630616	0

**c) Royalty Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	3.4733	1 Qntl.	0	0	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	50.25	22.6125	0
<b>BRM060</b> : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	424.5	152.82	0
<b>BRM052</b> : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	424.5	229.23	0
<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	1Cum.	0	0	0
<b>BRM092</b> : Non-sal bullahs 75mm. mean dia of any length.	0.000921	1Mtr.	0	0	0

<b>Total Amount (a+b+c)</b>	6149.557019146
<b>Total GST (a)</b>	346.45750704
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	487.20108946395
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	523.74117117375
<b>LABOUR CESS @ 1% (+)</b>	75.069567868237
<b>Grand Total</b>	7582.0263546919
<b>Say For Unit 1 (Grand Total/1)</b>	7582.0263546919

**Item 6**

**R.C.C. Work (AR0404Ab):** Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Plinth band)

Sub-Item of Work

**Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips**

**a) Specific Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>Combine :: R.C.C. Work (AR0404A)</b>					
<b>PM096</b> : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0
<b>PM083</b> : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0
<b>LR001</b> : Male mulia	1.3333	Per day	462	615.9846	0
<b>LR025</b> : Mason	0.1	Per day	562	56.2	0
<b>LR010</b> : Mate	0.0573	Per day	512	29.3376	0
<b>BRM340</b> : Cement	3.4733	1 Qntl.	554.16	1924.763928	346.45750704
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	65	29.25	0
<b>BRM060</b> : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1418.67	510.7212	0
<b>BRM052</b> : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1335	720.9	0
<b>Combine :: R.C.C. Work (AR0410c)</b>					
<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.01335	1Cum.	58374.79	779.3034465	0
<b>BRM092</b> : Non-sal bullahs 75mm. mean dia of any length.	0.63	1Mtr.	30.81	19.4103	0
<b>LR008</b> : Sangi mulia	0.25	Per day	512	128	0
<b>LR027</b> : Carpenter	0.25	Per day	562	140.5	0

**b) Carriage Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	3.4733	1 Qntl.	48.567	168.6877611	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	880.31	396.1395	0
<b>BRM060</b> : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	666.61	239.9796	0

<b>BRM052</b> : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	666.61	359.9694	0
<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.01335	1Cum.	198.296	2.6472516	0
<b>BRM092</b> : Non-sal bullahs 75mm. mean dia of any length.	0.00307	1Mtr.	198.296	0.60876872	0

**c) Royalty Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	3.4733	1 Qntl.	0	0	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	50.25	22.6125	0
<b>BRM060</b> : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	424.5	152.82	0
<b>BRM052</b> : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	424.5	229.23	0
<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.01335	1Cum.	0	0	0
<b>BRM092</b> : Non-sal bullahs 75mm. mean dia of any length.	0.00307	1Mtr.	0	0	0

<b>Total Amount (a+b+c)</b>	6898.88585592
<b>Total GST (a)</b>	346.45750704
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	543.400752222
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	584.15580863865
<b>LABOUR CESS @ 1% (+)</b>	83.728999238206
<b>Grand Total</b>	8456.6289230589
<b>Say For Unit 1 (Grand Total/1)</b>	8456.6289230589

**Item 7**

**R.C.C. Work (AR0404Ac):** Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge. (RCC Beams, Column, Girder & Bressmer etc)

Sub-Item of Work

**Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips**

**a) Specific Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>Combine :: R.C.C. Work (AR0404A)</b>					
<b>PM096</b> : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0
<b>PM083</b> : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0

<b>LR001</b> : Male mulia	1.3333	Per day	462	615.9846	0
<b>LR025</b> : Mason	0.1	Per day	562	56.2	0
<b>LR010</b> : Mate	0.0573	Per day	512	29.3376	0
<b>BRM340</b> : Cement	3.4733	1 Qntl.	554.16	1924.763928	346.45750704
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	65	29.25	0
<b>BRM060</b> : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1418.67	510.7212	0
<b>BRM052</b> : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1335	720.9	0
<b>Combine :: R.C.C. Work (AR0410d)</b>					
<b>BRM084</b> : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	4.4196	1Mtr	51.87	229.244652	0
<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.041529	1Cum.	58374.79	2424.24665391	0
<b>LR008</b> : Sangi mulia	5.23875	Per day	512	2682.24	0
<b>LR027</b> : Carpenter	5.23875	Per day	562	2944.1775	0

#### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	3.4733	1 Qntl.	48.567	168.6877611	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	880.31	396.1395	0
<b>BRM060</b> : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	666.61	239.9796	0
<b>BRM052</b> : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	666.61	359.9694	0
<b>BRM084</b> : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.045339	1Mtr	198.296	8.990542344	0
<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.041529	1Cum.	198.296	8.235034584	0

#### c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	3.4733	1 Qntl.	0	0	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	50.25	22.6125	0
<b>BRM060</b> : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	424.5	152.82	0

<b>BRM052</b> : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	424.5	229.23	0
<b>BRM084</b> : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.045339	1Mtr	0	0	0
<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.041529	1Cum.	0	0	0

<b>Total Amount (a+b+c)</b>	14125.550471938
<b>Total GST (a)</b>	346.45750704
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	1085.4005984233
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	1166.8056433051
<b>LABOUR CESS @ 1% (+)</b>	167.24214220706
<b>Grand Total</b>	16891.456362914
<b>Say For Unit 1 (Grand Total/1)</b>	16891.456362914

<b>Item 8</b>
<b>R.C.C. Work (AR0404Ag):</b> Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Roof slab, landing, balcony, sun shade)
Sub-Item of Work <b>Reinforced cement concrete work of M-20 grade with 20mm &amp; down grade size black hard crusher broken granite chips</b>

<b>a) Specific Rate Details</b>					
<b>Particular</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate</b>	<b>Amount</b>	<b>GST</b>
<b>Combine :: R.C.C. Work (AR0404A)</b>					
<b>PM096</b> : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0
<b>PM083</b> : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0
<b>LR001</b> : Male mulia	1.3333	Per day	462	615.9846	0
<b>LR025</b> : Mason	0.1	Per day	562	56.2	0
<b>LR010</b> : Mate	0.0573	Per day	512	29.3376	0
<b>BRM340</b> : Cement	3.4733	1 Qntl.	554.16	1924.763928	346.45750704
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	65	29.25	0
<b>BRM060</b> : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1418.67	510.7212	0
<b>BRM052</b> : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1335	720.9	0

Combine :: R.C.C. Work (AR0410a)					
<b>BRM084</b> : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	6.2216	1Mtr	51.87	322.714392	0
<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0502172	1Cum.	58374.79	2931.418504388	0
<b>LR008</b> : Sangi mulia	3.05525	Per day	512	1564.288	0
<b>LR027</b> : Carpenter	3.05525	Per day	562	1717.0505	0

b) Carriage Rate Details						
Particular	Quantity	Unit	Rate	Amount	GST	
<b>BRM340</b> : Cement	3.4733	1 Qntl.	48.567	168.6877611	0	
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	880.31	396.1395	0	
<b>BRM060</b> : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	666.61	239.9796	0	
<b>BRM052</b> : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	666.61	359.9694	0	
<b>BRM084</b> : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.076659	1Mtr	198.296	15.201173064	0	
<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0502172	1Cum.	198.296	9.9578698912	0	

c) Royalty Rate Details						
Particular	Quantity	Unit	Rate	Amount	GST	
<b>BRM340</b> : Cement	3.4733	1 Qntl.	0	0	0	
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	1 Cum	50.25	22.6125	0	
<b>BRM060</b> : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	424.5	152.82	0	
<b>BRM052</b> : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	424.5	229.23	0	
<b>BRM084</b> : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.076659	1Mtr	0	0	0	
<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0502172	1Cum.	0	0	0	

<b>Total Amount (a+b+c)</b>	12389.046528443
<b>Total GST (a)</b>	346.45750704
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	955.16280266124
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	1026.8000128608
<b>LABOUR CESS @ 1% (+)</b>	147.17466851005
<b>Grand Total</b>	14864.641519515
<b>Say For Unit 1 (Grand Total/1)</b>	14864.641519515

**Item 9**

**R.C.C. Work (AR0409):** Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.

Sub-Item of Work

**Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position**

**a) Specific Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
LR001 : Male mulia	8	Per day	462	3696	0
LR046 : Blacksmith	3	Per day	612	1836	0
LR010 : Mate	0.44	Per day	512	225.28	0
BRM162 : Binding Wire.	8	1 Kg.	90.1	720.8	0
BRM341 : Steel	10.5	1 Qntl.	6841.58	71836.59	12930.5862

**b) Carriage Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	10.5	1 Qntl.	48.567	509.9535	0

**c) Royalty Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	10.5	1 Qntl.	0	0	0

<b>Total Amount (a+b+c)</b>					78824.6235
<b>Total GST (a)</b>					12930.5862
<b>OVERHEAD CHARGES @ 7.5% (+)</b>					6881.6407275
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>					7397.7637820625
<b>LABOUR CESS @ 1% (+)</b>					1060.3461420956
<b>Grand Total</b>					107094.96035166
<b>Say For Unit 1 (Grand Total/10)</b>					10709.496035166

**Item 10**

**Painting (AR0901d):** Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.

Sub-Item of Work

**Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface)**

**a) Specific Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
------------	----------	------	------	--------	-----

<b>BRM253</b> : Wall cement primer (I.S.I.) Water bound	0.7812	1 Ltr	159.03	124.234236	0
<b>LR048</b> : Painter/ Polisher	0.5	Per day	612	306	0
<b>LR001</b> : Male mulia	0.5	Per day	462	231	0

**b) Carriage Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM253</b> : Wall cement primer (I.S.I.) Water bound	0.7812	1 Ltr	0.48567	0.379405404	0

**c) Royalty Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM253</b> : Wall cement primer (I.S.I.) Water bound	0.7812	1 Ltr	0	0	0

<b>Total Amount (a+b+c)</b>	661.613641404
<b>Total GST (a)</b>	0
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	49.6210231053
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	53.342599838197
<b>LABOUR CESS @ 1% (+)</b>	7.645772643475
<b>Grand Total</b>	772.22303699097
<b>Say For Unit 1 (Grand Total/9.3)</b>	83.03473516032

**Item 11**

**Painting (AR0920):** Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)

Sub-Item of Work

**Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside)**

**a) Specific Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM140</b> : Plastic Emulsion paint	1.25	1 Litre	243	303.75	0
<b>LR048</b> : Painter/ Polisher	0.54	Per day	612	330.48	0
<b>LR001</b> : Male mulia	0.64	Per day	462	295.68	0

**b) Carriage Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM140</b> : Plastic Emulsion paint	1.25	1 Litre	0.48567	0.6070875	0

**c) Royalty Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM140</b> : Plastic Emulsion paint	1.25	1 Litre	0	0	0

<b>Total Amount (a+b+c)</b>	930.5170875
-----------------------------	-------------

<b>Total GST (a)</b>	0
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	69.7887815625
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	75.022940179688
<b>LABOUR CESS @ 1% (+)</b>	10.753288092422
<b>Grand Total</b>	1086.0820973346
<b>Say For Unit 1 (Grand Total/10)</b>	108.60820973346

## Item 12

**Other Building Items. (AR1901B):** Supplying, fitting & fixing Vitrified Tile 600mmx600mm Plain Ivory in floors of size 600mm x 600 mm of approved make conforming IS:13755 laid on 20 mm thick cement mortar(1:4)and filling joints with white cement of approved quality including cost of all materials, taxes, labour, T&P , etc. required for the work all complete as per direction of Engineer-in-charge(for new work only)

Sub-Item of Work

**Vitrified Tile 600mmx600mm Plain Ivory**

### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM174</b> : White Cement.	0.076	1Qntl	2017.18	153.30568	0
<b>BRM340</b> : Cement	1.074	1 Qntl.	554.16	595.16784	107.1302112
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.21	1 Cum	65	13.65	0
<b>BRM131</b> : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	651.08	6510.8	0
<b>LR001</b> : Male mulia	2.16	Per day	462	997.92	0
<b>LR044</b> : Mason	2.16	Per day	612	1321.92	0

### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM174</b> : White Cement.	0.076	1Qntl	48.567	3.691092	0
<b>BRM340</b> : Cement	1.074	1 Qntl.	48.567	52.160958	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.21	1 Cum	880.31	184.8651	0
<b>BRM131</b> : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	16.1466671	161.466671	0

### c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM174</b> : White Cement.	0.076	1Qntl	0	0	0

<b>BRM340</b> : Cement	1.074	1 Qntl.	0	0	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.21	1 Cum	50.25	10.5525	0
<b>BRM131</b> : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	0	0	0

<b>Total Amount (a+b+c)</b>	10005.499841
<b>Total GST (a)</b>	107.1302112
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	758.447253915
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	815.33079795862
<b>LABOUR CESS @ 1% (+)</b>	116.86408104074
<b>Grand Total</b>	11803.272185114
<b>Say For Unit 1 (Grand Total/10)</b>	1180.3272185114

### Item 13

**Flooring (AR0817aa):** Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.

Sub-Item of Work

**Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3)**

#### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM131</b> : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	651.08	6510.8	0
<b>BRMMR0027</b> : Wax Polish	10	1 Sqm	8.5	85	0
<b>LR044</b> : Mason	3.25	Per day	612	1989	0
<b>LR001</b> : Male mulia	3.25	Per day	462	1501.5	0
<b>LR008</b> : Sangi mulia	7.6	Per day	512	3891.2	0
<b>BRM340</b> : Cement	1.375	1 Qntl.	554.16	761.97	137.1546
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.15	1 Cum	65	9.75	0

#### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
------------	----------	------	------	--------	-----

<b>BRM131</b> : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	16.1466671	161.466671	0
<b>BRM340</b> : Cement	1.375	1 Qntl.	48.567	66.779625	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.15	1 Cum	880.31	132.0465	0

### c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM131</b> : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	0	0	0
<b>BRM340</b> : Cement	1.375	1 Qntl.	0	0	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.15	1 Cum	50.25	7.5375	0

<b>Total Amount (a+b+c)</b>	15117.050296
<b>Total GST (a)</b>	137.1546
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	1144.0653672
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	1229.87026974
<b>LABOUR CESS @ 1% (+)</b>	176.2814053294
<b>Grand Total</b>	17804.421938269
<b>Say For Unit 1 (Grand Total/10)</b>	1780.4421938269

### Item 14

**Plastering (AR1027):** 6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces in inside including chipping with proper level and line, curing for the proper period with cost conveyance, royalty, taxes of all materials, labor, and T & P required for the work, etc comp. and as per the direction of the Engineer-in-charge.

Sub-Item of Work

**6mm thick cement Plaster in CM (1:4) over R.C.C. surfaces including chipping (Inside)**

### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>LR001</b> : Male mulia	0.12	Per day	462	55.44	0
<b>LR002</b> : Female mulia	0.05	Per day	462	23.1	0
<b>LR025</b> : Mason	0.14	Per day	562	78.68	0
<b>BRM340</b> : Cement	0.0372	1 Qntl.	554.16	20.614752	3.71065536
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.0075	1 Cum	65	0.4875	0

### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
------------	----------	------	------	--------	-----

<b>BRM340</b> : Cement	0.0372	1 Qntl.	48.567	1.8066924	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.0075	1 Cum	880.31	6.602325	0

**c) Royalty Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	0.0372	1 Qntl.	0	0	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.0075	1 Cum	50.25	0.376875	0

<b>Total Amount (a+b+c)</b>	187.1081444
<b>Total GST (a)</b>	3.71065536
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	14.311409982
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	15.38476573065
<b>LABOUR CESS @ 1% (+)</b>	2.2051497547265
<b>Grand Total</b>	222.72012522738
<b>Say For Unit 1 (Grand Total/1)</b>	222.72012522738

**Item 15**

**Plastering (AR1017):** 20mm thick cement Plaster in CM (1:4) over stone work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.

Sub-Item of Work

**20mm thick cement Plaster in CM (1:4) over masonry work in inside.**

**a) Specific Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>LR002</b> : Female mulia	0.11	Per day	462	50.82	0
<b>LR001</b> : Male mulia	0.13	Per day	462	60.06	0
<b>LR025</b> : Mason	0.16	Per day	562	89.92	0
<b>BRM340</b> : Cement	0.0744	1 Qntl.	554.16	41.229504	7.42131072
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.021	1 Cum	65	1.365	0

**b) Carriage Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	0.0744	1 Qntl.	48.567	3.6133848	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.021	1 Cum	880.31	18.48651	0

**c) Royalty Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM340</b> : Cement	0.0744	1 Qntl.	0	0	0
<b>BRM028</b> : Screened and washed sharp sand for mortar	0.021	1 Cum	50.25	1.05525	0

<b>Total Amount (a+b+c)</b>	266.5496488
<b>Total GST (a)</b>	7.42131072
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	20.547821964
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	22.0889086113
<b>LABOUR CESS @ 1% (+)</b>	3.166076900953
<b>Grand Total</b>	319.77376699625
<b>Say For Unit 1 (Grand Total/1)</b>	319.77376699625

### Item 16

**Painting (AR0918cb):** Finishing wall two coats with weather coat with one coat waterbound Primer including all costs of labour, Paint, Primer, Brushes and putty required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)

Sub-Item of Work

**Finishing wall two coats with weather coat with one coat waterbound Primer**

#### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>Combine :: Painting (AR0918f)</b>					
<b>BRM255 : Weather Coat (I.S.I.)</b>	0.125	1 Ltr	194.79	24.34875	0
<b>LR001 : Male mulia</b>	0.064	Per day	462	29.568	0
<b>LR048 : Painter/ Polisher</b>	0.054	Per day	612	33.048	0
<b>Combine :: Painting (AR0901di)</b>					
<b>BRM253 : Wall cement primer (I.S.I.) Water bound</b>	0.090322580645161	1 Ltr	159.03	14.364	0
<b>LR048 : Painter/ Polisher</b>	0.053763440860215	Per day	612	32.903225806452	0
<b>LR001 : Male mulia</b>	0.053763440860215	Per day	462	24.838709677419	0

#### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM255 : Weather Coat (I.S.I.)</b>	0.125	1 Ltr	0.48567	0.06070875	0
<b>BRM253 : Wall cement primer (I.S.I.) Water bound</b>	0.090322580645161	1 Ltr	0.48567	0.043866967741935	0

#### c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM255 : Weather Coat (I.S.I.)</b>	0.125	1 Ltr	0	0	0
<b>BRM253 : Wall cement primer (I.S.I.) Water bound</b>	0.090322580645161	1 Ltr	0	0	0

<b>Total Amount (a+b+c)</b>	159.17526120161
<b>Total GST (a)</b>	0
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	11.938144590121
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	12.83350543438

<b>LABOUR CESS @ 1% (+)</b>	1.8394691122611
<b>Grand Total</b>	185.78638033838
<b>Say For Unit 1 (Grand Total/1)</b>	185.78638033838

**Item 17**

**Other Building Items. (AR1911):** Supplying, fitting and fixing of Stainless steel of 304 grade in hand railing using 50mm dia of 2mm thick circular pipe with Balustrade of size 32mm x 32mm x 2mm @ 0.90mtr. C/C and stainless square pipe bracing of size 32mm x 32mm x 2mm in 3 rows in staircase as per approved design and specification, buffing, polishing etc with cost, conveyance, taxes of all materials, labour, T&P etc. required for the complete in all respect. and as per direction of Engineer in Charge

Sub-Item of Work

**Stainless steel of 304 grade in hand railing using 50mm dia of 2mm**

**a) Specific Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
<b>LR011</b> : Helper to carpenter or Blacksmith/ Painter/ Blaster/Plumber/ Electrician/ Fitter/Welder	0.89	Per day	512	455.68	0
<b>LR047</b> : Fitter	0.89	Per day	612	544.68	0
<b>BRMMR0024</b> : Buffing, Polishing etc.	1	L.S.	178.42	178.42	0
<b>BRMMR0023</b> : Fabrication	34.16	kg	10	341.6	0
<b>BRMMR0022</b> : Stainless steel square pipe bracing of size 32mmx32mmx2mm in 3 rows	16.63	kg	256.62	4267.5906	0
<b>BRMMR0021</b> : Balustrade of size 30mmx32mmx2mm	6.12	kg	256.62	1570.5144	0
<b>BRMMR0020</b> : Railing 50mm outer dia of 2mm thick	11.41	kg	240.24	2741.1384	0

<b>Total Amount (a+b+c)</b>	10099.6234
<b>Total GST (a)</b>	0
<b>OVERHEAD CHARGES @ 7.5% (+)</b>	757.471755
<b>CONTRACTOR PROFIT @ 7.5% (+)</b>	814.282136625
<b>LABOUR CESS @ 1% (+)</b>	116.71377291625
<b>Grand Total</b>	11788.091064541
<b>Say For Unit 1 (Grand Total/3.26)</b>	3615.9788541538

**Kandarpa Palei**  
**JE**  
**Kendujhar Sadar Block**

**Sabyasachi Pradhan**  
**AEE**  
**Kendujhar Sadar Block**

**Binod Chandra Panda**  
**BDO**  
**Kendujhar Sadar Block**