

Analysis

**OD/360/3435/119066/396688/00100590 : CONST OF CC ROAD FROM BISOKA MINI BANK TO
KATAKANA PANI TANKI
Block : Derabish, Gram Panchayat : Khamala
Created By:Namita Barik**

Item 1
Earth Work (AR0115): Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work Filling foundation and plinth with sand well watered and rammed

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	64.18	6418	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	341.11	34111	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	145.25	14525	0

Total Amount (a+b+c)	60764.32
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	4557.324
CONTRACTOR PROFIT @ 7.5% (+)	4899.1233
LABOUR CESS @ 1% (+)	702.207673
Grand Total	70922.974973
Say For Unit 1 (Grand Total/100)	709.22974973

Item 2
Concrete (AR0303): Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR025 : Mason	0.18	Per day	562	101.16	0
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	2.5	Per day	462	1155	0
BRM340 : Cement	2.29	1 Qntl.	559.18	1280.5222	230.493996
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	71.81	34.4688	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	934.84	897.4464	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	30.732	70.37628	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	341.11	163.7328	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	861.91	827.4336	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	145.25	69.72	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	444.5	426.72	0

Total Amount (a+b+c)	5673.38008
Total GST (a)	230.493996
OVERHEAD CHARGES @ 7.5% (+)	442.7905557
CONTRACTOR PROFIT @ 7.5% (+)	475.9998473775
LABOUR CESS @ 1% (+)	68.226644790775
Grand Total	6890.8911238683
Say For Unit 1 (Grand Total/1)	6890.8911238683

Item 3
R.C.C. Work (AR0410c): Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc
Sub-Item of Work R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	58374.79	1558.606893	0

BRM092 : Non-sal bullahs 75mm. mean dia of any length.	1.26	1Mtr.	30.81	38.8206	0
LR008 : Sangi mulia	0.5	Per day	512	256	0
LR027 : Carpenter	0.5	Per day	562	281	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	198.296	5.2945032	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	198.296	1.21753744	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	0	0	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	0	0	0

Total Amount (a+b+c)	2140.93953364
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	160.570465023
CONTRACTOR PROFIT @ 7.5% (+)	172.61324989972
LABOUR CESS @ 1% (+)	24.741232485627
Grand Total	2498.8644810484
Say For Unit 1 (Grand Total/10)	249.88644810484

Item 4

Concrete (AR0307): Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaicon and direction of Engineer-in charge.

Sub-Item of Work

Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	3.2	Per day	462	1478.4	0
LR025 : Mason	0.68	Per day	562	382.16	0
BRM340 : Cement	3.23	1 Qntl.	559.18	1806.1514	325.107252

BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	71.81	32.3145	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	1378.22	1240.398	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	30.732	99.26436	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	341.11	153.4995	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	861.91	775.719	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	145.25	65.3625	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	444.5	400.05	0

Total Amount (a+b+c)	7080.11926
Total GST (a)	325.107252
OVERHEAD CHARGES @ 7.5% (+)	555.3919884
CONTRACTOR PROFIT @ 7.5% (+)	597.04638753
LABOUR CESS @ 1% (+)	85.5766488793
Grand Total	8643.2415368093
Say For Unit 1 (Grand Total/1)	8643.2415368093

Item 5

Earth Work (AR0101aa): Earthwork in ordinary soil in foundation and plinth within 50m, initial lead and 1.5m, initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per direction of the Engineer-in-charge per 100 cum

Sub-Item of Work

Earthwork in ordinary soil in foundation and plinth within 50m, initial lead and 1.5m, initial lift

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	19.2	Per day	462	8870.4	0
LR001 : Male mulia	19.2	Per day	462	8870.4	0

Total Amount (a+b+c)	17740.8
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	1330.56
CONTRACTOR PROFIT @ 7.5% (+)	1430.352
LABOUR CESS @ 1% (+)	205.01712
Grand Total	20706.72912
Say For Unit 1 (Grand Total/100)	207.0672912

ABANI KUMAR MOHANTY
JE
Derabish Block

GOURAV SAHOO
AEE
Derabish Block

Namita Barik
BDO
Derabish Block