

Analysis

**OD/346/3299/116081/392724/00109404 : CONSTRUCTION OF CC ROAD FROM RD ROAD
SUDAM JENA HOUSE TO SUSHIL PAL HOUSE
Block : Baleshwar, Gram Panchayat : Parkhi
Created By:Uttam Kumar Jena**

Item 1
Earth Work (AR0115): Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work Filling foundation and plinth with sand well watered and rammed

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	71.94	7194	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	627.55	62755	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	427.25	42725	0

Total Amount (a+b+c)	118384.32
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	8878.824
CONTRACTOR PROFIT @ 7.5% (+)	9544.7358
LABOUR CESS @ 1% (+)	1368.078798
Grand Total	138175.958598
Say For Unit 1 (Grand Total/100)	1381.75958598

Item 2
Concrete (AR0303): Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR025 : Mason	0.18	Per day	562	101.16	0
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	2.5	Per day	462	1155	0
BRM340 : Cement	2.29	1 Qntl.	545.68	1249.6072	224.929296
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	76.88	36.9024	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	995.25	955.44	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	24.787	56.76223	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	627.55	301.224	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	1202.31	1154.2176	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	427.25	205.08	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	522.5	501.6	0

Total Amount (a+b+c)	6363.79343
Total GST (a)	224.929296
OVERHEAD CHARGES @ 7.5% (+)	494.15420445
CONTRACTOR PROFIT @ 7.5% (+)	531.21576978375
LABOUR CESS @ 1% (+)	76.140927002338
Grand Total	7690.2336272361
Say For Unit 1 (Grand Total/1)	7690.2336272361

Item 3
R.C.C. Work (AR0410c): Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc
Sub-Item of Work R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	58374.79	1558.606893	0

BRM092 : Non-sal bullahs 75mm. mean dia of any length.	1.26	1Mtr.	30.81	38.8206	0
LR008 : Sangi mulia	0.5	Per day	512	256	0
LR027 : Carpenter	0.5	Per day	562	281	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	198.296	5.2945032	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	198.296	1.21753744	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	0	0	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	0	0	0

Total Amount (a+b+c)	2140.93953364
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	160.570465023
CONTRACTOR PROFIT @ 7.5% (+)	172.61324989972
LABOUR CESS @ 1% (+)	24.741232485627
Grand Total	2498.8644810484
Say For Unit 1 (Grand Total/10)	249.88644810484

Item 4

Concrete (AR0307): Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaicaon and direction of Engineer-in charge.

Sub-Item of Work

Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	3.2	Per day	462	1478.4	0
LR025 : Mason	0.68	Per day	562	382.16	0
BRM340 : Cement	3.23	1 Qntl.	545.68	1762.5464	317.258352

BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	1396.62	1256.958	0

b) Carriage Rate Details						
Particular	Quantity	Unit	Rate	Amount	GST	
BRM340 : Cement	3.23	1 Qntl.	24.787	80.06201	0	
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	627.55	282.3975	0	
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	1202.31	1082.079	0	

c) Royalty Rate Details						
Particular	Quantity	Unit	Rate	Amount	GST	
BRM340 : Cement	3.23	1 Qntl.	0	0	0	
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	427.25	192.2625	0	
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	522.5	470.25	0	

Total Amount (a+b+c)	7668.51141				
Total GST (a)	317.258352				
OVERHEAD CHARGES @ 7.5% (+)	598.93273215				
CONTRACTOR PROFIT @ 7.5% (+)	643.85268706125				
LABOUR CESS @ 1% (+)	92.285551812112				
Grand Total	9320.8407330234				
Say For Unit 1 (Grand Total/1)	9320.8407330234				

Item 5
Earth Work (AR0101aa): Earthwork in ordinary soil in foundation and plinth within 50m, initial lead and 1.5m, initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per direction of the Engineer-in-charge per 100 cum
Sub-Item of Work Earthwork in ordinary soil in foundation and plinth within 50m, initial lead and 1.5m, initial lift

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	19.2	Per day	462	8870.4	0
LR001 : Male mulia	19.2	Per day	462	8870.4	0

Total Amount (a+b+c)	17740.8
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	1330.56
CONTRACTOR PROFIT @ 7.5% (+)	1430.352
LABOUR CESS @ 1% (+)	205.01712
Grand Total	20706.72912
Say For Unit 1 (Grand Total/100)	207.0672912

SASHIKANTA MOHALIK
JE
Baleshwar Block

PURUSOTTAM KARAN
AEE
Baleshwar Block

Uttam Kumar Jena
BDO
Baleshwar Block