

Analysis

**OD/355/3393/275607/397584/00104954 : Installation of Solar LED Mini Mast Light near
Taradevi Mandira, Ahana, Tentulipada
Block : Tirtol, Gram Panchayat : Tentulipada
Created By:Girija Sankar Mallick**

Item 1
R.C.C. Work (AR0404Aa): Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)
Sub-Item of Work Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
Combine :: R.C.C. Work (AR0404A)					
PM096 : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0
PM083 : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0
LR001 : Male mulia	1.3333	Per day	462	615.9846	0
LR025 : Mason	0.1	Per day	562	56.2	0
LR010 : Mate	0.0573	Per day	512	29.3376	0
BRM340 : Cement	3.4733	1 Qntl.	563.56	1957.412948	352.33433064
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	71.71	32.2695	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1415.1	509.436	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1382.29	746.4366	0
Combine :: R.C.C. Work (AR0410c)					
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	1Cum.	58374.79	233.79103395	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.189	1Mtr.	30.81	5.82309	0
LR008 : Sangi mulia	0.075	Per day	512	38.4	0
LR027 : Carpenter	0.075	Per day	562	42.15	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	24.787	86.0926871	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	471.31	212.0895	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1505.91	542.1276	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1505.91	813.1914	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	1Cum.	198.296	0.79417548	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.000921	1Mtr.	198.296	0.182630616	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	199.25	89.6625	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	444.5	160.02	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	444.5	240.03	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	1Cum.	0	0	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.000921	1Mtr.	0	0	0

Total Amount (a+b+c)	6783.251865146
Total GST (a)	352.33433064
OVERHEAD CHARGES @ 7.5% (+)	535.16896468395
CONTRACTOR PROFIT @ 7.5% (+)	575.30663703525
LABOUR CESS @ 1% (+)	82.460617975052
Grand Total	8328.5224154802
Say For Unit 1 (Grand Total/1)	8328.5224154802

RAMACHANDRA SARANGI
JE
Tirtol Block

SUCHISMITA BEHERA
AEE
Tirtol Block

Girija Sankar Mallick
BDO
Tirtol Block