

Analysis

OD/356/3403/118494/400448/00113819 : Construction of Shiva Mandira Boundary Wall
Block : Sukinda, Gram Panchayat : Bartanda
Created By:Prangyan Primita Prusty

Item 1
Earth Work (AR0102aa): Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge
Sub-Item of Work Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	25.8	Per day	462	11919.6	0
LR001 : Male mulia	25.8	Per day	462	11919.6	0
Total Amount (a+b+c)				23839.2	
Total GST (a)					0
OVERHEAD CHARGES @ 7.5% (+)					1787.94
CONTRACTOR PROFIT @ 7.5% (+)					1922.0355
LABOUR CESS @ 1% (+)					275.491755
Grand Total					27824.667255
Say For Unit 1 (Grand Total/100)					278.24667255

Item 2
Earth Work (AR0115): Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work Filling foundation and plinth with sand well watered and rammed

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	71.94	7194	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	731.71	73171	0

c) Royalty Rate Details					
-------------------------	--	--	--	--	--

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	274.25	27425	0
Total Amount (a+b+c)				113500.32	
Total GST (a)					0
OVERHEAD CHARGES @ 7.5% (+)				8512.524	
CONTRACTOR PROFIT @ 7.5% (+)				9150.9633	
LABOUR CESS @ 1% (+)				1311.638073	
Grand Total				132475.445373	
Say For Unit 1 (Grand Total/100)				1324.75445373	

Item 3

Concrete (AR0303): Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work
Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR025 : Mason	0.18	Per day	562	101.16	0
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	2.5	Per day	462	1155	0
BRM340 : Cement	2.29	1 Qntl.	543.88	1245.4852	224.187336
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	76.88	36.9024	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	940.6	902.976	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	30.732	70.37628	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	731.71	351.2208	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	796.81	764.9376	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	274.25	131.64	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	444.5	426.72	0

Total Amount (a+b+c)	5833.21828
-----------------------------	------------

Total GST (a)	224.187336
OVERHEAD CHARGES @ 7.5% (+)	454.3054212
CONTRACTOR PROFIT @ 7.5% (+)	488.37832779
LABOUR CESS @ 1% (+)	70.0008936499
Grand Total	7070.0902586399
Say For Unit 1 (Grand Total/1)	7070.0902586399

Item 4

R.C.C. Work (AR0404Aa): Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)

Sub-Item of Work

Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
Combine :: R.C.C. Work (AR0404A)					
PM096 : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0
PM083 : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0
LR001 : Male mulia	1.3333	Per day	462	615.9846	0
LR025 : Mason	0.1	Per day	562	56.2	0
LR010 : Mate	0.0573	Per day	512	29.3376	0
BRM340 : Cement	3.4733	1 Qntl.	543.88	1889.058404	340.03051272
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1415.1	509.436	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1382.29	746.4366	0
Combine :: R.C.C. Work (AR0410c)					
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	1Cum.	58374.79	233.79103395	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.189	1Mtr.	30.81	5.82309	0
LR008 : Sangi mulia	0.075	Per day	512	38.4	0

LR027 : Carpenter	0.075	Per day	562	42.15	0
-------------------	-------	---------	-----	-------	---

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	24.787	86.0926871	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	731.71	329.2695	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	796.81	286.8516	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	796.81	430.2774	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	1Cum.	198.296	0.79417548	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.000921	1Mtr.	198.296	0.182630616	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	274.25	123.4125	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	444.5	160.02	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	444.5	240.03	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	1Cum.	0	0	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.000921	1Mtr.	0	0	0

Total Amount (a+b+c)	6229.963821146
Total GST (a)	340.03051272
OVERHEAD CHARGES @ 7.5% (+)	492.74957503995
CONTRACTOR PROFIT @ 7.5% (+)	529.70579316795
LABOUR CESS @ 1% (+)	75.924497020739
Grand Total	7668.3741990946
Say For Unit 1 (Grand Total/1)	7668.3741990946

Item 5
R.C.C. Work (AR0409): Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.

Sub-Item of Work

Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR001 : Male mulia	8	Per day	462	3696	0
LR046 : Blacksmith	3	Per day	612	1836	0
LR010 : Mate	0.44	Per day	512	225.28	0
BRM162 : Binding Wire.	8	1 Kg.	90.1	720.8	0
BRM341 : Steel	10.5	1 Qntl.	6374.89	66936.345	12048.5421

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	10.5	1 Qntl.	30.732	322.686	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	10.5	1 Qntl.	0	0	0

Total Amount (a+b+c)

73737.111

Total GST (a)

12048.5421

OVERHEAD CHARGES @ 7.5% (+)

6433.9239825

CONTRACTOR PROFIT @ 7.5% (+)

6916.4682811875

LABOUR CESS @ 1% (+)

991.36045363687

Grand Total

100127.40581732

Say For Unit 1 (Grand Total/10)

10012.740581732

Item 6

Masonry Brick Work (AR0603bi): Brickwork with Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work

Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.14	Per day	462	64.68	0
BRMMR0025 : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK	1	1 Cum	33	33	0

LR001 : Male mulia	2.82	Per day	462	1302.84	0
LR025 : Mason	1.05	Per day	562	590.1	0
LR044 : Mason	0.35	Per day	612	214.2	0
BRM340 : Cement	0.672	1 Qntl.	543.88	365.48736	65.7877248
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	76.88	21.5264	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	350	1000 Nos	5.0305	1760.675	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.672	1 Qntl.	30.732	20.651904	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	731.71	204.8788	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	350	1000 Nos	1.01135	353.9725	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.672	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	274.25	76.79	0
BRM005 : Fly ash bricks of 25 Cm. x 12 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	350	1000 Nos	0	0	0

Total Amount (a+b+c)	5008.801964
Total GST (a)	65.7877248
OVERHEAD CHARGES @ 7.5% (+)	380.59422666
CONTRACTOR PROFIT @ 7.5% (+)	409.1387936595
LABOUR CESS @ 1% (+)	58.643227091195
Grand Total	5922.9659362107
Say For Unit 1 (Grand Total/1)	5922.9659362107

Item 7

Plastering (AR1004): 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.

Sub-Item of Work

12mm thick cement plaster (1:6) over Brick work in inside

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
------------	----------	------	------	--------	-----

LR002 : Female mulia	0.05	Per day	462	23.1	0
LR001 : Male mulia	0.07	Per day	462	32.34	0
LR025 : Mason	0.14	Per day	562	78.68	0
BRM340 : Cement	0.0358	1 Qntl.	543.88	19.470904	3.50476272
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	76.88	1.1532	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0358	1 Qntl.	30.732	1.1002056	0
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	731.71	10.97565	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0358	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	274.25	4.11375	0

Total Amount (a+b+c)	170.9337096
Total GST (a)	3.50476272
OVERHEAD CHARGES @ 7.5% (+)	13.082885424
CONTRACTOR PROFIT @ 7.5% (+)	14.0641018308
LABOUR CESS @ 1% (+)	2.015854595748
Grand Total	203.60131417055
Say For Unit 1 (Grand Total/1)	203.60131417055

Item 8

Plastering (AR1014): 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.

Sub-Item of Work

16mm thick cement Plaster in CM (1:6) over brick work in inside.

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.11	Per day	462	50.82	0
LR001 : Male mulia	0.13	Per day	462	60.06	0
LR025 : Mason	0.16	Per day	562	89.92	0
BRM340 : Cement	0.043	1 Qntl.	543.88	23.38684	4.2096312
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	76.88	1.38384	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.043	1 Qntl.	30.732	1.321476	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	731.71	13.17078	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.043	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	274.25	4.9365	0

Total Amount (a+b+c)	244.999436				
Total GST (a)	4.2096312				
OVERHEAD CHARGES @ 7.5% (+)	18.69068004				
CONTRACTOR PROFIT @ 7.5% (+)	20.092481043				
LABOUR CESS @ 1% (+)	2.87992228283				
Grand Total	290.87215056583				
Say For Unit 1 (Grand Total/1)	290.87215056583				

Item 9

Painting (AR0901a): Priming one coat in inner surface with primer of approved quality over woodwork including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.

Sub-Item of Work

Priming one coat in inner surface with primer of approved quality over woodwork

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR048 : Painter/ Polisher	0.5	Per day	612	306	0
BRM138 : Wood Primer	0.6975	1 Litre	155.08	108.1683	0
LR001 : Male mulia	0.5	Per day	462	231	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM138 : Wood Primer	0.6975	1 Litre	0.30732	0.2143557	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM138 : Wood Primer	0.6975	1 Litre	0	0	0

Total Amount (a+b+c)	645.3826557				
Total GST (a)	0				
OVERHEAD CHARGES @ 7.5% (+)	48.4036991775				

CONTRACTOR PROFIT @ 7.5% (+)	52.033976615813
LABOUR CESS @ 1% (+)	7.4582033149331
Grand Total	753.27853480825
Say For Unit 1 (Grand Total/9.3)	80.997691914865

Item 10

Painting (AR0918Ai): Finishing wall one coat with weather coat including all costs of labour, Paint, Primer and Brushes required for the work etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work

Finishing wall one coat with weather coat

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	0.75	1 Ltr	193	144.75	0
LR001 : Male mulia	0.43	Per day	462	198.66	0
LR048 : Painter/ Polisher	0.36	Per day	612	220.32	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	0.75	1 Ltr	0.30732	0.23049	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	0.75	1 Ltr	0	0	0

Total Amount (a+b+c)	563.96049
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	42.29703675
CONTRACTOR PROFIT @ 7.5% (+)	45.46931450625
LABOUR CESS @ 1% (+)	6.5172684125625
Grand Total	658.24410966881
Say For Unit 1 (Grand Total/10)	65.824410966881

Item 11

R.C.C. Work (AR0404Ab): Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Plinth band)

Sub-Item of Work

Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
Combine :: R.C.C. Work (AR0404A)					
PM096 : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0
PM083 : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0
LR001 : Male mulia	1.3333	Per day	462	615.9846	0
LR025 : Mason	0.1	Per day	562	56.2	0
LR010 : Mate	0.0573	Per day	512	29.3376	0
BRM340 : Cement	3.4733	1 Qntl.	543.88	1889.058404	340.03051272
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1415.1	509.436	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1382.29	746.4366	0
Combine :: R.C.C. Work (AR0410c)					
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.01335	1Cum.	58374.79	779.3034465	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.63	1Mtr.	30.81	19.4103	0
LR008 : Sangi mulia	0.25	Per day	512	128	0
LR027 : Carpenter	0.25	Per day	562	140.5	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	30.732	106.7414556	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	731.71	329.2695	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	796.81	286.8516	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	796.81	430.2774	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.01335	1Cum.	198.296	2.6472516	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00307	1Mtr.	198.296	0.60876872	0

c) Royalty Rate Details					
--------------------------------	--	--	--	--	--

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	274.25	123.4125	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	444.5	160.02	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	444.5	240.03	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.01335	1Cum.	0	0	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00307	1Mtr.	0	0	0

Total Amount (a+b+c)	6999.94142642
Total GST (a)	340.03051272
OVERHEAD CHARGES @ 7.5% (+)	550.4978954355
CONTRACTOR PROFIT @ 7.5% (+)	591.78523759316
LABOUR CESS @ 1% (+)	84.822550721687
Grand Total	8567.0776228904
Say For Unit 1 (Grand Total/1)	8567.0776228904

Item 12

R.C.C. Work (AR0404Ac): Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge. (RCC Beams, Column, Girder & Bressmer etc)

Sub-Item of Work

Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
Combine :: R.C.C. Work (AR0404A)					
PM096 : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0
PM083 : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0
LR001 : Male mulia	1.3333	Per day	462	615.9846	0
LR025 : Mason	0.1	Per day	562	56.2	0
LR010 : Mate	0.0573	Per day	512	29.3376	0
BRM340 : Cement	3.4733	1 Qntl.	543.88	1889.058404	340.03051272
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0

BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1415.1	509.436	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1382.29	746.4366	0
Combine :: R.C.C. Work (AR0410d)					
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	4.4196	1Mtr	51.87	229.244652	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.041529	1Cum.	58374.79	2424.24665391	0
LR008 : Sangi mulia	5.23875	Per day	512	2682.24	0
LR027 : Carpenter	5.23875	Per day	562	2944.1775	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	30.732	106.7414556	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	731.71	329.2695	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	796.81	286.8516	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	796.81	430.2774	0
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.045339	1Mtr	198.296	8.990542344	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.041529	1Cum.	198.296	8.235034584	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	274.25	123.4125	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	444.5	160.02	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	444.5	240.03	0
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.045339	1Mtr	0	0	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.041529	1Cum.	0	0	0

Total Amount (a+b+c)

14226.606042438

Total GST (a)	340.03051272
OVERHEAD CHARGES @ 7.5% (+)	1092.4977416369
CONTRACTOR PROFIT @ 7.5% (+)	1174.4350722596
LABOUR CESS @ 1% (+)	168.33569369054
Grand Total	17001.905062745
Say For Unit 1 (Grand Total/1)	17001.905062745

Ratnakar Sahoo
JE
Sukinda Block

Asish Kumar Biswal
AEE
Sukinda Block

Prangyan Primita Prusty
BDO
Sukinda Block