

Analysis

OD/371/3565/121404/382503/00113026 : Construction of Vana Surakshya Samiti Building at
Ambajhari

Block : Rairakhol, Gram Panchayat : Kadaligarh

Created By:Rajendra Senapati

Item 1

Earth Work (AR0102aa): Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge

Sub-Item of Work

Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	25.8	Per day	462	11919.6	0
LR001 : Male mulia	25.8	Per day	462	11919.6	0

Total Amount (a+b+c)

23839.2

Total GST (a)

0

OVERHEAD CHARGES @ 7.5% (+)

1787.94

CONTRACTOR PROFIT @ 7.5% (+)

1922.0355

LABOUR CESS @ 1% (+)

275.491755

Grand Total

27824.667255

Say For Unit 1 (Grand Total/100)

278.24667255

Item 2

Earth Work (AR0115): Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

Filling foundation and plinth with sand well watered and rammed

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	70	7000	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	276.01	27601	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	69	6900	0

Total Amount (a+b+c)	47211.32				
Total GST (a)	0				
OVERHEAD CHARGES @ 7.5% (+)	3540.849				
CONTRACTOR PROFIT @ 7.5% (+)	3806.412675				
LABOUR CESS @ 1% (+)	545.58581675				
Grand Total	55104.16749175				
Say For Unit 1 (Grand Total/100)	551.0416749175				

Item 3
Concrete (AR0303): Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR025 : Mason	0.18	Per day	562	101.16	0
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	2.5	Per day	462	1155	0
BRM340 : Cement	2.29	1 Qntl.	542	1241.18	223.4124
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	76.88	36.9024	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	950	912	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	42.622	97.60438	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	341.11	163.7328	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	536.41	514.9536	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	69	33.12	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	189	181.44	0

Total Amount (a+b+c)	5083.89318
Total GST (a)	223.4124
OVERHEAD CHARGES @ 7.5% (+)	398.0479185
CONTRACTOR PROFIT @ 7.5% (+)	427.9015123875
LABOUR CESS @ 1% (+)	61.332550108875
Grand Total	6194.5875609964
Say For Unit 1 (Grand Total/1)	6194.5875609964

Item 4

Masonry Brick Work (AR0603c): Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work

Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.14	Per day	462	64.68	0
BRM006 : Fly ash bricks of 23 Cm. x 11 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance ± 2 %	400	1000 Nos	4.55488	1821.952	0
LR001 : Male mulia	2.82	Per day	462	1302.84	0
LR025 : Mason	1.05	Per day	562	590.1	0
LR044 : Mason	0.35	Per day	612	214.2	0
BRM340 : Cement	0.672	1 Qntl.	542	364.224	65.56032
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	76.88	21.5264	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM006 : Fly ash bricks of 23 Cm. x 11 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance ± 2 %	400	1000 Nos	0.92692	370.768	0
BRM340 : Cement	0.672	1 Qntl.	42.622	28.641984	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	341.11	95.5108	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM006 : Fly ash bricks of 23 Cm. x 11 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance ± 2 %	400	1000 Nos	0	0	0

BRM340 : Cement	0.672	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	69	19.32	0
Total Amount (a+b+c)	4893.763184				
Total GST (a)	65.56032				
OVERHEAD CHARGES @ 7.5% (+)	371.9492628				
CONTRACTOR PROFIT @ 7.5% (+)	399.84545751				
LABOUR CESS @ 1% (+)	57.3111822431				
Grand Total	5788.4294065531				
Say For Unit 1 (Grand Total/1)	5788.4294065531				

Item 5

R.C.C. Work (AR0404Aa): Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)

Sub-Item of Work

Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
Combine :: R.C.C. Work (AR0404A)					
PM096 : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0
PM083 : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0
LR001 : Male mulia	1.3333	Per day	462	615.9846	0
LR025 : Mason	0.1	Per day	562	56.2	0
LR010 : Mate	0.0573	Per day	512	29.3376	0
BRM340 : Cement	3.4733	1 Qntl.	542	1882.5286	338.855148
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1418.67	510.7212	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1382.29	746.4366	0
Combine :: R.C.C. Work (AR0410c)					

BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	1Cum.	58374.79	233.79103395	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.189	1Mtr.	30.81	5.82309	0
LR008 : Sangi mulia	0.075	Per day	512	38.4	0
LR027 : Carpenter	0.075	Per day	562	42.15	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	42.622	148.0389926	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	341.11	153.4995	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	536.41	193.1076	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	536.41	289.6614	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	1Cum.	198.296	0.79417548	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.000921	1Mtr.	198.296	0.182630616	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	69	31.05	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	189	68.04	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	189	102.06	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	1Cum.	0	0	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.000921	1Mtr.	0	0	0

Total Amount (a+b+c)	5554.223022646
Total GST (a)	338.855148
OVERHEAD CHARGES @ 7.5% (+)	441.98086279845
CONTRACTOR PROFIT @ 7.5% (+)	475.12942750833
LABOUR CESS @ 1% (+)	68.101884609528
Grand Total	6878.2903455623
Say For Unit 1 (Grand Total/1)	6878.2903455623

Item 6

R.C.C. Work (AR0404Ab): Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Plinth band)

Sub-Item of Work

Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
Combine :: R.C.C. Work (AR0404A)					
PM096 : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0
PM083 : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0
LR001 : Male mulia	1.3333	Per day	462	615.9846	0
LR025 : Mason	0.1	Per day	562	56.2	0
LR010 : Mate	0.0573	Per day	512	29.3376	0
BRM340 : Cement	3.4733	1 Qntl.	542	1882.5286	338.855148
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1418.67	510.7212	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1382.29	746.4366	0
Combine :: R.C.C. Work (AR0410c)					
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.01335	1Cum.	58374.79	779.3034465	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.63	1Mtr.	30.81	19.4103	0
LR008 : Sangi mulia	0.25	Per day	512	128	0
LR027 : Carpenter	0.25	Per day	562	140.5	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	42.622	148.0389926	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	341.11	153.4995	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	536.41	193.1076	0

BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	536.41	289.6614	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.01335	1Cum.	198.296	2.6472516	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00307	1Mtr.	198.296	0.60876872	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	69	31.05	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	189	68.04	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	189	102.06	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.01335	1Cum.	0	0	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00307	1Mtr.	0	0	0

Total Amount (a+b+c)	6303.55185942
Total GST (a)	338.855148
OVERHEAD CHARGES @ 7.5% (+)	498.1805255565
CONTRACTOR PROFIT @ 7.5% (+)	535.54406497324
LABOUR CESS @ 1% (+)	76.761315979497
Grand Total	7752.8929139292
Say For Unit 1 (Grand Total/1)	7752.8929139292

Item 7

R.C.C. Work (AR0404Ac): Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge. (RCC Beams, Column, Girder & Bressmer etc)

Sub-Item of Work

Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
Combine :: R.C.C. Work (AR0404A)					
PM096 : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0
PM083 : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0

LR001 : Male mulia	1.3333	Per day	462	615.9846	0
LR025 : Mason	0.1	Per day	562	56.2	0
LR010 : Mate	0.0573	Per day	512	29.3376	0
BRM340 : Cement	3.4733	1 Qntl.	542	1882.5286	338.855148
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1418.67	510.7212	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1382.29	746.4366	0
Combine :: R.C.C. Work (AR0410d)					
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	4.4196	1Mtr	51.87	229.244652	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.041529	1Cum.	58374.79	2424.24665391	0
LR008 : Sangi mulia	5.23875	Per day	512	2682.24	0
LR027 : Carpenter	5.23875	Per day	562	2944.1775	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	42.622	148.0389926	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	341.11	153.4995	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	536.41	193.1076	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	536.41	289.6614	0
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.045339	1Mtr	198.296	8.990542344	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.041529	1Cum.	198.296	8.235034584	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	69	31.05	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	189	68.04	0

BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	189	102.06	0
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.045339	1Mtr	0	0	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.041529	1Cum.	0	0	0

Total Amount (a+b+c)	13530.216475438
Total GST (a)	338.855148
OVERHEAD CHARGES @ 7.5% (+)	1040.1803717579
CONTRACTOR PROFIT @ 7.5% (+)	1118.1938996397
LABOUR CESS @ 1% (+)	160.27445894836
Grand Total	16187.720353784
Say For Unit 1 (Grand Total/1)	16187.720353784

Item 8
R.C.C. Work (AR0404Ad): Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Lintels)
Sub-Item of Work Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
Combine :: R.C.C. Work (AR0404A)					
PM096 : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0
PM083 : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0
LR001 : Male mulia	1.3333	Per day	462	615.9846	0
LR025 : Mason	0.1	Per day	562	56.2	0
LR010 : Mate	0.0573	Per day	512	29.3376	0
BRM340 : Cement	3.4733	1 Qntl.	542	1882.5286	338.855148
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1418.67	510.7212	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1382.29	746.4366	0

Combine :: R.C.C. Work (AR0410e)					
BRM094 : Non-sal bullahs 125mm. mean dia of any length.	3.7695	1Mtr.	41.81	157.602795	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0741335	1Cum.	58374.79	4327.527494465	0
LR008 : Sangi mulia	2.24375	Per day	512	1148.8	0
LR027 : Carpenter	2.24375	Per day	562	1260.9875	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	42.622	148.0389926	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	341.11	153.4995	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	536.41	193.1076	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	536.41	289.6614	0
BRM094 : Non-sal bullahs 125mm. mean dia of any length.	0.049542	1Mtr.	198.296	9.823980432	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0741335	1Cum.	198.296	14.700376516	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	69	31.05	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	189	68.04	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	189	102.06	0
BRM094 : Non-sal bullahs 125mm. mean dia of any length.	0.049542	1Mtr.	0	0	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0741335	1Cum.	0	0	0

Total Amount (a+b+c)	12152.524239013
Total GST (a)	338.855148
OVERHEAD CHARGES @ 7.5% (+)	936.85345402597
CONTRACTOR PROFIT @ 7.5% (+)	1007.1174630779
LABOUR CESS @ 1% (+)	144.35350304117
Grand Total	14579.703807158
Say For Unit 1 (Grand Total/1)	14579.703807158

Item 9

R.C.C. Work (AR0404Ag): Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Roof slab, landing, balcony, sun shade)

Sub-Item of Work

Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
Combine :: R.C.C. Work (AR0404A)					
PM096 : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0
PM083 : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0
LR001 : Male mulia	1.3333	Per day	462	615.9846	0
LR025 : Mason	0.1	Per day	562	56.2	0
LR010 : Mate	0.0573	Per day	512	29.3376	0
BRM340 : Cement	3.4733	1 Qntl.	542	1882.5286	338.855148
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1418.67	510.7212	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1382.29	746.4366	0
Combine :: R.C.C. Work (AR0410a)					
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	6.2216	1Mtr	51.87	322.714392	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0502172	1Cum.	58374.79	2931.418504388	0
LR008 : Sangi mulia	3.05525	Per day	512	1564.288	0
LR027 : Carpenter	3.05525	Per day	562	1717.0505	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	42.622	148.0389926	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	341.11	153.4995	0

BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	536.41	193.1076	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	536.41	289.6614	0
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.076659	1Mtr	198.296	15.201173064	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0502172	1Cum.	198.296	9.9578698912	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	69	31.05	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	189	68.04	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	189	102.06	0
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.076659	1Mtr	0	0	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0502172	1Cum.	0	0	0

Total Amount (a+b+c)	11793.712531943
Total GST (a)	338.855148
OVERHEAD CHARGES @ 7.5% (+)	909.94257599574
CONTRACTOR PROFIT @ 7.5% (+)	978.18826919542
LABOUR CESS @ 1% (+)	140.20698525134
Grand Total	14160.905510386
Say For Unit 1 (Grand Total/1)	14160.905510386

Item 10

R.C.C. Work (AR0409): Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.

Sub-Item of Work

Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR001 : Male mulia	8	Per day	462	3696	0
LR046 : Blacksmith	3	Per day	612	1836	0
LR010 : Mate	0.44	Per day	512	225.28	0

BRM162 : Binding Wire.	8	1 Kg.	90	720	0
BRM341 : Steel	10.5	1 Qntl.	6404.74	67249.77	12104.9586

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	10.5	1 Qntl.	42.622	447.531	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	10.5	1 Qntl.	0	0	0

Total Amount (a+b+c)					74174.581
Total GST (a)					12104.9586
OVERHEAD CHARGES @ 7.5% (+)					6470.96547
CONTRACTOR PROFIT @ 7.5% (+)					6956.28788025
LABOUR CESS @ 1% (+)					997.0679295025
Grand Total					100703.86087975
Say For Unit 1 (Grand Total/10)					10070.386087975

Item 11

Masonry Brick Work (AR0603ci): Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work

Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.14	Per day	462	64.68	0
BRMMR0025 : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK	1	1 Cum	33	33	0
BRM006 : Fly ash bricks of 23 Cm. x 11 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm ² with dimensional tolerance ± 2 %	400	1000 Nos	4.55488	1821.952	0
LR001 : Male mulia	2.82	Per day	462	1302.84	0
LR025 : Mason	1.05	Per day	562	590.1	0
LR044 : Mason	0.35	Per day	612	214.2	0
BRM340 : Cement	0.672	1 Qntl.	542	364.224	65.56032

BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	76.88	21.5264	0
--	------	-------	-------	---------	---

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM006 : Fly ash bricks of 23 Cm. x 11 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	400	1000 Nos	0.92692	370.768	0
BRM340 : Cement	0.672	1 Qntl.	42.622	28.641984	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	341.11	95.5108	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM006 : Fly ash bricks of 23 Cm. x 11 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	400	1000 Nos	0	0	0
BRM340 : Cement	0.672	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	69	19.32	0

Total Amount (a+b+c)	4926.763184
Total GST (a)	65.56032
OVERHEAD CHARGES @ 7.5% (+)	374.4242628
CONTRACTOR PROFIT @ 7.5% (+)	402.50608251
LABOUR CESS @ 1% (+)	57.6925384931
Grand Total	5826.9463878031
Say For Unit 1 (Grand Total/1)	5826.9463878031

Item 12

Concrete (AR0317): 2.5 cm thick grading concrete (1:2:2) on roof slab with 6mm size hard granite chips including hoisting and laying in position compacting and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specification and direction of Engineer-in charge. (new work)

Sub-Item of Work

2.5 cm thick grading concrete (1:2:2) on roof slab with 6mm size hard granite chips

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR001 : Male mulia	0.36	Per day	462	166.32	0
LR044 : Mason	0.1	Per day	612	61.2	0
BRM340 : Cement	0.1208	1 Qntl.	542	65.4736	11.785248
BRM028 : Screened and washed sharp sand for mortar	0.0169	1 Cum	76.88	1.299272	0
BRM064 : Granite stone broken chips of 4.7 mm size passing through 6.7 mm sieve (crusher broken.) and retained on 2.36 mm sieve.	0.0169	1 Cum.	805	13.6045	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.1208	1 Qntl.	42.622	5.1487376	0
BRM028 : Screened and washed sharp sand for mortar	0.0169	1 Cum	341.11	5.764759	0
BRM064 : Granite stone broken chips of 4.7 mm size passing through 6.7 mm sieve (crusher broken.) and retained on 2.36 mm sieve.	0.0169	1 Cum.	536.41	9.065329	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.1208	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.0169	1 Cum	69	1.1661	0
BRM064 : Granite stone broken chips of 4.7 mm size passing through 6.7 mm sieve (crusher broken.) and retained on 2.36 mm sieve.	0.0169	1 Cum.	189	3.1941	0

Total Amount (a+b+c)	332.2363976				
Total GST (a)	11.785248				
OVERHEAD CHARGES @ 7.5% (+)	25.80162342				
CONTRACTOR PROFIT @ 7.5% (+)	27.7367451765				
LABOUR CESS @ 1% (+)	3.975600141965				
Grand Total	401.53561433846				
Say For Unit 1 (Grand Total/1)	401.53561433846				

Item 13

Plastering (AR1004): 12mm thick cement plaster (1:6) over Brick work in inside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.

Sub-Item of Work
12mm thick cement plaster (1:6) over Brick work in inside

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.05	Per day	462	23.1	0
LR001 : Male mulia	0.07	Per day	462	32.34	0
LR025 : Mason	0.14	Per day	562	78.68	0
BRM340 : Cement	0.0358	1 Qntl.	542	19.4036	3.492648
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	76.88	1.1532	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0358	1 Qntl.	42.622	1.5258676	0

BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	341.11	5.11665	0
--	-------	-------	--------	---------	---

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0358	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	69	1.035	0

Total Amount (a+b+c)	162.3543176
Total GST (a)	3.492648
OVERHEAD CHARGES @ 7.5% (+)	12.43852242
CONTRACTOR PROFIT @ 7.5% (+)	13.3714116015
LABOUR CESS @ 1% (+)	1.916568996215
Grand Total	193.57346861772
Say For Unit 1 (Grand Total/1)	193.57346861772

Item 14

Plastering (AR1014i): 16mm thick cement Plaster in CM (1:6) over brick work in outside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.

Sub-Item of Work

16mm thick cement Plaster in CM (1:6) over brick work in outside (outside)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.11	Per day	462	50.82	0
LR001 : Male mulia	0.13	Per day	462	60.06	0
LR025 : Mason	0.16	Per day	562	89.92	0
BRM340 : Cement	0.043	1 Qntl.	542	23.306	4.19508
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	76.88	1.38384	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.043	1 Qntl.	42.622	1.832746	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	341.11	6.13998	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.043	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	69	1.242	0

Total Amount (a+b+c)	234.704566
-----------------------------	------------

Total GST (a)	4.19508
OVERHEAD CHARGES @ 7.5% (+)	17.91747345
CONTRACTOR PROFIT @ 7.5% (+)	19.26128395875
LABOUR CESS @ 1% (+)	2.7607840340875
Grand Total	278.83918744284
Say For Unit 1 (Grand Total/1)	278.83918744284

Item 15

Flooring (AR0802ii): 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips including punning incl. cost, conveyance & royalty of materials as per direction of Engineer-in-charge.

Sub-Item of Work

2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR001 : Male mulia	0.14	Per day	462	64.68	0
LR002 : Female mulia	0.22	Per day	462	101.64	0
LR044 : Mason	0.13	Per day	612	79.56	0
BRM340 : Cement	0.0858	1 Qntl.	542	46.5036	8.370648
BRM028 : Screened and washed sharp sand for mortar	0.012	1 Cum	76.88	0.92256	0
BRM057 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve)(Hand broken)	0.023	1 Cum.	1080	24.84	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0858	1 Qntl.	42.622	3.6569676	0
BRM028 : Screened and washed sharp sand for mortar	0.012	1 Cum	341.11	4.09332	0
BRM057 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve)(Hand broken)	0.023	1 Cum.	536.41	12.33743	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0858	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.012	1 Cum	69	0.828	0

BRM057 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve)(Hand broken)	0.023	1 Cum.	189	4.347	0
Total Amount (a+b+c)	343.4088776				
Total GST (a)	8.370648				
OVERHEAD CHARGES @ 7.5% (+)	26.38346442				
CONTRACTOR PROFIT @ 7.5% (+)	28.3622242515				
LABOUR CESS @ 1% (+)	4.065252142715				
Grand Total	410.59046641421				
Say For Unit 1 (Grand Total/1)	410.59046641421				

Item 16

Flooring (AR0816): Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor , treads or steps and landing on a 25mm thick bed of cement mortar 1:1 (1cement: 1sand) jointed with neat cement slurry mixed with pigment to match the shades of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.

Sub-Item of Work

Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRMMR0027 : Wax Polish	10	1 Sqm	8.5	85	0
BRM130 : Tiles up to 30cm x 30cm / 40cm x 40cm special plain / printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755	10	1 Sqm.	445	4450	0
LR001 : Male mulia	2.16	Per day	462	997.92	0
LR044 : Mason	2.16	Per day	612	1321.92	0
LR008 : Sangi mulia	5.5	Per day	512	2816	0
BRM340 : Cement	2.737	1 Qntl.	542	1483.454	267.02172
BRM028 : Screened and washed sharp sand for mortar	0.13	1 Cum	76.88	9.9944	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM130 : Tiles up to 30cm x 30cm / 40cm x 40cm special plain / printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755	10	1 Sqm.	14.5102781	145.102781	0
BRM340 : Cement	2.737	1 Qntl.	42.622	116.656414	0

BRM028 : Screened and washed sharp sand for mortar	0.13	1 Cum	341.11	44.3443	0
---	------	----------	--------	---------	---

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM130 : Tiles up to 30cm x 30cm / 40cm x 40cm special plain / printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755	10	1 Sqm.	0	0	0
BRM340 : Cement	2.737	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.13	1 Cum	69	8.97	0

Total Amount (a+b+c)	11479.361895
Total GST (a)	267.02172
OVERHEAD CHARGES @ 7.5% (+)	880.978771125
CONTRACTOR PROFIT @ 7.5% (+)	947.05217895937
LABOUR CESS @ 1% (+)	135.74414565084
Grand Total	13710.158710735
Say For Unit 1 (Grand Total/10)	1371.0158710735

Item 17
Painting (AR0903i): Painting two coats of enamel paint in outer surface paint including all costs of labour, Paint and brushes required for the work etc. complete and as per direction of Engineer-in-charge.(Outside)
Sub-Item of Work Painting two coats of enamel paint in outer surface paint (outer surface)

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR048 : Painter/ Polisher	1.25	Per day	612	765	0
LR001 : Male mulia	1.1	Per day	462	508.2	0
BRM141 : Enamel paint	1.1625	1 Litre	205.34	238.70775	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM141 : Enamel paint	1.1625	1 Litre	0.42622	0.49548075	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM141 : Enamel paint	1.1625	1 Litre	0	0	0

Total Amount (a+b+c)	1512.40323075
Total GST (a)	0

OVERHEAD CHARGES @ 7.5% (+)	113.43024230625
CONTRACTOR PROFIT @ 7.5% (+)	121.93751047922
LABOUR CESS @ 1% (+)	17.477709835355
Grand Total	1765.2486933708
Say For Unit 1 (Grand Total/9.3)	189.81168745923

Item 18

Painting (AR0901c): Priming one coat with inner surface primer of approved quality oil-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.

Sub-Item of Work

Priming one coat with inner surface primer of approved quality oil-bound primer over plastering surfaces (Inner surface)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM252 : Wall cement primer (I.S.I.) Oil bound	0.7812	1 Ltr	125.5	98.0406	0
LR048 : Painter/ Polisher	0.5	Per day	612	306	0
LR001 : Male mulia	0.5	Per day	462	231	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM252 : Wall cement primer (I.S.I.) Oil bound	0.7812	1 Ltr	0.42622	0.332963064	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM252 : Wall cement primer (I.S.I.) Oil bound	0.7812	1 Ltr	0	0	0

Total Amount (a+b+c)	635.373563064
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	47.6530172298
CONTRACTOR PROFIT @ 7.5% (+)	51.226993522035
LABOUR CESS @ 1% (+)	7.3425357381583
Grand Total	741.59610955399
Say For Unit 1 (Grand Total/9.3)	79.741517156343

Item 19

Painting (AR0901ci): Priming one coat with outer surface primer of approved quality oil-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.

Sub-Item of Work

Priming one coat with outer surface primer of approved quality oil-bound primer over plastering surfaces(Outer surface)

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM252 : Wall cement primer (I.S.I.) Oil bound	0.7812	1 Ltr	125.5	98.0406	0
LR048 : Painter/ Polisher	0.5	Per day	612	306	0
LR001 : Male mulia	0.5	Per day	462	231	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM252 : Wall cement primer (I.S.I.) Oil bound	0.7812	1 Ltr	0.42622	0.332963064	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM252 : Wall cement primer (I.S.I.) Oil bound	0.7812	1 Ltr	0	0	0

Total Amount (a+b+c)	635.373563064				
Total GST (a)	0				
OVERHEAD CHARGES @ 7.5% (+)	47.6530172298				
CONTRACTOR PROFIT @ 7.5% (+)	51.226993522035				
LABOUR CESS @ 1% (+)	7.3425357381583				
Grand Total	741.59610955399				
Say For Unit 1 (Grand Total/9.3)	79.741517156343				

Item 20
Other Building Items. (AR1902): Finishing surface of walls with cement based wall putty (water based) of approved make and finished smooth and even surface to receive painting including cost of scaffolding staging charges with cost of all materials taxes,labour,T&P,etc.complete. and as per the direction of Engineer in Charge.
Sub-Item of Work cement based wall putty (water based)

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRMMR0038 : Cement based putty	8	kg	30	240	0
LR001 : Male mulia	0.57	Per day	462	263.34	0
LR025 : Mason	0.5	Per day	562	281	0

Total Amount (a+b+c)	784.34				
Total GST (a)	0				
OVERHEAD CHARGES @ 7.5% (+)	58.8255				
CONTRACTOR PROFIT @ 7.5% (+)	63.2374125				
LABOUR CESS @ 1% (+)	9.064029125				

Grand Total	915.466941625
Say For Unit 1 (Grand Total/10)	91.5466941625

Item 21

Painting (AR0919): Finishing wall One Coat with plastic emulsion paint of approved shades on old work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)

Sub-Item of Work

Finishing wall One Coat with plastic emulsion paint of approved shades on old work (Inside)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM140 : Plastic Emulsion paint	0.75	1 Litre	249.34	187.005	0
LR001 : Male mulia	0.43	Per day	462	198.66	0
LR048 : Painter/ Polisher	0.36	Per day	612	220.32	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM140 : Plastic Emulsion paint	0.75	1 Litre	0.42622	0.319665	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM140 : Plastic Emulsion paint	0.75	1 Litre	0	0	0

Total Amount (a+b+c)	606.304665
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	45.472849875
CONTRACTOR PROFIT @ 7.5% (+)	48.883313615625
LABOUR CESS @ 1% (+)	7.0066082849062
Grand Total	707.66743677553
Say For Unit 1 (Grand Total/10)	70.766743677553

Item 22

Painting (AR0918g): Finishing wall with two coats weather coat paint of approved shade including one coat of oil bound primer in the outer surface of old work to give an even shade including all costs of labour, Paint, Brushes, and putty required for the work, etc. complete and as per direction of Engineer-in-charge. (Outside)

Sub-Item of Work

Finishing wall with two coats weather coat paint of approved shade including one coat of oil bound primer in the outer surface of old work .(Outside)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
------------	----------	------	------	--------	-----

Combine :: Painting (AR0918f)					
BRM255 : Weather Coat (I.S.I.)	0.125	1 Ltr	194.79	24.34875	0
LR001 : Male mulia	0.064	Per day	462	29.568	0
LR048 : Painter/ Polisher	0.054	Per day	612	33.048	0
Combine :: Painting (AR0901ci)					
BRM252 : Wall cement primer (I.S.I.) Oil bound	0.084	1 Ltr	125.5	10.542	0
LR048 : Painter/ Polisher	0.053763440860215	Per day	612	32.903225806452	0
LR001 : Male mulia	0.053763440860215	Per day	462	24.838709677419	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	0.125	1 Ltr	0.42622	0.0532775	0
BRM252 : Wall cement primer (I.S.I.) Oil bound	0.084	1 Ltr	0.42622	0.03580248	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	0.125	1 Ltr	0	0	0
BRM252 : Wall cement primer (I.S.I.) Oil bound	0.084	1 Ltr	0	0	0

Total Amount (a+b+c)	155.33776546387
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	11.65033240979
CONTRACTOR PROFIT @ 7.5% (+)	12.524107340525
LABOUR CESS @ 1% (+)	1.7951220521419
Grand Total	181.30732726633
Say For Unit 1 (Grand Total/1)	181.30732726633

Item 23
R.C.C. Work (AR0404Ae): Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Stairs excluding landing but including railing)
Sub-Item of Work Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
Combine :: R.C.C. Work (AR0404A)					
PM096 : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0

PM083 : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0
LR001 : Male mulia	1.3333	Per day	462	615.9846	0
LR025 : Mason	0.1	Per day	562	56.2	0
LR010 : Mate	0.0573	Per day	512	29.3376	0
BRM340 : Cement	3.4733	1 Qntl.	542	1882.5286	338.855148
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1418.67	510.7212	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1382.29	746.4366	0
Combine :: R.C.C. Work (AR0410b)					
BRM094 : Non-sal bullahs 125mm. mean dia of any length.	1.17	1Mtr.	41.81	48.9177	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.04806	1Cum.	58374.79	2805.4924074	0
LR008 : Sangi mulia	4.95	Per day	512	2534.4	0
LR027 : Carpenter	4.95	Per day	562	2781.9	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	42.622	148.0389926	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	341.11	153.4995	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	536.41	193.1076	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	536.41	289.6614	0
BRM094 : Non-sal bullahs 125mm. mean dia of any length.	0.01494	1Mtr.	198.296	2.96254224	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.04806	1Cum.	198.296	9.53010576	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	69	31.05	0

BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	189	68.04	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	189	102.06	0
BRM094 : Non-sal bullahs 125mm. mean dia of any length.	0.01494	1Mtr.	0	0	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.04806	1Cum.	0	0	0

Total Amount (a+b+c)	13416.284848
Total GST (a)	338.855148
OVERHEAD CHARGES @ 7.5% (+)	1031.6354997
CONTRACTOR PROFIT @ 7.5% (+)	1109.0081621775
LABOUR CESS @ 1% (+)	158.95783657878
Grand Total	16054.741494456
Say For Unit 1 (Grand Total/1)	16054.741494456

Item 24

Concrete (AR0307): Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.

Sub-Item of Work

Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	3.2	Per day	462	1478.4	0
LR025 : Mason	0.68	Per day	562	382.16	0
BRM340 : Cement	3.23	1 Qntl.	542	1750.66	315.1188
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	1396.62	1256.958	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	42.622	137.66906	0

BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	341.11	153.4995	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	536.41	482.769	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	69	31.05	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	189	170.1	0

Total Amount (a+b+c)	6524.66156
Total GST (a)	315.1188
OVERHEAD CHARGES @ 7.5% (+)	512.983527
CONTRACTOR PROFIT @ 7.5% (+)	551.457291525
LABOUR CESS @ 1% (+)	79.04221178525
Grand Total	7983.2633903103
Say For Unit 1 (Grand Total/1)	7983.2633903103

Khiraabdi Tanaya Padhy
JE
Rairakhol Block

Supriya Biswal
AEE
Rairakhol Block

Rajendra Senapati
BDO
Rairakhol Block