

Analysis

**OD/346/3304/116204/393632/00105131 : Const. of CRC near RD road of village Dhaligadia
Block : Khaira, Gram Panchayat : Bartana
Created By:Narayan Sahu**

Item 1

R.C.C. Work (AR0409): Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.

Sub-Item of Work

Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR001 : Male mulia	8	Per day	462	3696	0
LR046 : Blacksmith	3	Per day	612	1836	0
LR010 : Mate	0.44	Per day	512	225.28	0
BRM162 : Binding Wire.	8	1 Kg.	90	720	0
BRM341 : Steel	10.5	1 Qntl.	6354.22	66719.31	12009.4758

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	10.5	1 Qntl.	24.787	260.2635	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	10.5	1 Qntl.	0	0	0

Total Amount (a+b+c)	73456.8535
Total GST (a)	12009.4758
OVERHEAD CHARGES @ 7.5% (+)	6409.9746975
CONTRACTOR PROFIT @ 7.5% (+)	6890.7227998125
LABOUR CESS @ 1% (+)	987.67026797312
Grand Total	99754.697065286
Say For Unit 1 (Grand Total/10)	9975.4697065286

Item 2

Pile Foundation (AR1501bc): Single under reamed pile foundation 300 mm dia and 4.0 metre long with RCC M-20 using 12mm size black hard granite (Crusher broken) stone chips including cost of boring but excluding cost of M.S./Tor steel and labour charges for cutting, bending and binding of steel including cost, convenience, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. (300mm dia and 4.0 meter long)

Sub-Item of Work

Single under reamed pile foundation 300 mm dia and 4.0 metre long with RCC M20 using 12mm size black hard granite (Crusher broken) stone chips

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM178 : Bentonite powder	0.825	1Qntl	337.87	278.74275	0
BRM342 : Tripod	0.33	Per day	450	148.5	0
LR063 : Winch operator	0.33	Per day	612	201.96	0
LR062 : Boring Mistry	1.32	Per day	612	807.84	0
PM096 : Generator 33KVA Generation of Electric Energy 50KVA	0.158	per hour	700	110.6	0
PM083 : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.158	per hour	229.55	36.2689	0
LR001 : Male mulia	0.526	Per day	462	243.012	0
LR025 : Mason	0.04	Per day	562	22.48	0
LR010 : Mate	0.023	Per day	512	11.776	0
BRM340 : Cement	1.5	1 Qntl.	545.68	818.52	147.3336
BRM028 : Screened and washed sharp sand for mortar	0.178	1 Cum	76.88	13.68464	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.356	1 Cum.	1396.62	497.19672	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	1.5	1 Qntl.	24.787	37.1805	0
BRM028 : Screened and washed sharp sand for mortar	0.178	1 Cum	917.11	163.24558	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.356	1 Cum.	757.75	269.759	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	1.5	1 Qntl.	0	0	0

BRM028 : Screened and washed sharp sand for mortar	0.178	1 Cum	442.25	78.7205	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.356	1 Cum.	1125.5	400.678	0

Total Amount (a+b+c)	4140.16459
Total GST (a)	147.3336
OVERHEAD CHARGES @ 7.5% (+)	321.56236425
CONTRACTOR PROFIT @ 7.5% (+)	345.67954156875
LABOUR CESS @ 1% (+)	49.547400958188
Grand Total	5004.2874967769
Say For Unit 1 (Grand Total/1)	5004.2874967769

Item 3

R.C.C. Work (AR0404A): Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge. (excluding centring and shuttering)

Sub-Item of Work

Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
PM096 : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0
PM083 : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0
LR001 : Male mulia	1.3333	Per day	462	615.9846	0
LR025 : Mason	0.1	Per day	562	56.2	0
LR010 : Mate	0.0573	Per day	512	29.3376	0
BRM340 : Cement	3.4733	1 Qntl.	545.68	1895.310344	341.15586192
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1418.67	510.7212	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1382.29	746.4366	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	24.787	86.0926871	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	917.11	412.6995	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	757.75	272.79	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	757.75	409.185	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	442.25	199.0125	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1125.5	405.18	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1124.5	607.23	0

Total Amount (a+b+c)	6652.5960311
Total GST (a)	341.15586192
OVERHEAD CHARGES @ 7.5% (+)	524.5313919765
CONTRACTOR PROFIT @ 7.5% (+)	563.87124637474
LABOUR CESS @ 1% (+)	80.821545313712
Grand Total	8162.976076685
Say For Unit 1 (Grand Total/1)	8162.976076685

Item 4

R.C.C. Work (AR0410c): Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc

Sub-Item of Work

R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	58374.79	1558.606893	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	1.26	1Mtr.	30.81	38.8206	0

LR008 : Sangi mulia	0.5	Per day	512	256	0
LR027 : Carpenter	0.5	Per day	562	281	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	198.296	5.2945032	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	198.296	1.21753744	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	0	0	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	0	0	0

Total Amount (a+b+c)	2140.93953364
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	160.570465023
CONTRACTOR PROFIT @ 7.5% (+)	172.61324989972
LABOUR CESS @ 1% (+)	24.741232485627
Grand Total	2498.8644810484
Say For Unit 1 (Grand Total/10)	249.88644810484

Item 5

R.C.C. Work (AR0410d): Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. beams, column, grider and bressmer, etc. Data for 4.2sqm

Sub-Item of Work

Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	2.32	1Mtr	51.87	120.3384	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0218	1Cum.	58374.79	1272.570422	0
LR008 : Sangi mulia	2.75	Per day	512	1408	0
LR027 : Carpenter	2.75	Per day	562	1545.5	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
------------	----------	------	------	--------	-----

BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.0238	1Mtr	198.296	4.7194448	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0218	1Cum.	198.296	4.3228528	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.0238	1Mtr	0	0	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0218	1Cum.	0	0	0

Total Amount (a+b+c)	4355.4511196
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	326.65883397
CONTRACTOR PROFIT @ 7.5% (+)	351.15824651775
LABOUR CESS @ 1% (+)	50.332682000878
Grand Total	5083.6008820886
Say For Unit 1 (Grand Total/4.2)	1210.3811624021

Item 6

R.C.C. Work (AR0410e): Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. Lintels Data for 7.8 sqm

Sub-Item of Work

Rigid and smooth centering and shuttering for R.C.C. works including false works and dismantling them after casting

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM094 : Non-sal bullahs 125mm. mean dia of any length.	2.1	1Mtr.	41.81	87.801	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0413	1Cum.	58374.79	2410.878827	0
LR008 : Sangi mulia	1.25	Per day	512	640	0
LR027 : Carpenter	1.25	Per day	562	702.5	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM094 : Non-sal bullahs 125mm. mean dia of any length.	0.0276	1Mtr.	198.296	5.4729696	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0413	1Cum.	198.296	8.1896248	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM094 : Non-sal bullahs 125mm. mean dia of any length.	0.0276	1Mtr.	0	0	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0413	1Cum.	0	0	0

Total Amount (a+b+c)	3854.8424214
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	289.113181605
CONTRACTOR PROFIT @ 7.5% (+)	310.79667022538
LABOUR CESS @ 1% (+)	44.547522732304
Grand Total	4499.2997959627
Say For Unit 1 (Grand Total/7.8)	576.8333071747

Item 7

R.C.C. Work (AR0410a): Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas up to 4.3m height

Sub-Item of Work

Centring & Shuttering for R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	5.6	1Mtr	51.87	290.472	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0452	1Cum.	58374.79	2638.540508	0
LR008 : Sangi mulia	2.75	Per day	512	1408	0
LR027 : Carpenter	2.75	Per day	562	1545.5	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.069	1Mtr	198.296	13.682424	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0452	1Cum.	198.296	8.9629792	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.069	1Mtr	0	0	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0452	1Cum.	0	0	0

Total Amount (a+b+c)	5905.1579112
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	442.88684334
CONTRACTOR PROFIT @ 7.5% (+)	476.1033565905
LABOUR CESS @ 1% (+)	68.241481111305
Grand Total	6892.3895922418

Say For Unit 1 (Grand Total/9)	765.82106580465
--------------------------------	-----------------

Item 8

Earth Work (AR0115): Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

Filling foundation and plinth with sand well watered and rammed

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	71.94	7194	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	917.11	91711	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	442.25	44225	0

Total Amount (a+b+c)	148840.32
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	11163.024
CONTRACTOR PROFIT @ 7.5% (+)	12000.2508
LABOUR CESS @ 1% (+)	1720.035948
Grand Total	173723.630748
Say For Unit 1 (Grand Total/100)	1737.23630748

Item 9

Concrete (AR0303): Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR025 : Mason	0.18	Per day	562	101.16	0
LR002 : Female mulia	1.4	Per day	462	646.8	0

LR001 : Male mulia	2.5	Per day	462	1155	0
BRM340 : Cement	2.29	1 Qntl.	545.68	1249.6072	224.929296
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	76.88	36.9024	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	995.25	955.44	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	24.787	56.76223	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	917.11	440.2128	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	757.75	727.44	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	442.25	212.28	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	1125.5	1080.48	0

Total Amount (a+b+c)	6662.08463
Total GST (a)	224.929296
OVERHEAD CHARGES @ 7.5% (+)	516.52604445
CONTRACTOR PROFIT @ 7.5% (+)	555.26549778375
LABOUR CESS @ 1% (+)	79.588054682337
Grand Total	8038.3935229161
Say For Unit 1 (Grand Total/1)	8038.3935229161

Item 10

Concrete (AR0307): Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.

Sub-Item of Work

Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	3.2	Per day	462	1478.4	0
LR025 : Mason	0.68	Per day	562	382.16	0
BRM340 : Cement	3.23	1 Qntl.	545.68	1762.5464	317.258352

BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	1396.62	1256.958	0

b) Carriage Rate Details						
Particular	Quantity	Unit	Rate	Amount	GST	
BRM340 : Cement	3.23	1 Qntl.	24.787	80.06201	0	
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	917.11	412.6995	0	
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	757.75	681.975	0	

c) Royalty Rate Details						
Particular	Quantity	Unit	Rate	Amount	GST	
BRM340 : Cement	3.23	1 Qntl.	0	0	0	
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	442.25	199.0125	0	
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	1125.5	1012.95	0	

Total Amount (a+b+c)	7948.15941
Total GST (a)	317.258352
OVERHEAD CHARGES @ 7.5% (+)	619.90633215
CONTRACTOR PROFIT @ 7.5% (+)	666.39930706125
LABOUR CESS @ 1% (+)	95.517234012112
Grand Total	9647.2406352234
Say For Unit 1 (Grand Total/1)	9647.2406352234

Item 11
Masonry Brick Work (AR0603c): Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth having crushing strength not less than 75.00 Kg/cm ² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.
Sub-Item of Work Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in foundation and plinth

a) Specific Rate Details						
Particular	Quantity	Unit	Rate	Amount	GST	
LR002 : Female mulia	0.14	Per day	462	64.68	0	

BRM006 : Fly ash bricks of 23 Cm. x 11 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	400	1000 Nos	4.55488	1821.952	0
LR001 : Male mulia	2.82	Per day	462	1302.84	0
LR025 : Mason	1.05	Per day	562	590.1	0
LR044 : Mason	0.35	Per day	612	214.2	0
BRM340 : Cement	0.672	1 Qntl.	545.68	366.69696	66.0054528
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	76.88	21.5264	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM006 : Fly ash bricks of 23 Cm. x 11 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	400	1000 Nos	1.63384	653.536	0
BRM340 : Cement	0.672	1 Qntl.	24.787	16.656864	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	917.11	256.7908	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM006 : Fly ash bricks of 23 Cm. x 11 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance $\pm 2\%$	400	1000 Nos	0	0	0
BRM340 : Cement	0.672	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	442.25	123.83	0

Total Amount (a+b+c)	5432.809024
Total GST (a)	66.0054528
OVERHEAD CHARGES @ 7.5% (+)	412.41108576
CONTRACTOR PROFIT @ 7.5% (+)	443.341917192
LABOUR CESS @ 1% (+)	63.54567479752
Grand Total	6418.1131545495
Say For Unit 1 (Grand Total/1)	6418.1131545495

Item 12

Flooring (AR0817aa): Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3) jointed with neat cement slurry mixed with pigments to match the shade of the Vitrified tiles including rubbing and polishing complete including cost of precast tiles.

Sub-Item of Work

Fixing Vitrified tiles of premium grade having thickness 8mm to 10mm confirming to IS 13756 of size 600mmx600mm plain (Ivory) in dados skirting and risers of steps on 12mm thick cement plaster (1:3)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	651.08	6510.8	0
BRMMR0027 : Wax Polish	10	1 Sqm	8.5	85	0
LR044 : Mason	3.25	Per day	612	1989	0
LR001 : Male mulia	3.25	Per day	462	1501.5	0
LR008 : Sangi mulia	7.6	Per day	512	3891.2	0
BRM340 : Cement	1.375	1 Qntl.	545.68	750.31	135.0558
BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	76.88	11.532	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	9.60111111	96.0111111	0
BRM340 : Cement	1.375	1 Qntl.	24.787	34.082125	0
BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	917.11	137.5665	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM131 : Tiles up to Polished Vitrified floor tiles of premium grade having thickness 8 mm to 10mm confirming to IS 15622:2006 (Group-B la) of sizes Vitrified Tile 600mmx600mm Plain (Ivory)	10	1 Sqm.	0	0	0
BRM340 : Cement	1.375	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.15	1 Cum	442.25	66.3375	0

Total Amount (a+b+c)	15073.339236
Total GST (a)	135.0558
OVERHEAD CHARGES @ 7.5% (+)	1140.6296277
CONTRACTOR PROFIT @ 7.5% (+)	1226.1768497775
LABOUR CESS @ 1% (+)	175.75201513477
Grand Total	17750.953528612
Say For Unit 1 (Grand Total/10)	1775.0953528612

Item 13

Flooring (AR0816): Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor , treads or steps and landing on a 25mm thick bed of cement mortar 1:1 (1cement: 1sand) jointed with neat cement slurry mixed with pigment to match the shades of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.

Sub-Item of Work

Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRMMR0027 : Wax Polish	10	1 Sqm	8.5	85	0
BRM130 : Tiles up to 30cm x 30cm / 40cm x 40cm special plain / printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755	10	1 Sqm.	450.08	4500.8	0
LR001 : Male mulia	2.16	Per day	462	997.92	0
LR044 : Mason	2.16	Per day	612	1321.92	0
LR008 : Sangi mulia	5.5	Per day	512	2816	0
BRM340 : Cement	2.737	1 Qntl.	545.68	1493.52616	268.8347088
BRM028 : Screened and washed sharp sand for mortar	0.13	1 Cum	76.88	9.9944	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM130 : Tiles up to 30cm x 30cm / 40cm x 40cm special plain / printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755	10	1 Sqm.	9.6011111	96.011111	0
BRM340 : Cement	2.737	1 Qntl.	24.787	67.842019	0
BRM028 : Screened and washed sharp sand for mortar	0.13	1 Cum	917.11	119.2243	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM130 : Tiles up to 30cm x 30cm / 40cm x 40cm special plain / printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755	10	1 Sqm.	0	0	0
BRM340 : Cement	2.737	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.13	1 Cum	442.25	57.4925	0

Total Amount (a+b+c)

11565.73049

Total GST (a)	268.8347088
OVERHEAD CHARGES @ 7.5% (+)	887.59238991
CONTRACTOR PROFIT @ 7.5% (+)	954.16181915325
LABOUR CESS @ 1% (+)	136.76319407863
Grand Total	13813.082601942
Say For Unit 1 (Grand Total/10)	1381.3082601942

Item 14

Flooring (AR0820): 2.5 cm. Damp proof course with C.C. (1:2:4) using 12mm. Size hard broken(crusher broken) granite Chips including curing for seven days with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

2.5 cm. Damp proof course with C.C. (1:2:4) using 12mm. Size hard broken(crusher broken) granite Chips

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR001 : Male mulia	0.36	Per day	462	166.32	0
LR044 : Mason	0.103	Per day	612	63.036	0
BRM340 : Cement	0.0754	1 Qntl.	545.68	41.144272	7.40596896
BRM028 : Screened and washed sharp sand for mortar	0.012	1 Cum	76.88	0.92256	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.023	1 Cum.	1396.62	32.12226	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0754	1 Qntl.	24.787	1.8689398	0
BRM028 : Screened and washed sharp sand for mortar	0.012	1 Cum	917.11	11.00532	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.023	1 Cum.	757.75	17.42825	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0754	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.012	1 Cum	442.25	5.307	0

BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.023	1 Cum.	1125.5	25.8865	0
--	-------	-----------	--------	---------	---

Total Amount (a+b+c)	365.0411018
Total GST (a)	7.40596896
OVERHEAD CHARGES @ 7.5% (+)	27.933530307
CONTRACTOR PROFIT @ 7.5% (+)	30.028545080025
LABOUR CESS @ 1% (+)	4.3040914614703
Grand Total	434.7132376085
Say For Unit 1 (Grand Total/1)	434.7132376085

Item 15

Iron Work (AR1704): Supplying, fitting & fixing of Mild steel and put up for frames & shutters of Doors and windows fixing in position with cost, conveyance, taxes of all materials, labours and T & P required for the work etc. as per direction of Engineer-in-charge.

Sub-Item of Work
Iron Doors and windows fixing

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	0.508	1 Qntl.	6354.22	3227.94376	581.0298768
LR001 : Male mulia	3.25	Per day	462	1501.5	0
LR011 : Helper to carpenter or Blacksmith/ Painter/ Blaster/Plumber/ Electrician/ Fitter/Welder	1	Per day	512	512	0
LR028 : Fitter	1	Per day	562	562	0
LR047 : Fitter	1	Per day	612	612	0
LR026 : Black smith	1	Per day	562	562	0
LR046 : Blacksmith	0.75	Per day	612	459	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	0.508	1 Qntl.	24.787	12.591796	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	0.508	1 Qntl.	0	0	0

Total Amount (a+b+c)	7449.035556
-----------------------------	-------------

Total GST (a)	581.0298768
OVERHEAD CHARGES @ 7.5% (+)	602.25490746
CONTRACTOR PROFIT @ 7.5% (+)	647.4240255195
LABOUR CESS @ 1% (+)	92.797443657795
Grand Total	9372.5418094373
Say For Unit 1 (Grand Total/0.508)	18449.885451648

Item 16

Plastering (AR1004i): 12mm thick cement plaster (1:6) over Brick work in outside including racking out joints finishing smooth with proper plumb and line curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc. comp.and as per direction of Engineer-in-charge.

Sub-Item of Work

12mm thick cement plaster (1:6) over Brick work in outside.

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.05	Per day	462	23.1	0
LR001 : Male mulia	0.07	Per day	462	32.34	0
LR025 : Mason	0.14	Per day	562	78.68	0
BRM340 : Cement	0.0358	1 Qntl.	545.68	19.535344	3.51636192
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	76.88	1.1532	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0358	1 Qntl.	24.787	0.8873746	0
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	917.11	13.75665	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0358	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.015	1 Cum	442.25	6.63375	0

Total Amount (a+b+c)	176.0863186
Total GST (a)	3.51636192
OVERHEAD CHARGES @ 7.5% (+)	13.470201039
CONTRACTOR PROFIT @ 7.5% (+)	14.480466116925
LABOUR CESS @ 1% (+)	2.0755334767592
Grand Total	209.62888115268
Say For Unit 1 (Grand Total/1)	209.62888115268

Item 17

Plastering (AR1014): 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.

Sub-Item of Work

16mm thick cement Plaster in CM (1:6) over brick work in inside.

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.11	Per day	462	50.82	0
LR001 : Male mulia	0.13	Per day	462	60.06	0
LR025 : Mason	0.16	Per day	562	89.92	0
BRM340 : Cement	0.043	1 Qntl.	545.68	23.46424	4.2235632
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	76.88	1.38384	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.043	1 Qntl.	24.787	1.065841	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	917.11	16.50798	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.043	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	442.25	7.9605	0

Total Amount (a+b+c)

251.182401

Total GST (a)

4.2235632

OVERHEAD CHARGES @ 7.5% (+)

19.155447315

CONTRACTOR PROFIT @ 7.5% (+)

20.592105863625

LABOUR CESS @ 1% (+)

2.9515351737863

Grand Total

298.10505255241

Say For Unit 1 (Grand Total/1)

298.10505255241

Item 18

Painting (AR0901d): Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.

Sub-Item of Work

Priming one coat with inner surface primer of approved quality water-bound primer over plastering surfaces (Inner surface)

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM253 : Wall cement primer (I.S.I.) Water bound	0.7812	1 Ltr	159.03	124.234236	0
LR048 : Painter/ Polisher	0.5	Per day	612	306	0
LR001 : Male mulia	0.5	Per day	462	231	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM253 : Wall cement primer (I.S.I.) Water bound	0.7812	1 Ltr	0.24787	0.193636044	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM253 : Wall cement primer (I.S.I.) Water bound	0.7812	1 Ltr	0	0	0

Total Amount (a+b+c)	661.427872044				
Total GST (a)	0				
OVERHEAD CHARGES @ 7.5% (+)	49.6070904033				
CONTRACTOR PROFIT @ 7.5% (+)	53.327622183548				
LABOUR CESS @ 1% (+)	7.6436258463085				
Grand Total	772.00621047716				
Say For Unit 1 (Grand Total/9.3)	83.011420481415				

Item 19
Painting (AR0920): Finishing wall two coats with plastic emulsion paint of approved shades on new work to give an even shade including all costs of labor, Paint and Brushes required for the work, etc. complete and as per direction of the Engineer-in-charge.(Inside)
Sub-Item of Work Finishing wall two coats with plastic emulsion paint of approved shades on new work (Inside)

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM140 : Plastic Emulsion paint	1.25	1 Litre	249.34	311.675	0
LR048 : Painter/ Polisher	0.54	Per day	612	330.48	0
LR001 : Male mulia	0.64	Per day	462	295.68	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM140 : Plastic Emulsion paint	1.25	1 Litre	0.24787	0.3098375	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST

BRM140 : Plastic Emulsion paint	1.25	1 Litre	0	0	0
Total Amount (a+b+c)	938.1448375				
Total GST (a)	0				
OVERHEAD CHARGES @ 7.5% (+)	70.3608628125				
CONTRACTOR PROFIT @ 7.5% (+)	75.637927523437				
LABOUR CESS @ 1% (+)	10.841436278359				
Grand Total	1094.9850641143				
Say For Unit 1 (Grand Total/10)	109.49850641143				

Shradhananda Panigrahi
JE
Khaira Block

Bibhuti Bhusan Nayak
AEE
Khaira Block

Narayan Sahu
BDO
Khaira Block