

Analysis

OD/354/3369/117689/412131/00107807 : CONSTRUCTION OF GUNDICHA RURAL PARK AT VILLAGE TANGANAPALLI

Block : Chatrapur, Gram Panchayat : Tangonapalli

Created By:Sri Sambit Sangramjeet Sahoo

Item 1

Earth Work (AR0102aa): Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge

Sub-Item of Work

Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	25.8	Per day	462	11919.6	0
LR001 : Male mulia	25.8	Per day	462	11919.6	0

Total Amount (a+b+c)

23839.2

Total GST (a)

0

OVERHEAD CHARGES @ 7.5% (+)

1787.94

CONTRACTOR PROFIT @ 7.5% (+)

1922.0355

LABOUR CESS @ 1% (+)

275.491755

Grand Total

27824.667255

Say For Unit 1 (Grand Total/100)

278.24667255

Item 2

Earth Work (AR0115): Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

Filling foundation and plinth with sand well watered and rammed

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	62.86	6286	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	536.41	53641	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	110.25	11025	0

Total Amount (a+b+c)	76662.32				
Total GST (a)	0				
OVERHEAD CHARGES @ 7.5% (+)	5749.674				
CONTRACTOR PROFIT @ 7.5% (+)	6180.89955				
LABOUR CESS @ 1% (+)	885.9289355				
Grand Total	89478.8224855				
Say For Unit 1 (Grand Total/100)	894.788224855				

Item 3
Concrete (AR0303): Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR025 : Mason	0.18	Per day	562	101.16	0
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	2.5	Per day	462	1155	0
BRM340 : Cement	2.29	1 Qntl.	560.45	1283.4305	231.01749
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	66.23	31.7904	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	995.25	955.44	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	30.732	70.37628	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	536.41	257.4768	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	471.31	452.4576	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	110.25	52.92	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	409.5	393.12	0

Total Amount (a+b+c)	5399.97158
Total GST (a)	231.01749
OVERHEAD CHARGES @ 7.5% (+)	422.32418025
CONTRACTOR PROFIT @ 7.5% (+)	453.99849376875
LABOUR CESS @ 1% (+)	65.073117440188
Grand Total	6572.3848614589
Say For Unit 1 (Grand Total/1)	6572.3848614589

Item 4

Masonry Stone Work (AR0703): Random rubble H.G. stone of size not less than 0.0025 cum stacked masonry in cement mortar (1:6) in foundation and plinth including watering, curing for seven days with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

Random rubble H.G. stone of masonry.

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.41	Per day	462	651.42	0
LR001 : Male mulia	1.76	Per day	462	813.12	0
LR025 : Mason	1.41	Per day	562	792.42	0
LR044 : Mason	0.35	Per day	612	214.2	0
BRM340 : Cement	0.8151	1 Qntl.	560.45	456.822795	82.2281031
BRM028 : Screened and washed sharp sand for mortar	0.34	1 Cum	66.23	22.5182	0
BRM034 : Granite broken stone of size not less than 0.0025 Cum. Stacked	1	1 Cum.	289.28	289.28	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.8151	1 Qntl.	30.732	25.0496532	0
BRM028 : Screened and washed sharp sand for mortar	0.34	1 Cum	536.41	182.3794	0
BRM034 : Granite broken stone of size not less than 0.0025 Cum. Stacked	1	1 Cum.	471.31	471.31	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.8151	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.34	1 Cum	110.25	37.485	0
BRM034 : Granite broken stone of size not less than 0.0025 Cum. Stacked	1	1 Cum.	409.5	409.5	0

Total Amount (a+b+c)	4365.5050482
Total GST (a)	82.2281031
OVERHEAD CHARGES @ 7.5% (+)	333.5799863475
CONTRACTOR PROFIT @ 7.5% (+)	358.59848532356
LABOUR CESS @ 1% (+)	51.399116229711
Grand Total	5191.3107392008
Say For Unit 1 (Grand Total/1)	5191.3107392008

Item 5

R.C.C. Work (AR0404Ab): Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC Plinth band)

Sub-Item of Work

Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
Combine :: R.C.C. Work (AR0404A)					
PM096 : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0
PM083 : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0
LR001 : Male mulia	1.3333	Per day	462	615.9846	0
LR025 : Mason	0.1	Per day	562	56.2	0
LR010 : Mate	0.0573	Per day	512	29.3376	0
BRM340 : Cement	3.4733	1 Qntl.	560.45	1946.610985	350.3899773
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	66.23	29.8035	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1407.77	506.7972	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1382.29	746.4366	0
Combine :: R.C.C. Work (AR0410c)					
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.01335	1Cum.	58374.79	779.3034465	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.63	1Mtr.	30.81	19.4103	0
LR008 : Sangi mulia	0.25	Per day	512	128	0

LR027 : Carpenter	0.25	Per day	562	140.5	0
-------------------	------	---------	-----	-------	---

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	30.732	106.7414556	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	536.41	241.3845	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	471.31	169.6716	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	471.31	254.5074	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.01335	1Cum.	198.296	2.6472516	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00307	1Mtr.	198.296	0.60876872	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	110.25	49.6125	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	409.5	147.42	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	409.5	221.13	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.01335	1Cum.	0	0	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00307	1Mtr.	0	0	0

Total Amount (a+b+c)	6563.92770742
Total GST (a)	350.3899773
OVERHEAD CHARGES @ 7.5% (+)	518.573826354
CONTRACTOR PROFIT @ 7.5% (+)	557.46686333055
LABOUR CESS @ 1% (+)	79.903583744046
Grand Total	8070.2619581486
Say For Unit 1 (Grand Total/1)	8070.2619581486

Item 6

R.C.C. Work (AR0409): Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.

Sub-Item of Work

Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR001 : Male mulia	8	Per day	462	3696	0
LR046 : Blacksmith	3	Per day	612	1836	0
LR010 : Mate	0.44	Per day	512	225.28	0
BRM162 : Binding Wire.	8	1 Kg.	90.1	720.8	0
BRM341 : Steel	10.5	1 Qntl.	6374.61	66933.405	12048.0129

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	10.5	1 Qntl.	30.732	322.686	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	10.5	1 Qntl.	0	0	0

Total Amount (a+b+c)

73734.171

Total GST (a)

12048.0129

OVERHEAD CHARGES @ 7.5% (+)

6433.6637925

CONTRACTOR PROFIT @ 7.5% (+)

6916.1885769375

LABOUR CESS @ 1% (+)

991.32036269437

Grand Total

100123.35663213

Say For Unit 1 (Grand Total/10)

10012.335663213

Item 7

Masonry Brick Work (AR0603ci): Brickwork with Flyash Bricks of size (23cm x 11cm x 8cm) in cement mortar (1:6) in superstructure having crushing strength not less than 75.00 Kg/cm² with dimensional tolerance ± 8 percent immersing the bricks in water not less than six hours with cost conveyance, royalty, taxes of all materials, labor, and T&P required for the work, etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work

Flyash Bricks of size (25cm x 12cm x 8cm) in cement mortar (1:6) in superstructure

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.14	Per day	462	64.68	0
BRMMR0025 : SCAFFOLDING CHARGES FOR BRICK MASONRY WORK	1	1 Cum	33	33	0

BRM006 : Fly ash bricks of 23 Cm. x 11 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance \pm 2 %	400	1000 Nos	4.55488	1821.952	0
LR001 : Male mulia	2.82	Per day	462	1302.84	0
LR025 : Mason	1.05	Per day	562	590.1	0
LR044 : Mason	0.35	Per day	612	214.2	0
BRM340 : Cement	0.672	1 Qntl.	560.45	376.6224	67.792032
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	66.23	18.5444	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM006 : Fly ash bricks of 23 Cm. x 11 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance \pm 2 %	400	1000 Nos	0.8091	323.64	0
BRM340 : Cement	0.672	1 Qntl.	30.732	20.651904	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	536.41	150.1948	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM006 : Fly ash bricks of 23 Cm. x 11 Cm. x 8 Cm. size having crushing strength not less than 75 Kg./Cm2 with dimensional tolerance \pm 2 %	400	1000 Nos	0	0	0
BRM340 : Cement	0.672	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.28	1 Cum	110.25	30.87	0

Total Amount (a+b+c)	4947.295504
Total GST (a)	67.792032
OVERHEAD CHARGES @ 7.5% (+)	376.1315652
CONTRACTOR PROFIT @ 7.5% (+)	404.34143259
LABOUR CESS @ 1% (+)	57.9556053379
Grand Total	5853.5161391279
Say For Unit 1 (Grand Total/1)	5853.5161391279

Item 8

Plastering (AR1014): 16mm thick cement Plaster in CM (1:6) over brick work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.

Sub-Item of Work

16mm thick cement Plaster in CM (1:6) over brick work in inside.

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
------------	----------	------	------	--------	-----

LR002 : Female mulia	0.11	Per day	462	50.82	0
LR001 : Male mulia	0.13	Per day	462	60.06	0
LR025 : Mason	0.16	Per day	562	89.92	0
BRM340 : Cement	0.043	1 Qntl.	560.45	24.09935	4.337883
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	66.23	1.19214	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.043	1 Qntl.	30.732	1.321476	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	536.41	9.65538	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.043	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.018	1 Cum	110.25	1.9845	0

Total Amount (a+b+c)	239.052846
Total GST (a)	4.337883
OVERHEAD CHARGES @ 7.5% (+)	18.254304675
CONTRACTOR PROFIT @ 7.5% (+)	19.623377525625
LABOUR CESS @ 1% (+)	2.8126841120063
Grand Total	284.08109531263
Say For Unit 1 (Grand Total/1)	284.08109531263

Item 9

Plastering (AR1008): 20mm thick cement Plaster in CM (1:6) for stone work in inside including racking out joints finishing smooth with proper plumb and line, curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T & P required for the work etc comp.and as per direction of Engineer-in-charge.

Sub-Item of Work

20mm thick cement Plaster in CM (1:6) over brick work in inside.

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	0.11	Per day	462	50.82	0
LR001 : Male mulia	0.13	Per day	462	60.06	0
LR025 : Mason	0.16	Per day	562	89.92	0
BRM340 : Cement	0.057	1 Qntl.	560.45	31.94565	5.750217
BRM028 : Screened and washed sharp sand for mortar	0.021	1 Cum	66.23	1.39083	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.057	1 Qntl.	30.732	1.751724	0
BRM028 : Screened and washed sharp sand for mortar	0.021	1 Cum	536.41	11.26461	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.057	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.021	1 Cum	110.25	2.31525	0

Total Amount (a+b+c)	249.468064				
Total GST (a)	5.750217				
OVERHEAD CHARGES @ 7.5% (+)	19.141371075				
CONTRACTOR PROFIT @ 7.5% (+)	20.576973905625				
LABOUR CESS @ 1% (+)	2.9493662598062				
Grand Total	297.88599224043				
Say For Unit 1 (Grand Total/1)	297.88599224043				

Item 10

Painting (AR0901c): Priming one coat with inner surface primer of approved quality oil-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.

Sub-Item of Work

Priming one coat with inner surface primer of approved quality oil-bound primer over plastering surfaces (Inner surface)

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM252 : Wall cement primer (I.S.I.) Oil bound	0.7812	1 Ltr	125.5	98.0406	0
LR048 : Painter/ Polisher	0.5	Per day	612	306	0
LR001 : Male mulia	0.5	Per day	462	231	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM252 : Wall cement primer (I.S.I.) Oil bound	0.7812	1 Ltr	0.30732	0.240078384	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM252 : Wall cement primer (I.S.I.) Oil bound	0.7812	1 Ltr	0	0	0

Total Amount (a+b+c)	635.280678384				
Total GST (a)	0				
OVERHEAD CHARGES @ 7.5% (+)	47.6460508788				

CONTRACTOR PROFIT @ 7.5% (+)	51.21950469471
LABOUR CESS @ 1% (+)	7.3414623395751
Grand Total	741.48769629709
Say For Unit 1 (Grand Total/9.3)	79.729859816891

Item 11

Painting (AR0918Ai): Finishing wall one coat with weather coat including all costs of labour, Paint, Primer and Brushes required for the work etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work

Finishing wall one coat with weather coat

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	0.75	1 Ltr	194.79	146.0925	0
LR001 : Male mulia	0.43	Per day	462	198.66	0
LR048 : Painter/ Polisher	0.36	Per day	612	220.32	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	0.75	1 Ltr	0.30732	0.23049	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	0.75	1 Ltr	0	0	0

Total Amount (a+b+c)	565.30299
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	42.39772425
CONTRACTOR PROFIT @ 7.5% (+)	45.57755356875
LABOUR CESS @ 1% (+)	6.5327826781875
Grand Total	659.81105049694
Say For Unit 1 (Grand Total/10)	65.981105049694

Item 12

Flooring (AR0816): Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor , treads or steps and landing on a 25mm thick bed of cement mortar 1:1 (1cement: 1sand) jointed with neat cement slurry mixed with pigment to match the shades of the ceramic tiles including rubbing and polishing, cost of precast tiles complete as per direction of Engineer-in-charge.

Sub-Item of Work

Fixing ceramic Tiles (30cmx30cm / 40cmx40cm special plain/printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755) in floor

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRMMR0027 : Wax Polish	10	1 Sqm	8.5	85	0
BRM130 : Tiles up to 30cm x 30cm / 40cm x 40cm special plain / printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755	10	1 Sqm.	450.08	4500.8	0
LR001 : Male mulia	2.16	Per day	462	997.92	0
LR044 : Mason	2.16	Per day	612	1321.92	0
LR008 : Sangi mulia	5.5	Per day	512	2816	0
BRM340 : Cement	2.737	1 Qntl.	560.45	1533.95165	276.111297
BRM028 : Screened and washed sharp sand for mortar	0.13	1 Cum	66.23	8.6099	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM130 : Tiles up to 30cm x 30cm / 40cm x 40cm special plain / printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755	10	1 Sqm.	11.2375001	112.375001	0
BRM340 : Cement	2.737	1 Qntl.	30.732	84.113484	0
BRM028 : Screened and washed sharp sand for mortar	0.13	1 Cum	536.41	69.7333	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM130 : Tiles up to 30cm x 30cm / 40cm x 40cm special plain / printed series ceramic floor tiles of premium grade having thickness 7mm to 8mm confirming to IS 13755	10	1 Sqm.	0	0	0
BRM340 : Cement	2.737	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.13	1 Cum	110.25	14.3325	0

Total Amount (a+b+c)	11544.755835
Total GST (a)	276.111297
OVERHEAD CHARGES @ 7.5% (+)	886.5650349
CONTRACTOR PROFIT @ 7.5% (+)	953.0574125175
LABOUR CESS @ 1% (+)	136.60489579418
Grand Total	13797.094475212
Say For Unit 1 (Grand Total/10)	1379.7094475212

JAYASENA BEHERA
JE
Chatrapur Block

LAGNAJEET SAHOO
AEE
Chatrapur Block

Sri Sambit Sangramjeet Sahoo
BDO
Chatrapur Block