

Analysis

OD/366/3517/120488/427837/00107143 : CONSTRUCTION OF BALICHAMUNDA CULTURAL CENTRE AT BADAMOSIGAN
Block : Nabarangpur, Gram Panchayat : Badamosigam
Created By:SUNIL KHORA

Item 1

Earth Work (AR0102aa): Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge

Sub-Item of Work

Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	25.8	Per day	462	11919.6	0
LR001 : Male mulia	25.8	Per day	462	11919.6	0

Total Amount (a+b+c)

23839.2

Total GST (a)

0

OVERHEAD CHARGES @ 7.5% (+)

1787.94

CONTRACTOR PROFIT @ 7.5% (+)

1922.0355

LABOUR CESS @ 1% (+)

275.491755

Grand Total

27824.667255

Say For Unit 1 (Grand Total/100)

278.24667255

Item 2

Earth Work (AR0115): Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

Filling foundation and plinth with sand well watered and rammed

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	71.94	7194	0
LR002 : Female mulia	12.36	Per day	462	5710.32	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	341.11	34111	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	40.25	4025	0

Total Amount (a+b+c)	51040.32				
Total GST (a)	0				
OVERHEAD CHARGES @ 7.5% (+)	3828.024				
CONTRACTOR PROFIT @ 7.5% (+)	4115.1258				
LABOUR CESS @ 1% (+)	589.834698				
Grand Total	59573.304498				
Say For Unit 1 (Grand Total/100)	595.73304498				

Item 3
Concrete (AR0303): Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
LR025 : Mason	0.18	Per day	562	101.16	0
LR002 : Female mulia	1.4	Per day	462	646.8	0
LR001 : Male mulia	2.5	Per day	462	1155	0
BRM340 : Cement	2.29	1 Qntl.	561	1284.69	231.2442
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	76.13	36.5424	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	995.25	955.44	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	30.732	70.37628	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	341.11	163.7328	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	341.11	327.4656	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	40.25	19.32	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	149.5	143.52	0

Total Amount (a+b+c)	4904.04708
Total GST (a)	231.2442
OVERHEAD CHARGES @ 7.5% (+)	385.146846
CONTRACTOR PROFIT @ 7.5% (+)	414.03285945
LABOUR CESS @ 1% (+)	59.3447098545
Grand Total	5993.8156953045
Say For Unit 1 (Grand Total/1)	5993.8156953045

Item 4

R.C.C. Work (AR0410c): Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc

Sub-Item of Work

R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	58374.79	1558.606893	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	1.26	1Mtr.	30.81	38.8206	0
LR008 : Sangi mulia	0.5	Per day	512	256	0
LR027 : Carpenter	0.5	Per day	562	281	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	245.856	6.5643552	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	245.856	1.50955584	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	0	0	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	0	0	0

Total Amount (a+b+c)	2142.50140404
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	160.687605303
CONTRACTOR PROFIT @ 7.5% (+)	172.73917570073
LABOUR CESS @ 1% (+)	24.759281850437
Grand Total	2500.6874668942

Say For Unit 1 (Grand Total/10)	250.06874668942
---------------------------------	-----------------

Item 5

R.C.C. Work (AR0410a): Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas up to 4.3m height

Sub-Item of Work
Centring & Shuttering for R.C.C. floor and roof slabs, landings, balconies, projecting sun shades and chajjas

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	5.6	1Mtr	51.87	290.472	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0452	1Cum.	58374.79	2638.540508	0
LR008 : Sangi mulia	2.75	Per day	512	1408	0
LR027 : Carpenter	2.75	Per day	562	1545.5	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.069	1Mtr	245.856	16.964064	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0452	1Cum.	245.856	11.1126912	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM084 : Sal bullahs 75mm. to 120mm. mean dia up to 5.5m. long.	0.069	1Mtr	0	0	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0452	1Cum.	0	0	0

Total Amount (a+b+c)	5910.5892632
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	443.29419474
CONTRACTOR PROFIT @ 7.5% (+)	476.5412593455
LABOUR CESS @ 1% (+)	68.304247172855
Grand Total	6898.7289644584
Say For Unit 1 (Grand Total/9)	766.52544049537

Item 6

R.C.C. Work (AR0409): Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position including cost of binding wire 18 to 20 gauge with cost of steel rod and as per drawing, design, and direction of Engineer-in-charge.

Sub-Item of Work

Supplying, fitting, and placing uncoated HYSD bar reinforcement including labor charges for cutting, bending, binding, and tying the grills and placing in position

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR001 : Male mulia	8	Per day	462	3696	0
LR046 : Blacksmith	3	Per day	612	1836	0
LR010 : Mate	0.44	Per day	512	225.28	0
BRM162 : Binding Wire.	8	1 Kg.	90.1	720.8	0
BRM341 : Steel	10.5	1 Qntl.	6183.17	64923.285	11686.1913

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	10.5	1 Qntl.	30.732	322.686	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM341 : Steel	10.5	1 Qntl.	0	0	0

Total Amount (a+b+c)

71724.051

Total GST (a)

11686.1913

OVERHEAD CHARGES @ 7.5% (+)

6255.7681725

CONTRACTOR PROFIT @ 7.5% (+)

6724.9507854375

LABOUR CESS @ 1% (+)

963.90961257938

Grand Total

97354.870870517

Say For Unit 1 (Grand Total/10)

9735.4870870517

Item 7

Flooring (AR0802ii): 2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips including punning incl. cost, conveyance & royalty of materials as per direction of Engineer-in-charge.

Sub-Item of Work

2.5 cm thick A.S. flooring in C.C (1:2:4) with 12 mm size HG Hand broken chips

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR001 : Male mulia	0.14	Per day	462	64.68	0
LR002 : Female mulia	0.22	Per day	462	101.64	0
LR044 : Mason	0.13	Per day	612	79.56	0

BRM340 : Cement	0.0858	1 Qntl.	561	48.1338	8.664084
BRM028 : Screened and washed sharp sand for mortar	0.012	1 Cum	76.13	0.91356	0
BRM057 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve)(Hand broken)	0.023	1 Cum.	1085.19	24.95937	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0858	1 Qntl.	30.732	2.6368056	0
BRM028 : Screened and washed sharp sand for mortar	0.012	1 Cum	341.11	4.09332	0
BRM057 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve)(Hand broken)	0.023	1 Cum.	341.11	7.84553	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	0.0858	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.012	1 Cum	40.25	0.483	0
BRM057 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve)(Hand broken)	0.023	1 Cum.	149.5	3.4385	0

Total Amount (a+b+c)	338.3838856
Total GST (a)	8.664084
OVERHEAD CHARGES @ 7.5% (+)	26.02859772
CONTRACTOR PROFIT @ 7.5% (+)	27.980742549
LABOUR CESS @ 1% (+)	4.01057309869
Grand Total	405.06788296769
Say For Unit 1 (Grand Total/1)	405.06788296769

Item 8

R.C.C. Work (AR0404Aa): Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty,taxes of all materials, labour and T&P required for the work etc. (including centring and shuttering) complete and as per direction of Engineer-in charge (RCC foundation, footing bases of column, mass concrete, pre-cast slabs etc.)

Sub-Item of Work

Reinforced cement concrete work of M-20 grade with 20mm & down grade size black hard crusher broken granite chips

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
Combine :: R.C.C. Work (AR0404A)					
PM096 : Generator 33KVA Generation of Electric Energy 50KVA	0.4	per hour	700	280	0
PM083 : Concrete Mixer 04/0.28 cum Concrete Mixing 2.5cum/hour	0.4	per hour	229.55	91.82	0
LR001 : Male mulia	1.3333	Per day	462	615.9846	0
LR025 : Mason	0.1	Per day	562	56.2	0
LR010 : Mate	0.0573	Per day	512	29.3376	0
BRM340 : Cement	3.4733	1 Qntl.	561	1948.5213	350.733834
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	76.13	34.2585	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	1418.67	510.7212	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	1382.29	746.4366	0
Combine :: R.C.C. Work (AR0410c)					
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	1Cum.	58374.79	233.79103395	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.189	1Mtr.	30.81	5.82309	0
LR008 : Sangi mulia	0.075	Per day	512	38.4	0
LR027 : Carpenter	0.075	Per day	562	42.15	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.4733	1 Qntl.	30.732	106.7414556	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	341.11	153.4995	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	341.11	122.7996	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	341.11	184.1994	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	1Cum.	245.856	0.98465328	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.000921	1Mtr.	245.856	0.226433376	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
------------	----------	------	------	--------	-----

BRM340 : Cement	3.4733	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	40.25	18.1125	0
BRM060 : Granite Stone broken chips 10mm. size (Minimum 65% by Wt. Passing through 9.5mm sieve & retained on 6.3mm sieve but whole should pass through 13.2mm sieve) (Crusher broken)	0.36	1 Cum.	149.5	53.82	0
BRM052 : Granite Stone broken chips 20mm. size (Minimum 65% by Wt. Passing through 19mm sieve & retained on 13.2mm sieve but whole should pass through 26.5mm sieve) (Crusher broken)	0.54	1 Cum.	149.5	80.73	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.004005	1Cum.	0	0	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.000921	1Mtr.	0	0	0

Total Amount (a+b+c)	5354.557466206
Total GST (a)	350.733834
OVERHEAD CHARGES @ 7.5% (+)	427.89684751545
CONTRACTOR PROFIT @ 7.5% (+)	459.98911107911
LABOUR CESS @ 1% (+)	65.931772588006
Grand Total	6659.1090313886
Say For Unit 1 (Grand Total/1)	6659.1090313886

Item 9
Painting (AR0901ci): Priming one coat with outer surface primer of approved quality oil-bound primer over plastering surfaces including cost conveyance, taxes of all materials, labor and T&P required for the work complete as per direction of the Engineer-in-charge.
Sub-Item of Work First Floor

a) Specific Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM252 : Wall cement primer (I.S.I.) Oil bound	0.7812	1 Ltr	125.5	98.0406	0
LR048 : Painter/ Polisher	0.525	Per day	612	321.3	0
LR001 : Male mulia	0.525	Per day	462	242.55	0

b) Carriage Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM252 : Wall cement primer (I.S.I.) Oil bound	0.7812	1 Ltr	0.30732	0.240078384	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM252 : Wall cement primer (I.S.I.) Oil bound	0.7812	1 Ltr	0	0	0

Total Amount (a+b+c)	662.130678384
Total GST (a)	0

OVERHEAD CHARGES @ 7.5% (+)	49.6598008788
CONTRACTOR PROFIT @ 7.5% (+)	53.38428594471
LABOUR CESS @ 1% (+)	7.6517476520751
Grand Total	772.82651285958
Say For Unit 1 (Grand Total/9.3)	83.099625038665

Item 10

R.C.C. Work (AR0410e): Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. Lintels Data for 7.8 sqm

Sub-Item of Work
Third floor

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM094 : Non-sal bullahs 125mm. mean dia of any length.	3.6288	1Mtr.	41.81	151.720128	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0713664	1Cum.	58374.79	4165.998613056	0
LR008 : Sangi mulia	2.16	Per day	512	1105.92	0
LR027 : Carpenter	2.16	Per day	562	1213.92	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM094 : Non-sal bullahs 125mm. mean dia of any length.	0.0476928	1Mtr.	245.856	11.7255610368	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0713664	1Cum.	245.856	17.5458576384	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM094 : Non-sal bullahs 125mm. mean dia of any length.	0.0476928	1Mtr.	0	0	0
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0713664	1Cum.	0	0	0

Total Amount (a+b+c)	6666.8301597312
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	500.01226197984
CONTRACTOR PROFIT @ 7.5% (+)	537.51318162833
LABOUR CESS @ 1% (+)	77.043556033394
Grand Total	7781.3991593728
Say For Unit 1 (Grand Total/7.8)	997.61527684266

Item 11

Painting (AR0918Ai): Finishing wall one coat with weather coat including all costs of labour, Paint, Primer and Brushes required for the work etc. complete and as per direction of Engineer-in-charge.

Sub-Item of Work

Finishing wall one coat with weather coat

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	0.75	1 Ltr	194.79	146.0925	0
LR001 : Male mulia	0.43	Per day	462	198.66	0
LR048 : Painter/ Polisher	0.36	Per day	612	220.32	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	0.75	1 Ltr	0.30732	0.23049	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM255 : Weather Coat (I.S.I.)	0.75	1 Ltr	0	0	0

Total Amount (a+b+c)	565.30299
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	42.39772425
CONTRACTOR PROFIT @ 7.5% (+)	45.57755356875
LABOUR CESS @ 1% (+)	6.5327826781875
Grand Total	659.81105049694
Say For Unit 1 (Grand Total/10)	65.981105049694

ARABINDA BEHERA
JE
Nabarangpur Block

ASHISH KUMAR PRADHAN
AEE
Nabarangpur Block

SUNIL KHORA
BDO
Nabarangpur Block