

Analysis

**OD/348/3322/116584/394900/00126399 : CONSTRUCTION OF GUARD WALL AT BADA
GADIA
Block : Basudevpur, Gram Panchayat : Artuna
Created By: Tanmita Kar**

Item 1

Earth Work (AR0102aa): Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge

Sub-Item of Work

Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	25.8	Per day	472	12177.6	0
LR001 : Male mulia	25.8	Per day	472	12177.6	0

Total Amount (a+b+c)

24355.2

Total GST (a)

0

OVERHEAD CHARGES @ 7.5% (+)

1826.64

CONTRACTOR PROFIT @ 7.5% (+)

1963.638

LABOUR CESS @ 1% (+)

281.45478

Grand Total

28426.93278

Say For Unit 1 (Grand Total/100)

284.2693278

Item 2

Earth Work (AR0115): Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

Filling foundation and plinth with sand well watered and rammed

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	65.7	6570	0
LR002 : Female mulia	12.36	Per day	472	5833.92	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	1229.91	122991	0

c) Royalty Rate Details					
Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	110.25	11025	0

Total Amount (a+b+c)	146419.92				
Total GST (a)	0				
OVERHEAD CHARGES @ 7.5% (+)	10981.494				
CONTRACTOR PROFIT @ 7.5% (+)	11805.10605				
LABOUR CESS @ 1% (+)	1692.0652005				
Grand Total	170898.5852505				
Say For Unit 1 (Grand Total/100)	1708.985852505				

Item 3

Concrete (AR0303): Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR025 : Mason	0.18	Per day	572	102.96	0
LR002 : Female mulia	1.4	Per day	472	660.8	0
LR001 : Male mulia	2.5	Per day	472	1180	0
BRM340 : Cement	2.29	1 Qntl.	544.08	1245.9432	224.269776
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	68.45	32.856	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	995.25	955.44	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	24.787	56.76223	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	1229.91	590.3568	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	953.91	915.7536	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	110.25	52.92	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	409.5	393.12	0

Total Amount (a+b+c)	6186.91183
Total GST (a)	224.269776
OVERHEAD CHARGES @ 7.5% (+)	480.83862045
CONTRACTOR PROFIT @ 7.5% (+)	516.90151698375
LABOUR CESS @ 1% (+)	74.089217434338
Grand Total	7483.0109608681
Say For Unit 1 (Grand Total/1)	7483.0109608681

Item 4

R.C.C. Work (AR0410c): Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc

Sub-Item of Work

R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc

a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	58374.79	1558.606893	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	1.26	1Mtr.	30.81	38.8206	0
LR008 : Sangi mulia	0.5	Per day	522	261	0
LR027 : Carpenter	0.5	Per day	572	286	0

b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	198.296	5.2945032	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	198.296	1.21753744	0

c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM104 : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	0	0	0
BRM092 : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	0	0	0

Total Amount (a+b+c)	2150.93953364
Total GST (a)	0
OVERHEAD CHARGES @ 7.5% (+)	161.320465023
CONTRACTOR PROFIT @ 7.5% (+)	173.41949989972
LABOUR CESS @ 1% (+)	24.856794985627

Grand Total	2510.5362935484
Say For Unit 1 (Grand Total/10)	251.05362935484

SAMIR KUMAR MANNA
JE
Basudevpur Block

Smrutyunjaya Tarai
AEE
Basudevpur Block

Tanmita Kar
BDO
Basudevpur Block