

## Analysis

**OD/364/3482/119961/430938/00079022 : Improvement of road with CC/Grade-II Metaling  
from OLD BALIMELA TO JOGIPUT under 5th SFC MV TAX Fund for the year 2024-25  
Block : Korukonda, Gram Panchayat : Chitapari-ii  
Created By:MalkangiriKorukondaBDO**

### Item 1

**Earth Work (AR0102aa):** Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge

Sub-Item of Work

**Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift**

#### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	25.8	Per day	472	12177.6	0
LR001 : Male mulia	25.8	Per day	472	12177.6	0

**Total Amount (a+b+c)**

24355.2

**Total GST (a)**

0

**LABOUR CESS @ 1% (+)**

243.552

**Grand Total**

24598.752

**Say For Unit 1 (Grand Total/100)**

245.98752

### Item 2

**Earth Work (AR0115):** Filling foundation and plinth with sand well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T & P required for the work etc. complete and as per direction of Engineer-in charge.

Sub-Item of Work

**Filling foundation and plinth with sand well watered and rammed**

#### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	71.94	7194	0
LR002 : Female mulia	12.36	Per day	472	5833.92	0

#### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
BRM029 : Sand for filling and road blinding	100	1 Cum	471.31	47131	0

#### c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
------------	----------	------	------	--------	-----

BRM029 : Sand for filling and road blinding	100	1 Cum	96.25	9625	0
---	-----	-------	-------	------	---

<b>Total Amount (a+b+c)</b>	69783.92
<b>Total GST (a)</b>	0
<b>LABOUR CESS @ 1% (+)</b>	697.8392
<b>Grand Total</b>	70481.7592
<b>Say For Unit 1 (Grand Total/100)</b>	704.817592

<b>Item 3</b>
<b>Concrete (AR0303):</b> Cement concrete (1:3:6) with 4 cm. hard granite(Crusher Broken) metal including laying in layers not exceeding 300 mm in depth, ramming, compacting to proper thickness, watering and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete and as per direction of Engineer-in charge.
Sub-Item of Work <b>Cement concrete (1:3:6) with 4 cm. Crusher Broken hard granite metal</b>

<b>a) Specific Rate Details</b>					
Particular	Quantity	Unit	Rate	Amount	GST
LR025 : Mason	0.18	Per day	572	102.96	0
LR002 : Female mulia	1.4	Per day	472	660.8	0
LR001 : Male mulia	2.5	Per day	472	1180	0
BRM340 : Cement	2.29	1 Qntl.	537.3	1230.417	221.47506
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	76.88	36.9024	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	995.25	955.44	0

<b>b) Carriage Rate Details</b>					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	30.732	70.37628	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	471.31	226.2288	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	406.21	389.9616	0

<b>c) Royalty Rate Details</b>					
Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	2.29	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.48	1 Cum	96.25	46.2	0
BRM044 : Granite Stone broken metal 40mm. size (Crusher broken)	0.96	1 Cum.	208.5	200.16	0

<b>Total Amount (a+b+c)</b>	5099.44608
<b>Total GST (a)</b>	221.47506
<b>LABOUR CESS @ 1% (+)</b>	53.2092114
<b>Grand Total</b>	5374.1303514

Say For Unit 1 (Grand Total/1)	5374.1303514
--------------------------------	--------------

**Item 4**

**Concrete (AR0307):** Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&P required for the work etc. complete as per specifaion and direction of Engineer-in charge.

Sub-Item of Work  
**Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum**

**a) Specific Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
LR002 : Female mulia	1.4	Per day	472	660.8	0
LR001 : Male mulia	3.2	Per day	472	1510.4	0
LR025 : Mason	0.68	Per day	572	388.96	0
BRM340 : Cement	3.23	1 Qntl.	537.3	1735.479	312.38622
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	76.88	34.596	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	1396.62	1256.958	0

**b) Carriage Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	30.732	99.26436	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	471.31	212.0895	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	406.21	365.589	0

**c) Royalty Rate Details**

Particular	Quantity	Unit	Rate	Amount	GST
BRM340 : Cement	3.23	1 Qntl.	0	0	0
BRM028 : Screened and washed sharp sand for mortar	0.45	1 Cum	96.25	43.3125	0
BRM056 : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	1 Cum.	208.5	187.65	0

<b>Total Amount (a+b+c)</b>	6495.09836
<b>Total GST (a)</b>	312.38622

<b>LABOUR CESS @ 1% (+)</b>	68.0748458
<b>Grand Total</b>	6875.5594258
<b>Say For Unit 1 (Grand Total/1)</b>	6875.5594258

### Item 5

**R.C.C. Work (AR0410c):** Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc

Sub-Item of Work

**R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc**

#### a) Specific Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	58374.79	1558.606893	0
<b>BRM092</b> : Non-sal bullahs 75mm. mean dia of any length.	1.26	1Mtr.	30.81	38.8206	0
<b>LR008</b> : Sangi mulia	0.5	Per day	522	261	0
<b>LR027</b> : Carpenter	0.5	Per day	572	286	0

#### b) Carriage Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	245.856	6.5643552	0
<b>BRM092</b> : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	245.856	1.50955584	0

#### c) Royalty Rate Details

Particular	Quantity	Unit	Rate	Amount	GST
<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.0267	1Cum.	0	0	0
<b>BRM092</b> : Non-sal bullahs 75mm. mean dia of any length.	0.00614	1Mtr.	0	0	0

<b>Total Amount (a+b+c)</b>	2152.50140404
<b>Total GST (a)</b>	0
<b>LABOUR CESS @ 1% (+)</b>	21.5250140404
<b>Grand Total</b>	2174.0264180804
<b>Say For Unit 1 (Grand Total/10)</b>	217.40264180804

### Item 6

**Earth Work (AR0114):** Filling in foundation and plinth with excavated materials in ordinary soil including watering and ramming as directed by the Engineer-in-charge.

Sub-Item of Work  
**Filling of foundation with escalated earth**

**a) Specific Rate Details**

<b>Particular</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate</b>	<b>Amount</b>	<b>GST</b>
LR002 : Female mulia	10.6666	Per day	472	5034.6352	0
LR001 : Male mulia	10.6666	Per day	472	5034.6352	0
<b>Total Amount (a+b+c)</b>				10069.2704	
<b>Total GST (a)</b>					0
<b>LABOUR CESS @ 1% (+)</b>					100.692704
<b>Grand Total</b>				10169.963104	
<b>Say For Unit 1 (Grand Total/100)</b>				101.69963104	

**BAPUJI NAYAK**  
**JE**  
**Korukonda Block**

**SUKANTA KUMAR SWAIN**  
**AEE**  
**Korukonda Block**

**MalkangiriKorukondaBDO**  
**BDO**  
**Korukonda Block**