

ESTIMATION DPR							
<b>State</b>	Odisha	<b>District</b>	Ganjam	<b>Block</b>	Chatrapur	<b>Gram Panchayat</b>	Podapadar

<b>Work Code</b>	OD/354/3369/117686/412103/00014069 (Construction of CC/Paver road from nua sahi Raghunath temple to Reddy Street Humar)						
<b>Project Category</b>	Road						

<b>Financial Year</b>	2023-24	<b>Execution Level</b>	PS
<b>Executing Agency</b>	Panchayat Samiti, Chatrapur	<b>Proposal Date</b>	01-07-2023
<b>Date of Commencement</b>	-	<b>Date of Completion</b>	
<b>Scheme Name</b>	5th SFC Grant in Aid	<b>Scheme Component Name</b>	Maintenance and improvement of Road infrastructure
<b>Project Sub-Category</b>	CC Road	<b>Project Type</b>	New Work
<b>Name of Executant</b>			

### Administrative Approval Details

<b>Approval No.</b>	
---------------------	--

### Technical Sanction Details

<b>Technical Sanction No.</b>	OD/354/3369/117686/412103/00014069/TS
<b>Fund Sanction No.</b>	13745
<b>Fund Sanction Amount (in Rs.)</b>	200000

### ACTIVITY STATEMENT

S/N	ACTIVITY TAKEN	UNIT	QUANTITY	UNIT PRICE (IN RS.)	TOTAL (IN RS.)
-----	----------------	------	----------	---------------------	----------------

1	<p style="text-align: center;"><b>Earth Work (AR0102aa)</b>  <b>: Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift -</b>  Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	Cum	4.9695984	240.77592	1196.5596267905
2	<p style="text-align: center;"><b>R.C.C. Work (AR0410c)</b>  <b>: R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc -</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	Sqm	38.26117152	216.23489289764	8273.4003257654

3	<p style="text-align: center;"><b>Concrete (AR0307) :</b>  <b>Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum - Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete as per specificaion and direction of Engineer-in charge.</b></p>	Cum	7.686312192	7509.75866822	57722.349610517
---	--	-----	-------------	---------------	-----------------

4	<p><b>miscellaneous (ARM287) : Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC - Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.</b></p>	Sqm	152.175114	651.5586	99151.00423268
---	---	-----	------------	----------	----------------

5	<p align="center"><b>Earth Work (AR0115a) : Filling foundation and plinth with crusher dust well watered and rammed - Filling foundation and plinth with crusher dust well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T &amp; P required for the work etc. complete and as per direction of Engineer-in charge.</b></p>	Cum	16.962895872	727.152732	12334.616075956
<b>Total Amount (in Rs.): 178677.92987171</b>					

#### LABOUR STATEMENT

SI.No.	Activity Name	Qty/unit(B=Analysis Basic Qty/HeaderUnit)	Quantity(Measurement Qty)	Unit
1	<p><b>Earth Work (AR0102aa) : Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift -</b> Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge</p>	-	4.9695984	Cum
i	Un-Skilled	0.516	2.5643127744	-

2	<p><b>R.C.C. Work (AR0410c) : R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc -</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc</p>	-	38.26117152	Sqm
i	Semi-Skilled	0.05	1.913058576	-
ii	Skilled	0.05	1.913058576	-
3	<p><b>Concrete (AR0307) : Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum -</b> Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	7.686312192	Cum
i	Un-Skilled	4.6	35.3570360832	-
ii	Skilled	0.68	5.22669229056	-

4	<p><b>miscellaneous (ARM287) : Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC -</b></p> <p>Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.</p>	-	152.175114	Sqm
5	<p><b>Earth Work (AR0115a) : Filling foundation and plinth with crusher dust well watered and rammed -</b></p> <p>Filling foundation and plinth with crusher dust well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T &amp; P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	16.962895872	Cum
	i Un-Skilled	0.1236	2.0966139297792	-

SI.No.	Labour Type	Qty Unit	Rate	Amount
1	Un-Skilled	40.017962787379	462	18488.298807769
2	Semi-Skilled	1.913058576	512	979.485990912

3	Skilled	7.13975086656	562	4012.5399870067
				<b>Total: 23480.324785688</b>

## MATERIAL STATEMENT

SI.No.	Activity Name/Material	Qty/unit (B=Analysis Basic Qty/Header Unit)	Quantity (Meaurement Qty)	Unit
1	<b>Earth Work (AR0102aa) :.Earth work in hard soil or gravelly soil foundation &amp; plinth within 50m. Initial lead and 1.5m initial lift -</b> Earth work in hard soil or gravelly soil foundation & plinth within 50m. Initial lead and 1.5m initial lift including rough dressing and breaking clods to maximum 5cm to 7cm and laying in layers not exceeding 0.3m in depth and as per the direction of the Engineer-in-charge	-	<b>4.9695984</b>	Cum
2	<b>R.C.C. Work (AR0410c) :.R.C.C. foundation , plinth band and footings bases of columns mass concrete precast slabs etc -</b> Rigid and smooth centring and shuttering for R.C.C. works including false works and dismantling them after casting including cost of materials complete in ground floor R.C.C. foundation, plinth band and footings bases of columns mass concrete precast slabs, etc	-	<b>38.26117152</b>	Sqm
i)	<b>BRM104</b> : Non Sal wood scantling & plants(Tentera, Kasi, Gamhari, Kuruma)	0.00267	0.1021573279584	1Cum.
ii)	<b>BRM092</b> : Non-sal bullahs 75mm. mean dia of any length.	0.126	4.82090761152	1Mtr.

3	<p><b>Concrete (AR0307)</b>  <b>:.Cement concrete (1:2:4)with 12mm size hard broken granite chips per 1cum -</b>  Cement concrete work with (1:2:4) using 12mm size hard granite(crusher broken) chips including hoisting and laying in position compacting to specified design section and curing for proper period with cost conveyance, royalty, taxes of all materials, labour and T&amp;P required for the work etc. complete as per specifaion and direction of Engineer-in charge.</p>	-	<b>7.686312192</b>	Cum
i)	<b>BRM340</b> : Cement	3.23	24.82678838016	1 Qntl.
ii)	<b>BRM028</b> : Screened and washed sharp sand for mortar	0.45	3.4588404864	1 Cum
iii)	<b>BRM056</b> : Granite Stone broken chips 12mm. size (Minimum 65% by Wt. Passing through 13.2mm sieve & retained on 9.50mm sieve but whole should pass through 19mm sieve) (Crusher broken)	0.9	6.9176809728	1 Cum.

4	<p><b>miscellaneous(ARM28 7) :.Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC -</b></p> <p>Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items) and as directed by Engineer-in-Charge.</p>	-	152.175114	Sqm
i)	<p><b>BRM029</b> : Sand for filling and road blinding</p>	0.03	4.56525342	1 Cum
ii)	<p><b>BRMM287</b> : Supplying and fixing of 80mm thick cement concrete interlocking paver block of M-40 grade of approved make, design, colour and size made by Block making machine with proper compaction laid in required pattern etc. complete in all respect conforming to IRC SP-63:2018. (New miscellaneous items)</p>	1	152.175114	1 Sqm
5	<p><b>Earth Work (AR0115a) :.Filling foundation and plinth with crusher dust well watered and rammed -</b></p> <p>Filling foundation and plinth with crusher dust well watered and rammed including cost, conveyance, royalty, taxes of all materials, labours and T &amp; P required for the work etc. complete and as per direction of Engineer-in charge.</p>	-	16.962895872	Cum

i)	<b>BRM026</b> : Stone screened Dust passing through 2.36 mm sieve and retained on 0.075 mm sieve	1	16.962895872	1 Cum
----	--	---	--------------	-------

SI.No.	Material Name	Qty	Unit	Rate	Amount
1	<b>BRM104</b>	0.1021573279584	1Cum.	58573.086	5983.6699560376
2	<b>BRM092</b>	4.82090761152	1Mtr.	229.106	1104.4988592449
3	<b>BRM340</b>	24.82678838016	1 Qntl.	593.017	14722.707564837
4	<b>BRM028</b>	3.4588404864	1 Cum	667.74	2309.6061463887
5	<b>BRM056</b>	6.9176809728	1 Cum.	1802.83	12471.402788193
6	<b>BRM029</b>	4.56525342	1 Cum	664.37	3033.0174146454
7	<b>BRMM287</b>	152.175114	1 Sqm	608.4	92583.3393576
8	<b>BRM026</b>	16.962895872	1 Cum	519.6	8813.9206950912
<b>Total: 141022.16278204</b>					

#### ROYALTY STATEMENT

S/N	Material Name	Qty	Unit	Royalty Rate	Amount
1	<b>BRM028</b>	3.4588404864	1 Cum	774.25	2678.0072465952
2	<b>BRM056</b>	6.9176809728	1 Cum.	252.5	1746.714445632
3	<b>BRM029</b>	4.56525342	1 Cum	774.25	3534.647460435
4	<b>BRM026</b>	16.962895872	1 Cum	143.25	2429.934833664
<b>Total: 10389.303986326</b>					

#### ADDITION COMPONENT

SI.No.	Item Name	Amount (in Rs.)
1	Provision for Contingency @ 1%	Rs. 1786.7792987171
2	Display Citizen Board @ Rs. 1845	Rs. 1845
3	Any Other Lumpsum @ Rs. 17690	Rs. 17690
<b>Total Addition Component Amount (in Rs.): 21321.779298717</b>		

**Total Net Amount (in Rs.): 199999.70917043**